

# भारत सरकार Government of India विद्युत मंत्रालय Ministry of Power उत्तर क्षेत्रीय विद्युत समिति Northern Regional Power Committee

विषय: प्रचालन समन्वय उप-समिति की 238 वीं बैठक की कार्यसूची।

Subject: Agenda of the 238th OCC meeting.

प्रचालन समन्वय उप-समिति की 238<sup>वी</sup> बैठक का आयोजन दिनांक 17.12.2025 को 10:30 बजे से एनआरपीसी सचिवालय, कटवारिया सराय, नई दिल्ली में किया जायेगा। उक्त बैठक की कार्यसूची उत्तर क्षेत्रीय विद्युत् समिति की वेबसाइट <a href="https://nrpc.gov.in">https://nrpc.gov.in</a> पर उपलब्ध है।

कृपया बैठक में उपस्थित होने की स्विधा प्रदान करें।

The 238<sup>th</sup> meeting of the Operation Co-ordination sub-committee will be conducted through Physical Mode on 17.12.2025 from 10:30 Hrs at NRPC Secretariat, Katwaria Sarai, New Delhi. The agenda of this meeting has been uploaded on the NRPC web-site <a href="https://nrpc.gov.in">https://nrpc.gov.in</a>.

Kindly make it convenient to attend the meeting.

Digitally signed by Dharmendra Kumar Meena Date: 12-12-2025 19:54:46

(डी. के. मीना)

अधीक्षण अभियंता (प्रचालन)

सेवा में : प्रचालन समन्वय उप समिति के सभी सदस्य।

To : All Members of OCC

	OCC Members for FY 2025-26						
S. No	OCC Member	Category	E-mail				
1	NLDC	National Load Despatch Centre	nomination awaited (susha@grid-india.in)				
2	NRLDC	Northern Regional Load Despatch Centre	somara.lakra@grid-india.in				
3	CTUIL	Central Transmission Utility	sandeepk@powergrid.in				
4	PGCIL	Central Government owned Transmission Company	rtamc.nr1@powergrid.in rtamcjammu@powergrid.in cpcc.nr3@powergrid.in				
5	NTPC		RAMESHSINGH@NTPC.CO.IN				
6	BBMB		powerc@bbmb.nic.in				
7	THDC	Central Generating	bhagatsingh@thdc.co.in				
8	SJVN	Company	sivn.cso@sivn.nic.in				
9	NHPC	-	surendramishra@nhpc.nic.in				
10	NPCIL		df@npcil.co.in				
11	Delhi SLDC		gmsldc@delhisldc.org				
12	Haryana SLDC		cesocomml@hvpn.org.in				
13	Rajasthan SLDC	_	ce.ld@rvpn.co.in				
14	Uttar Pradesh SLDC	State Load Despatch	cepso@upsldc.org				
15	Uttarakhand SLDC	Centre	se sldc@ptcul.org				
16	Punjab SLDC	-	ce-sldc@pstcl.org				
17	Himachal Pradesh	_	cehpsldc@gmail.com				
17	SLDC		<u>cenpsiac@gmaii.com</u>				
18	DTL		bl.gujar@dtl.gov.in				
19	HVPNL		cetspkl@hvpn.org.in				
20	RRVPNL		ce.ppm@rvpn.co.in				
21	UPPTCL	State Transmission	smart.saxena@gmail.com				
22	PTCUL	Utility	ce oandmk@ptcul.org				
23	PSTCL		ce-tl@pstcl.org				
24	HPPTCL		gmprojects.tcl@hpmail.in				
25	IPGCL		ncsharma@ipgcl-ppcl.nic.in				
26	HPGCL		seom2.rgtpp@hpgcl.org.in				
27	RRVUNL	State Congrating	ce.ppmcit@rrvun.com				
28	UPRVUNL	State Generating Company	cgm.to@uprvunl.org				
29	UJVNL		gm engg ujvn@yahoo.co.in				
30	HPPCL	-	gm_generation@hppcl.in				
31	PSPCL	State Generating	ce-ppr@pspcl.in				
		Company & State owned Distribution Company					
32	DHBVN		nomination awaited (md@dhbvn.org.in)				
33	Ajmer Vidyut Vitran	State owned Distribution	nomination awaited				
	Nigam Ltd.	Company (alphabetical	(md.avvnl@rajasthan.gov.in)				
34	Purvanchal Vidyut Vitaran Nigam Ltd.	rotational basis/nominated by state govt.)	nomination awaited (mdpurvanchalvvnl@gmail.com )				
35	UPCL	90,00	cgmupcl@yahoo.com				
36	HPSEB	-	cesysophpsebl@gmail.com				
	525		<u>scayaopripacator giridii.com</u>				

37	Prayagraj Power Generation Co. Ltd.		sanjay.bhargava@tatapower.co <u>m</u>
38	Aravali Power Company Pvt. Ltd		amit.hooda01@apcpl.co.in
39	Apraave Energy Ltd.,		niraj.gupta@apraava.com
40	Talwandi Sabo Power Ltd.		arun.kumar@vedanta.co.in
41	Nabha Power Limited		<u>Durvesh.Yadav@larsentoubro.c</u> <u>om</u>
42	MEIL Anpara Energy Limited	IPP having more than 1000 MW installed	arun.tholia@meilanparapower.co <u>m</u>
43	Rosa Power Supply Company Ltd	capacity	Suvendu.Dey@relianceada.com
44	Lalitpur Power Generation Company Ltd		avinashkumar.ltp@lpgcl.com
45	MEJA Urja Nigam Ltd.		rsjuneja@ntpc.co.in
46	Adani Power Rajasthan Limited		manoj.taunk@adani.com
47	JSW Energy Ltd. (KWHEP)		roshan.zipta@jsw.in
48	Transition Cleantech Services Private Limited	IPP having less than 1000 MW installed capacity (alphabetical rotational basis)	nomination awaited (kswamidoss@evrenenergy.co m)
49	UT of J&K	From each of the Union Territories in the region,	sojpdd@gmail.com
50	UT of Ladakh	a representative nominated by the administration of the	cepdladakh@gmail.com
51	UT of Chandigarh	Union Territory concerned out of the entities engaged in generation/ transmission/ distribution of electricity in the Union Territory.	seelo-chd@nic.in
52	NVVN	Nodal Agency appointed by the Government of India for coordinating cross-border power transactions	ceonvvn@ntpc.co.in
53	Tata Power Delhi Distribution Limited	Private Distribution Company in region (alphabetical rotational basis)	nomination awaited (sandeep.k@tatapower- ddl.com)
54	Gurgaon Palwal Transmission Limited	Private transmission licensee (nominated by central govt.)	(samriddhi.gogoi@indigrid.com)
55	PTC India Limited	Electricity Trader (nominated by central govt.)	nomination awaited (bibhuti.prakash@ptcindia.com)
56	ReNew Power Private Limited	RE Generating Company	sumant@renew.com
57	NTPC Green Energy	having more than 1000	rajivgupta@ntpc.co.in

	Limited
58	Azure Power India Pvt. Limited
59	Avaada Energy Private Limited
60	Adani Green Energy Limited

MW installed capacity

sunil.gupta@azurepower.com
kishor.nair@avaada.com
chaitanya.sahoo@adani.com

CEA-GO-17-11/1/2023-NRPC

# Contents

A.1. Confirmation of Minutes	
A.2. Status of action taken on decisions of 237 <sup>th</sup> OCC meeting of NRPC7	
A.3. Review of Grid operations	
A.4. Maintenance Programme of Generating Units and Transmission Lines8	
A.5. Planning of Grid Operation8	
A.6. Follow-up of issues from previous OCC Meetings- Status update9	
A.7. NR Islanding scheme9	
A.8. Coal Supply Position of Thermal Plants in Northern Region10	
A.9. Periodic testing of generators and FACTS/HVDC Devices (Agenda by NRPC Sectt.)11	
A.10. Implementation of AUFLS scheme in accordance with the report of Task Force on Automatic under Frequency Load Shedding (AUFLS) (Agenda by NRPC Secretariat)13	
A.11. Monthly Review of LGBR for the next 11 months (Availability & Requirement) (Agenda by NRPC Secretariat)	
A.12. Deemed Availability for Planned Outages During Retrofitting of Electro-Mechanical relays including Busbar and LBB Relays (agenda by Powergrid NR-3)	
A.13. Delay In Outages (Agenda by BKTL)	
A.14. Replacement of Damaged 400 kV Jack Bus Sections at Mandola & Ballabgarh Substations un ADDCAP (Agenda by Powergrid NR-1)	de
A.15. Details of Captive Generation in NR Region (Agenda by NRPC Secretariat)19	
B.1. NR Grid Highlights for Nov 2025.	
B.2. Demand forecasting and resource adequacy related: CERC order dated 05.10.202522	
B.3. Database of transmission lines having terminal equipments rating lower than transmission line conductor capacity	
B.4. Winter preparedness measures 2025-26	
B.5. Insulator cleaning and replacement of damaged insulators/ porcelain insulator with polymer insulators	
B.6. Reactive power performance of thermal generators in Northern region32	
B.7. Severe Low voltages in J&K and N-1 violations	
B.8. Critical operation of Rajasthan Grid during upcoming winter season:35	
B.9. State-wise transmission constraints during high demand season of 2025 and SPS proposals 42	<u> </u>
B.10. Bypass of 400kV Dadri-Maharanibagh and 400kV Maharanibagh-Ballabgarh at 400kV Maharanibagh	
B.11. Ensuring availability of hydro generators for AGC support	
B.12. Mock testing of islanding scheme and simulation studies	
B.13. Self-audit related:	
B.14. Multiple element tripping events in Northern region in the month of November 2025: 48	}
<ul><li>B.15. Status of submission of DR/EL and tripping report of utilities for the month of November</li><li>2025: 49</li></ul>	

B.16.	Mock testing of System Protection Schemes (SPS) in Northern Region49
B.17.	Mock trial run and testing of black start facilities at generating stations in Northern Region
54	
B.18.	Revision of document for Reactive Power Management of Northern Region:55
B.19.	Revision of document for System Restoration Procedure Document of Northern Region:
55	
B.20.	Revision of document for System Protection Scheme Document of Northern Region: 56

खण्ड-कः उ.क्षे.वि.स. Part-A: NRPC

#### A.1. Confirmation of Minutes

237<sup>th</sup> OCC meeting was held on 17.11.2025. Minutes of the meeting were issued vide letter dt. 08.12.2025. No comments received till date.

## **Decision required from Forum:**

Forum may approve the minutes of 237<sup>th</sup> OCC meeting.

# A.2. Status of action taken on decisions of 237th OCC meeting of NRPC

A.2.1. Status of action taken on decisions of 237<sup>th</sup> OCC meeting is attached as **Annexure- A.I.** 

## A.3. Review of Grid operations

## A.3.1. Power Supply Position (Provisional) for November 2025

Anticipated Power Supply Position v/s Actual Power Supply Position (Provisional) of Northern Region during the month of November-2025 is as under:

		Energy (MU)			Peak (MW)		
State / UT	Req. / Avl.	Anticipate d	Actua I	% variatio n	Anticipate d	Actual	% variatio n
CHANDIGAR	(AvI)	110	106	-3.3%	350	218	-37.7%
Н	(Req	122	106	-12.8%	322	218	-32.3%
	(AvI)	2564	2252	-12.1%	4400	4486	2.0%
DELHI	(Req	2250	2253	0.1%	4400	4486	2.0%
	(AvI)	4760	4551	-4.4%	9983	8795	-11.9%
HARYANA	(Req	4527	4551	0.5%	8162	8795	7.8%
HIMACHAL	(Avl)	1126	1083	-3.8%	2131	2239	5.1%
PRADESH	(Req	1135	1084	-4.5%	2150	2239	4.1%
J&K and	(AvI)	1030	1786	73.4%	2490	3131	25.7%
LADAKH	(Req	1891	1786	-5.6%	3653	3131	-14.3%
	(Avl)	4510	4393	-2.6%	10610	9808	-7.6%
PUNJAB	(Req	4694	4394	-6.4%	8589	9808	14.2%
	(AvI)	8630	8939	3.6%	19890	17859	-10.2%
RAJASTHAN	(Req	10075	8939	-11.3%	17000	17859	5.1%
UTTAR	(AvI)	11100	9728	-12.4%	20700	19341	-6.6%
PRADESH	(Req	10950	9728	-11.2%	20700	19341	-6.6%

UTTARAKHA ND NORTHERN REGION	(AvI)	1185	1177	-0.7%	2225	2297	3.2%
	(Req	1200	1178	-1.8%	2250	2297	2.1%
	(AvI)	35015	34015	-2.9%	74000	63800	-13.8%
	(Req	36844	34019	-7.7%	64600	63800	-1.2%

As per above, negative / significant variation (≥5%) in Actual Power Supply Position(Provisional) vis-à-vis Anticipated figures is observed for the month of November-2025 in terms of Energy Requirement for Chandigarh, HP, UTs of J&K and Ladakh, Punjab, Rajasthan, UP, and Uttarakhand and in terms of Peak Demand similar variation is noted for Chandigarh, Haryana, UTs of J&K and Ladakh, Punjab, Rajasthan, UP, . These states/UTs are requested to submit reason for such variations so that the same can be deliberated in the meeting.

All SLDCs are requested to furnish provisional and revised power supply position in prescribed formats on NRPC website portal by 2<sup>nd</sup> and 15<sup>th</sup> day of the month respectively for the compliance of Central Electricity Authority (Furnishing of Statistics, Returns and Information) Regulations, 2007.

#### A.4. Maintenance Programme of Generating Units and Transmission Lines

# A.4.1. Maintenance Programme for Generating Units

The meeting on proposed maintenance programme for Generating Units for the month of January-2026 is scheduled on 15-December-2025 via Video Conferencing.

# A.4.2. Outage Programme for Transmission Elements

The meeting on proposed outage programme of Transmission elements for the month of January-2026 is scheduled on 15-December-2025 via Video conferencing.

#### A.5. Planning of Grid Operation

#### A.5.1. Anticipated Power Supply Position in Northern Region for December 2025

The Anticipated Power Supply Position in Northern Region for December 2025 is as under:

State / UT	Availability / Requirement	Revised Energy (MU)	Revised Peak (MW)	Date of revision
	Availability	120	350	
CHANDICADII	Requirement	173	341	No Revision
CHANDIGARH	Surplus / Shortfall	-53	9	submitted
	% Surplus / Shortfall	-30.6%	2.6%	

State / UT	Availability /	Revised Energy	Revised Peak	Date of revision
	Requirement Availability	(MU) 3110	(MW) 6810	
DELHI	Requirement	2766	6738	No Revision
DELHI	Surplus / Shortfall	344	72	submitted
	% Surplus / Shortfall	12.4%	1.1%	
	Availability	5580	9815	
HARYANA	Requirement	4927	9651	5-Dec-2025
	Surplus / Shortfall	653	164	
	% Surplus / Shortfall	13.3%	1.7%	
	Availability	1342	2380	
HIMACHAL	Requirement	1326	2400	
PRADESH	Surplus / Shortfall	16	-20	9-Dec-2025
	% Surplus / Shortfall	1.2%	-0.8%	
	Availability	1050	2460	
J&K and	Requirement	2349	3737	No Revision
LADAKH	Surplus / Shortfall	-1299	-1277	submitted
	% Surplus / Shortfall	-55.3%	-34.2%	
	Availability	4510	10670	
PUNJAB	Requirement	5511	10868	No Revision submitted
	Surplus / Shortfall	-1001	-198	Submitteu
	% Surplus / Shortfall	-18.2%	-1.8%	
	Availability	9200	19690	
RAJASTHAN	Requirement	12090	20746	No Revision submitted
	Surplus / Shortfall	-2890	-1056	Submitted
	% Surplus / Shortfall	-23.9%	-5.1%	
	Availability	15000	28230	
UTTAR	Requirement	11851	27641	No Revision
PRADESH	Surplus / Shortfall	3149	589	submitted
	% Surplus / Shortfall	26.6%	2.1%	
	Availability	1433	2600	
	Requirement	1449	2675	2 Dec 2005
UTTARAKHAND	Surplus / Shortfall	-16	-75	3-Dec-2025
	% Surplus / Shortfall	-1.1%	-2.8%	

State / UT	Availability / Requirement Availability	Revised Energy (MU) 41345	Revised Peak (MW) 78400	Date of revision
NORTHERN	Requirement	42442	80800	
REGION	Surplus / Shortfall	-1097	-2400	
	% Surplus / Shortfall	-2.6%	-3.0%	

SLDCs are requested to update the anticipated power supply position of their respective state / UT for the month of January-2026 and submit the measures proposed to be taken to bridge the gap between demand & availability, as well to dispose-off the surplus, if any, in the prescribed format.

## A.6. Follow-up of issues from previous OCC Meetings- Status update.

The updated status of agenda items is enclosed at **Annexure-A.II**.

All utilities are requested to update the status.

## A.7. NR Islanding scheme

Latest status of Islanding Scheme of NR is attached as Annexure-A.III.

Members may kindly deliberate.

#### A.8. Coal Supply Position of Thermal Plants in Northern Region

- A.8.1In 186<sup>th</sup> OCC meeting, it was agreed that coal stock position of generating stations in northern region may be reviewed in the OCC meetings on the monthly basis.
- A.8.2 Accordingly, coal stock position of generating stations in northern region during current month (till 08<sup>th</sup> December 2025) is as follows:

Station	Capacity (MW)	PLF % (prev. months)	Normative Stock Reqd. (Days)	Actual Stock (Days)
ANPARA C TPS	1200	0.60	15	9.9
ANPARA TPS	2630	0.75	15	19.5
BARKHERA TPS	90	0.31	24	43.1
DADRI (NCTPP)	1820	0.51	24	21.0
GH TPS (LEH.MOH.)	920	0.73	24	22.9
GOINDWAL SAHIB				
TPP	540	0.51	24	23.9
HARDUAGANJ TPS	1265	0.35	24	37.6
INDIRA GANDHI STPP	1500	0.46	24	38.1
KAWAI TPS	1320	0.69	24	24.6
KHAMBARKHERA TPS	90	0.31	24	45.0

Station	Capacity (MW)	PLF % (prev. months)	Normative Stock Reqd. (Days)	Actual Stock (Days)
KOTA TPS	1240	0.62	24	25.2
KUNDARKI TPS	90	0.31	24	38.3
LALITPUR TPS	1980	0.59	24	21.2
MAHATMA GANDHI TPS	1320	0.53	24	29.0
MAQSOODPUR TPS	90	0.26	23	47.0
MEJA STPP	1320	0.68	24	19.2
OBRA TPS	1094	0.48	24	12.8
PANIPAT TPS	710	0.47	24	42.7
PARICHHA TPS	1140	0.63	24	17.3
PRAYAGRAJ TPP	1980	0.65	23	27.5
RAJIV GANDHI TPS	1200	0.40	24	38.4
RAJPURA TPP	1400	0.86	24	24.0
RIHAND STPS	3000	0.80	15	23.4
ROPAR TPS	840	0.70	24	26.9
ROSA TPP Ph-I	1200	0.58	24	27.5
SINGRAULI STPS	2000	0.84	15	12.7
SURATGARH TPS	1500	0.43	24	18.4
TALWANDI SABO TPP	1980	0.59	24	18.8
TANDA TPS	1760	0.53	24	24.7
UNCHAHAR TPS	1550	0.64	24	23.2
UTRAULA TPS	90	0.28	24	40.7
YAMUNA NAGAR TPS	600	0.61	24	27.9
CHHABRA-I PH-1 TPP	500	0.59	24	26.6
KALISINDH TPS	1200	0.43	24	23.9
SURATGARH STPS	1320	0.60	24	23.8
CHHABRA-I PH-2 TPP	500	0.58	24	25.5
CHHABRA-II TPP	1320	0.62	24	30.6
JAWAHARPUR STPP	660	0.03	24	27.0

# A.9. Periodic testing of generators and FACTS/HVDC Devices (Agenda by NRPC Sectt.)

A.9.1. Regulation 40 (1) of CERC (IEGC) Regulations, 2023 stipulate that there shall be periodic tests, as required under clause (3) of this Regulation, carried out on power system elements for ascertaining the correctness of mathematical models used for simulation studies as well as ensuring desired performance during an event in the system.

A.9.2. The tests shall be performed once every five (5) years or whenever major retrofitting is done. If any adverse performance is observed during any grid event, then the tests shall be carried out even earlier, if advised by SLDC/RLDC/NLDC/RPC, as the case may be.

A.9.3. Further, Regulation 40(1)(b) stipulate that "All equipment owners shall submit a testing plan for the next year to the concerned RPC by 31st October to ensure proper coordination during testing as per the schedule. In case of any change in the schedule, the owners shall inform the concerned RPC in advance."

Extract of IEGC 2023 clause 40,

#### "40. PERIODIC TESTING

- (1) There shall be periodic tests, as required under clause (3) of this Regulation, carried out on power system elements for ascertaining the correctness of mathematical models used for simulation studies as well as ensuring desired performance during an event in the system.
- (2) General provisions
- (a) The owner of the power system element shall be responsible for carrying out tests as specified in these regulations and for submitting reports to NLDC, RLDCs, CEA and CTU for all elements and to STUs and SLDCs for intra-State elements.
- (b) All equipment owners shall submit a testing plan for the next year to the concerned RPC by 31st October to ensure proper coordination during testing as per the schedule. In case of any change in the schedule, the owners shall inform the concerned RPC in advance.
- (c) The tests shall be performed once every five (5) years or whenever major retrofitting is done. If any adverse performance is observed during any grid event, then the tests shall be carried out even earlier, if so advised by SLDC, RLDC, NLDC, or RPC, as the case may be.
- (d) The owners of the power system elements shall implement the recommendations, if any, suggested in the test reports in consultation with NLDC, RLDC, CEA, RPC and CTU.
- (3) Testing requirements

The following tests shall be carried out on the respective power system elements:

TABLE 9: TESTS REQUIRED FOR POWER SYSTEM ELEMENTS

Power System Elements	Tests	Applicability
Synchronous	(1) Real and Reactive Power Capability	Individual Unit
Generator	assessment.	of rating
	(2) Assessment of Reactive Power Control	100MW and
	Capability as per CEA Technical Standards	above for
	for Connectivity	Coal/lignite,
	(3) Model Validation and verification test for the	50MW and
	complete Generator and Excitation System	above gas
	model including PSS.	turbine and 25
	(4) Model Validation and verification of	MW and above
	Turbine/Governor and Load Control or Active	for Hydro.
	Power/ Frequency Control Functions.	***
	(5) Testing of Governor performance and	
	Automatic Generation Control.	
Non	(1) Real and Reactive Power Capability for	Applicable as
synchronous	Generator	per CEA
Generator	(2) Power Plant Controller Function Test	Technical
(Solar/Wind)	(3) Frequency Response Test	Standards for
	(4) Active Power Set Point change test.	Connectivity.
	(5) Reactive Power (Voltage / Power Factor / Q) Set Point change test	
HVDC/FACTS	(1) Reactive Power Controller (RPC) Capability	To all ISTS
Devices	for HVDC/FACTS	HVDC as well
	(2) Filter bank adequacy assessment based on	as Intra-State
	present grid condition, in consultation with	HVDC/FACTS
	NLDC.	as applicable
	(3) Validation of response by FACTS devices as per settings.	

- A.9.4. In 73 NRPC meeting, NRPC forum asked all Generators and HVDC/FACT owners to furnish the Testing schedule for 2024-25 and 2025-26 to NRPC/NRLDC at the earliest. However, the same is still pending.
- A.9.5. In 236<sup>th</sup> OCC meeting, MS NRPC asked Generators and HVDC/FACT owners to furnish Testing schedule for 2025-26 in the format attached at **Annexure-A.IV.a** to <u>seonrpc@nic.in</u>.
- A.9.6. In view of the above Generators and HVDC/FACT owners are requested to furnish Testing schedule for 2025-26 and 2026-27 in the format attached as **Annexure-A.IV.a** to <a href="mailto:seo-nrpc@nic.in">seo-nrpc@nic.in</a>.
- A.9.7. List of Generating station from which information is received is attached as **Annexure-A.IV.b** 
  - Utilities to update status.
- A.10. Implementation of AUFLS scheme in accordance with the report of Task Force on Automatic under Frequency Load Shedding (AUFLS) (Agenda by NRPC Secretariat)
- A.10.1. In line with the report of Task Force on Automatic under Frequency Load Shedding (AUFLS) and df/dt scheme, NPC Secretariat to communicate the Region wise relief quantum (based on Regional Peak Demand Met during the previous year) by 31<sup>st</sup> of May to RPCs for implementation in the next Financial Year (FY).

A.10.2. NPC Secretariat has communicated to RPC's that they have computed the quantum of load shedding in different stages of AUFLS based on the Peak Demand Met of the Region in the financial year (2024-25). The region wise Peak Demand Met considered by NPC Sectt. is as follows:

Reg	gion		NI	R	SR		WR		ER		NE	NER	
Pea Met	ak D t (MW)	emand	80	),548	68,0	094	72,556		29,299 3,678		78		
Sr Sta Frequen Demand Disconnect ion (%)				Quantum of Load shed in MW									
Р	AUFLS Set Points and Percentage Quantum of Relief		NR	SR	W	/R	ER	NER	All India Load shed				
1	Stag e 1	49.4 H	z	5.00%	Ó	3801. 7	3213.		24. 5	1382 .8	173. 5	11996. 55	
2	Stag e 2	49.2 H	z	6.00%	ó	4562. 04	. 3856. 7		09. 4	1659 .4	208. 3	14395. 86	
3	Stag e 3	49.0 H	z	7.00%	, O	5322. 4	4499.		94. 3	1935 .9	243. 03	16795. 17	
4	Stag e 4	48.8 H	z	7.00%	ó	5322. 4	4499.		94. 3	1935 .9	243. 03	16795. 17	
	Total (in MW)			19008 .5	3 16069 .5		122 4	6914 .3	867. 9	59982. 7			

- A.10.3. The quantum of load shedding as per Task Force in different stages of AUFLS region-wise is as follows:
- A.10.4. After the receipt of the allocated load shedding quantum of the Region from NPC, AUFLS relief quantum should be distributed among the State/UT in the region by the RPCs in consultation with the stakeholders.
- A.10.5. NRPC Sectt. has computed each State/UT Stage-wise AUFLS quantum for NR based upon the task force report and quantum of load shedding in different stages of AUFLS region-wise finalized by NPC. The details of which are mentioned in the table below:-

State/UT	Stage-1 49.4 Hz (5%)	Stage-2 49.2 Hz (6%)	Stage-3 49.0 Hz (7%)	Stage-4 48.8 Hz (7%)	Total	Currently implemente d relief as
	Stage-1 Relief	Stage-2 Relief	Stage-3 Relief	Stage-4 Relief	. Ottai	per 231st OCC
Chandigarh	17	21	24	24	86	Nil
Delhi	334	400	467	467	1668	1595
Haryana	586	704	821	821	2931	3177
Himachal						
Pradesh	101	122	142	142	507	1076

UT J&K &						
Ladhak	140	168	196	196	700	777
Punjab	645	773	902	902	3223	3012
Rajasthan	853	1024	1194	1194	4266	4066
Uttar						
Pradesh	1297	1557	1816	1816	6486	8537
Uttarakhand	127	152	177	177	633	865
Total	4100	4920	5740	5740	20499	23105

Note: Pumped storage hydro plants operating in pumping mode or ESS operating in charging mode shall be automatically disconnected before the first stage of UFR

- A.10.6. States/UT shall identify the load relief for each stage considering the Quantum of relief and their demand contribution considering the intra-day, seasonality etc. 10% additional relief would be finalised considering the demand growth of the year, planned and forced outages, UFR and breaker issues etc. SLDC would communicate feeder-wise, Stage-wise details etc. to RPC/RLDC.
- A.10.7. In 234<sup>th</sup> OCC meeting it was apprised that states like Chandigarh, Delhi, Punjab (In Stage 1&2), Rajasthan (In Stage 1& 2) need to plan load relief in comparison to actual load relief required (attached as **Annexure-A.V**). Further, as per the recommendation of task force, the planned relief should be 10% more than the actual estimated relief.
- A.10.8. In 237<sup>th</sup> OCC meeting forum asked Forum asked states to plan load relief as per the recommendations of Task Force.

Members may kindly deliberate.

- A.11. Monthly Review of LGBR for the next 11 months (Availability & Requirement)
  (Agenda by NRPC Secretariat)
- A.11.1. In 236<sup>th</sup> OCC meeting matter regarding monthly Review of LGBR for the next 11 months (Availability & Requirement) was discussed and it was agreed that NR States/UTs shall submit the data for the monthly Review of LGBR for the next 11 months including the break-up of sources through which demand is proposed to be met, such as ISGS, internal generation, bilateral arrangements, DAM/RTM transactions, or other contracts, shall also be provided.
- A.11.2. In 237<sup>th</sup> OCC meeting, OCC forum requested NR States/UT's to submit the data for monthly Review of LGBR for the next 11 months in the google sheet to be shared by NRPC Secretariat.
- A.11.3. Accordingly, NR States/UTs are requested to update the data for the monthly Review of LGBR for the next 11 months (Jan'26 to Nov'26) in the google sheet. Link to access the google sheet is mentioned below:

https://docs.google.com/spreadsheets/d/ 1LmYwSHcFCaRAniwHUlpoiWFwaFCmKnQjlPqFDvWYy1k/edit?usp=sharing CEA-GO-17-11/1/2023-NRPC

1/57660/2025

Members may kindly deliberate.

# A.12. Deemed Availability for Planned Outages During Retrofitting of Electro-Mechanical relays including Busbar and LBB Relays (agenda by Powergrid NR-3)

- A.12.1. Powergrid NR-3 has submitted that as per CEA regulations on Technical Standards for Construction of Electrical Plants and Electric Lines Regulations, 2022 (dated 27.12.2022, page 166, clause 48.(1).(b)) and regulation 2010 "All major protection relays shall be of numerical type and communication protocol shall be as per IS-61850." In line with these guidelines, the existing relays including Busbar and LBB relays must be replaced with modern numerical relays supporting IEC 61850 communication protocol.
- A.12.2. Accordingly, for compliance CEA Regulation, replacement of electromechanical Busbar and LBB relays has been undertaken. Retrofitting of LBB relays at Lucknow, Allahabad, Gorakhpur, Pithoragarh, and Sitarganj has been completed, while work at Mainpuri and Raebareli is pending. Busbar relay retrofitting at 400/220 kV Lucknow and 220/132 kV Sitarganj is complete, and work at other substations is either in progress or scheduled to start shortly
- A.12.3. Several POWERGRID substations commissioned over 20 years ago (before 2010) were equipped with electro-mechanical Busbar and LBB protection relays, such as those at 400/220 kV Lucknow, Gorakhpur, Prayagraj, Mainpuri, 220/132 kV Pithoragarh, 220 kV Raebareli, and 220/132 kV Sitarganj. These relays have limited settings, configurations, and features, including disturbance recording and event logging. They are now obsolete and no longer supported by the OEM. Therefore, upgrading them to the latest numerical IEDs is essential for system improvement also.
- A.12.4. The agenda was discussed in the meeting taken by MS, NRPC on 03.12.2025 wherein it was decided to consider the outages as regulatory requirement (beyond control of licensee/ forced majeure) for replacement of electromechanical relays to numerical relays for substations commissioned before 2010. However, POWERGRID was asked to put up agenda in OCC for decision of approx. time taken in replacement work.
- A.12.5. Retrofitting a single LBB relay requires an outage of approximately 15–20 hours for the respective element, while retrofitting Busbar relays typically requires 35–40 hours of outage for each individual element. As the work is being carried out in conventional substations (around 20 years old), several constraints are encountered:
  - Space Constraints: Limited panel space with congested wiring and inter-panel connections necessitates extensive dismantling and rewiring.
  - Panel Modifications: Cutting panels, installing new relays, rearranging existing relays, and performing Test Block and SEM work are critical and time-consuming tasks.
  - Scheme/Drawing Issues: Old or deteriorated drawings, and in some cases, unavailability of drawings, pose challenges.
  - RTU Constraints: Non-reporting of critical monitoring signals is observed, requiring troubleshooting and rectification after shutdown.

# **Timewise detail for LBB relays Retrofitting Activities:**

Activity	Estimated Hours
Isolation and Issuance of PTW	0.5 Hrs
CT Shorting & DC isolation after Shutdown	1 Hrs
Dismantling existing wiring & old LBB relay	2-3 Hrs
Panel Cutting and Installation of New LBB Relay	2-3 Hrs
Re-Wiring Termination as per approved Scheme	3-4 Hrs
Verification of new wiring as per approved scheme	0.5-1 Hrs
Configuration of Events & DRs and Integration with SCADA/NTAMC	1-2 Hrs.
LBB relay Testing as per controlled documents	2-3 Hrs
Signal verification with RTAMC/NTAMC	0.5-1 Hr
Result Review and Approvals	1-2 Hrs.
Rectification/Correction of reviewed observations	0.5-1Hr
Code Collection & Charging	1 Hr.
Total	15-20 Hrs.

# Time wise detail for Bus bar relays Retrofitting Activities:

Activity	Estimated Hours
Isolation and Issuance of PTW	0.5 Hrs
CT Shorting & DC isolation after Shutdown	2 Hrs
Dismantling existing wiring & old relays	7-8 Hrs
Panel Cutting and Installation of New Bus Bar PU A & PU B Relays	2-3 Hrs
Re-Wiring Termination as per approved Scheme	8-9 Hrs
CT TB Replacement Work	0.5 Hrs
Verification of new wiring as per approved scheme	1-2 Hrs
Configuration of Events & DRs and Integration with SCADA/NTAMC	1-2 Hr.

Bus Bar relay Testing as per controlled documents	4-5 Hrs
Signal verification with RTAMC/NTAMC	1-2 Hrs
Result Review and Approvals	1-2 Hrs.
Rectification/Correction of reviewed observations	2-3 Hrs
Code Collection & Charging	1 Hr.
Total	35-40 Hrs.

- A.12.6. POWERGRID has requested that in view of regulatory compliance, following time may be allowed for replacement:
  - **15–20 hours** for LBB relay retrofitting per element.
  - **35–40 hours** for Busbar relay retrofitting per element.

Members may kindly deliberate.

### A.13. Delay In Outages (Agenda by BKTL)

A.13.1. BKTL has submitted that recurring delays in outages at BKTL SPV were observed, primarily due to multiple operational challenges. These delays have adversely impacted the optimal utilization of the scheduled outage period by the Licensee. Contributing factors include issues at the other end, grid constraints, and extended process timelines. A detailed summary of these instances is provided at **Annexure-A.VI.** 

Members may kindly deliberate.

- A.14. Replacement of Damaged 400 kV Jack Bus Sections at Mandola & Ballabgarh Substations under ADDCAP (Agenda by Powergrid NR-1)
- A.14.1. Powergrid NR-1 has submitted that requirement for complete shutdown of 400 kV Bus-1 & Bus-2 at Mandola and Ballabgarh substations was placed earlier for carrying out the replacement of severely aged and damaged 400 kV jack bus sections. The matter was deliberated in earlier OCC meetings
  - At Mandola, shutdown was agreed with DTL consent & work was completed in 400KV Bus system.
  - At Ballabgarh, shutdown consent for complete 400 kV bus sections were not provided by BBMB/HVPNL. Subsequently, work of Bus section 3& 4 completed, and shutdown approved for Bus section 1& 2 in recent OCC & same will be taken up after consent of BBMB/HVPNL.
- A.14.2. The existing jack buses have completed over 30+ years of service
  - Ballabgarh commissioned in 1988
  - Mandola commissioned in 1990 and have deteriorated significantly, requiring urgent replacement to ensure safety, reliability, and operational continuity.
- A.14.3. Following submission for proposing in ADDCAP:

# 1. Severe deterioration of 400 kV jack bus sections:

The existing conductor/structures have reached the end of their operational life (>30 years), with visible weakening, corrosion, and safety concerns.

## 2. Urgent replacement essential for system reliability:

Any failure in bus conductors at these high-capacity substations can lead to widespread outages and system disturbances.

### 3. Unscheduled forced outage risk mitigation:

Proactive replacement avoids major grid contingencies and reduces high-impact failure possibilities.

## 4. Original system assets fully depreciated:

Since the assets have crossed their useful life, replacement is categorized under Additional Capitalization (AddCap) as per tariff regulations.

# 5. Work carried out under urgent operational requirement:

Replacement work was undertaken to maintain reliability and ensure compliance with safety norms.

#### A.14.4. Details of Cost Incurred

POWERGRID NR-I has completed the replacement of damaged jack bus sections at Mandola & Ballabgarh 400 kV 3& 4 and also proposed for Bus section 1&2.

The incurred cost includes:

- •Supply of 400 kV jack bus conductor & hardware
- Replacement of clamps, tension fittings & accessories
- Tower/gantry strengthening (if required)
- •Labour, T&P, shutdown coordination and safety measures
- Testing & commissioning activities

Total Cost Incurred under Add Cap:

Mandola Substation:- Rs 96,25,000/-

Ballabgarhss Substation:- Rs 95,00,000/-

Total Additional Capitalization for replacement of Jack bus Conductor at Mandola & Ballabgarh Substation :- Rs 1,91,25,000/-

#### A.14.5. Powergrid has requested for the following proposal:

- 1. Approve the cost incurred under Additional Capitalization (AddCap) for the replacement of the deteriorated jack bus sections at 400 kV Mandola & Ballabgarh Substations.
- 2. Acknowledge the criticality of timely execution considering the 30+ years of asset age and system safety requirements.
- 3. outages during complete bus shutdown may be considered deemed available, as the activity pertains to replacement of end-of-life equipment critical for reliable grid operation.

Members may kindly deliberate.

## A.15. Details of Captive Generation in NR Region (Agenda by NRPC Secretariat)

A.15.1. MoP has directed all RPCs (except NERPC) to contact the State Load Despatch Centers (SLDCs) in their respective region to get the details of Captive, Open Access & Rooftop Solar Generation of 500 kW and above at the earliest.

- A.15.2. A High Level Meeting under the chairmanship of Secretary MoP is scheduled to be convened on this matter on 16.12.2025.
- A.15.3. All the SLDCs are requested to send the requisite data as per format **Annexure-A.VII** (copy enclosed) to GM Division (<a href="mailto:gmcea@nic.in">gmcea@nic.in</a>) at the earliest with copy to NRPC (<a href="mailto:seo-nrpc@nic.in">seo-nrpc@nic.in</a>). Kindly ensure that Captive Generation 500KW and above should be reflected in the report.

Matter may be treated as most urgent.

SLDC's to submit the data before OCC meeting.

खण्ड-खः उ.क्षे.भा.प्रे.के. Part-B: NRLDC

## **B.1. NR Grid Highlights for Nov 2025**

## **Demand met and Consumption details of NR**

S.No.	Constituen ts	Max Demand met (in MW)	Date & Time of Max Demand met	All time Max. Demand	Date & Time of All time Max Demand met
1	Chandigarh	218	28-11-2025 07:00	482	18.06.24 at 15:28
2	Delhi	4486	28-11-2025 10:44	8656	19.06.24 at 15:06
4	Haryana	8626	28-11-2025 09:00	14662	31.07.24 at 14:30
3	H.P.	2239	26-11-2025 07:45	2273	17.01.25 at 09:00
5	J&K	3131	28-11-2025 08:00	3200	07.01.25 at 10:00
6	Punjab	9808	29-11-2025 10:45	16754	28.06.25 at 15:00
7	Rajasthan	17614	30-11-2025 09:00	19165	12.02.25 at 11:00
9	U.P.	19341	28-11-2025 18:18	31486	11.06.25 at 00:45
8	Uttarakhan d	2297	28-11-2025 07:00	2910	11.06.25 at 22:00

10	Northern Region	63755	28-11-2025 10:00	91234	19.06.24 at 14:37

S.No.	Constitue nts	Max Consumpti on (in MUs)	Date of Max Consumpti on	Average Demand met (in Mus)	All time Max consumpti on	Date of All time Max Consumpti on
1	Chandigar h	3.8	01-11-2025	3.55	9.3	12.06.2025
2	Delhi	82.9	01-11-2025	75.44	177.7	18.06.2024
4	Haryana	163.4	28-11-2025	151.84	293.4	30.07.2024
3	H.P.	37.8	26-11-2025	35.52	42.6	11.06.2025
5	J&K	65.2	28-11-2025	59.53	70.3	04.02.2025
6	Punjab	165.8	29-11-2025	147.52	366.8	21.07.2024
7	Rajasthan	338.3	29-11-2025	297.93	388.0	11.06.2025
9	U.P.	345.9	28-11-2025	323.06	658.7	17.06.2024
8	Uttarakhan d	42.17	28-11-2025	40.74	62.1	14.06.2024
10	Northern Region	1233.1	28-11-2025	1135.137	2022.9	12.06.2025


- In November'25, the Maximum energy consumption of Northern Region was **1233.1 MUs** on 28<sup>th</sup> November'25 and it was 1.4% lower than November'24 (1248 MUs on 09th Nov'24).
- In November'25, the Average energy consumption per day of Northern Region was **1135.14 MUs** and it was 2.5% lower than November'24 (1165 MUs/day)
- In November'25, the Maximum Demand met of Northern Region was 63755 MW on 28<sup>th</sup> November'25 @10:00 Hrs as compared to 61434 MW on 29<sup>th</sup> Nov'24 @10:43 Hrs.

# Comparison of Average Energy Consumption (MUs/Day) – November '24 vs November '25

क्षेत्र/राज्य	अक्टूबर- 2024	अक्टूबर - 2025	% अंतर
चंडीगढ़	3.6	3.5	-2.2%

दिल्ली	74.8	75.4	0.9%
हिमाचल प्रदेश	33.9	35.5	4.7%
हरियाणा	144.8	151.8	4.9%
जम्मू और कश्मीर	54.6	59.5	9.0%
पंजाब	143.6	147.5	2.7%
राजस्थान	320.2	297.9	-7.0%
<b>उत्तरा</b> खंड	39.8	40.8	2.5%
उत्तर प्रदेश	349.5	323.1	-7.6%
उत्तरी क्षेत्र	1164.7	1135.1	-2.5%

# **Energy Consumptions**




# Frequency profile

Month	Avg. Freq. (Hz)	Max. Freq. (Hz)	Min. Freq. (Hz)	<49.90 (% time)	49.90 – 50.05 (% time)	>50.0 5 (% time)
Nov'2 5	49.994	50.403 (28.11.25 at 06:02:20 hrs)	49.542 (01.11.25 at 18:14:40 hrs)	5.66	79.39	14.95
Nov'2 4	49.995	50.317 (02.11.24 at 11:04:20 hrs)	49.553 (27.11.24 at 17:18:50 hrs)	5.2	80.8	14.0



# Reservoir Level and Generation on Last Day of Month



Reservoir Leve month	(Low: - ve)		(High: +ve )			
Year	Bhakra	Pong	Rihand HPS	RSD	Tehri	Koteshwa r
2025	508	418	265	523	823	611
2024	501	415	264.235	497	825	606
Diff (in m)	6.7	3.5	0.6	26.3	-2.1	5.4

Detailed presentation on grid highlights of Nov'2025 will be shared by NRLDC in OCC meeting.

# B.2. Demand forecasting and resource adequacy related: CERC order dated 05.10.2025

Hon'ble CERC In the matter of Planning for safe, secure, and reliable integrated operation of the power system during critical periods arising on account of seasonal variations wherein the electricity demand increases rapidly by undertaking specific measures to mitigate the risks on the power system, under clause (h) of sub-section (1) of Section 79 of the Electricity Act, 2003 and the Regulation 31 of the Central Electricity Regulatory Commission (Indian Electricity Grid Code) Regulations, 2023 has issued suo-motto order 9/SM/2024 dated 07.10.2024.

Subsequently, a meeting was taken by Hon'ble CERC on 14.02.2025 with all NR SLDCs, NRLDC and NRPC to review the actions being taken at SLDC end on measures related to resource adequacy.

It is to be noted that CERC has also released "Report on Planning for safe, secure, and reliable integrated operation of the power system during critical periods arising on account of seasonal variations wherein the electricity demand increases rapidly by undertaking specific measures to mitigate the risks on the power system under Order dated 07.10.2024 in Suo-Moto Petition No. 9/SM/2024" on 29.04.2025.

With reference to the Clause 31(2) of Central Electricity Regulatory Commission-IEGC Regulations, 2023 and the Operating Procedure of NRLDC prepared in accordance with the same, each SLDC has to furnish the demand estimation for day ahead, week ahead, month ahead (with time block wise granularity) and demand estimation for year ahead (with hour granularity). The sub-clause 31(2) (h) of IEGC-2023 states the following timeline for the submission of demand estimate data to RLDC.

Type of Demand Estimation	Timeline
Daily	10:00 hours of previous day
Weekly	First working day of previous week
Monthly	Fifth day of previous month
Yearly	30th September of previous year

Status of Day Ahead Forecasting, week ahead, month-ahead and year-ahead submission status for Nov-2025 as per Clause 31(4) (a) & (b) of IEGC-2023 is shown below:

State/Entity	Day Ahead	Week Ahead	Month Ahead	Year-Ahead(2026-27)
Punjab	Punjab As per Format		As per Format	Only Demand
Haryana	Haryana As per Format but irregular		Not received	Not received
Delhi	Delhi As per Format		As per Format	As per Format
Rajasthan	Rajasthan As per Format		As per Format but irregular	As per Format
Uttar Pradesh	As per Format	As per Format	As per Format	As per Format
Uttarakhand	As per Format	As per Format	As per Format	Only Demand
Himachal Pradesh	As per Format	As per Format	As per Format	As per Format
J&K and Ladakh (UT)	As per Format	As per Format but irregular	Not received	Only Demand
Chandigarh (UT)	As per Format	Not received	Not received	Not received

In accordance with above, all SLDCs are requested to timely furnish the demand estimation data along with generation adequacy data as per the formats available at <a href="https://drive.google.com/drive/folders/1KWY4G9gTBLV5wTJkhGEleRptKP-QbhjL?">https://drive.google.com/drive/folders/1KWY4G9gTBLV5wTJkhGEleRptKP-QbhjL?</a>

<u>usp=drive\_link</u> to NRLDC through mail (nrldcmis@grid-india.in) and FTP as per above timeline.

All SLDCs need to take actions at their end for timely submission of demand forecasting and resource adequacy data on day-ahead, week-ahead, month ahead and year ahead basis.

Portal has been prepared for submission of data by states. The user credentials have been provided to all states of Northern region.

Further, NRLDC has also carried out month ahead resource adequacy analysis on regional basis for Jan 2026 as per data available at NRLDC through PRAS software. The results are attached as **Annexure-B.I**.


As per IEGC clause 31

#### Quote

(4) Adequacy of Resources (a) SLDCs shall estimate and ensure the adequacy of resources, identify generation reserves, demand response capacity and generation flexibility requirements with due regard to the resource adequacy framework as specified under Chapter 2 of these regulations.

#### Unquote

Accordingly, NRLDC is also regularly sending emails based on day ahead resource adequacy exercise being carried out at NRLDC end. In case of major shortfall seen for a state based on demand forecast and generation adequacy data submitted by state, NRLDC communicates the actions required from state side in real-time also. Some sample snapshots emailed to respective states are shown below for reference:



However, it is being observed that states are only submitting the generation availability and not the actual internal generation schedule. This leads to a situation wherein only surplus/shortage values are checked. This does not take into account the schedule changes in internal thermal generation which may be happening based on merit order to accommodate high solar generation during daytime.

During 237 OCC meeting, OCC forum discussed that:

 NRLDC representative stated that as per CERC RNOD issued on 23.10.2025, demand forecasting and resource adequacy aspect was one of the crucial area and there needs to be major improvement starting from the data submission part. Haryana SLDC was especially asked to regularly share the data as per the approved CERC timelines.

- Haryana SLDC representative stated that they have taken up the matter with concerned wing of Power purchase deptt. at senior level. Power purchase deptt. has agreed to share the data as per approved formats.
- Data on day ahead basis received from some of the states (as shown in table) is not as per NRLDC format. It was further mentioned that NRLDC has developed a code/program for automation of day-ahead resource adequacy. In case data is not received in formats circulated by NRLDC, it would not be possible to map/utilize the data submitted by states in the internal program being developed at NRLDC end.
- States should submit actual generation schedule and not generation availability as flat/constant value throughout the day.
- It was discussed that PRAS is open source tool and can be utilised at SLDC level, also similar to being used at NRLDC end. It was discussed that already one training program on resource adequacy and PRAS was done by NRLDC and another training program would be planned before next OCC meeting.
- Further, it was discussed that one representative from SLDC may visit NRLDC and develop code for each SLDC during one/two day interaction with concerned SLDC.

Accordingly, an online workshop on PRAS software is planned by NRLDC for all NR SLDCs before the OCC meeting.

Further, CERC vide has issued final order dated 05.10.2025 regarding 9/SM/2024. CERC has also issued Consolidated Record Notes of discussions held during the Workshop on addressing various challenges faced by the states in Operational Planning for safe, secure, and reliable integrated operation of the power system dated 23.10.2025. The meeting for Northern region was held on 11.08.2025. The RNOD mentions the discussions held in the meeting on various points such as:

- (i) Adequacy of workforce:
- (ii) Training and Certification of the SLDC staff:
- (iii) Backing down of intra-state thermal generating units:
- (iv) Demand estimation and Resource Adequacy data submission:
- (v) Alignment of the State Grid Code with IEGC 2023:
- (vi) Implementation of SAMAST:
- (vii) Fee and Charges Regulations for SLDCs:

During 237 OCC meeting, MS NRPC stated that all concerned SLDCs may take necessary actions as discussed in previous OCC meetings also. It was mentioned that special attention may be given by SLDCs on demand estimation and Resource Adequacy data submission & ensuring adequate manpower in SLDCs.

It was suggested that as per IEGC clauses, SLDCs also carry out day-ahead, week-ahead and month ahead resource adequacy exercise and share their results with NRLDC. Further, all may take note of the recent CERC order dated 05.10.2025. All concerned SLDCs were asked to submit the actions taken at their end after the workshop organized by CERC.

Further, NRLDC MIS team has also mailed to all NR SLDCs to submit actions taken on various action points arising from CERC's observations, along with the current status on each item. To facilitate uniform data submission, a format has been prepared and enclosed as Annexure B.II. Response from SLDC side is still awaited.

Members may please discuss.

# B.3. Database of transmission lines having terminal equipments rating lower than transmission line conductor capacity

For conducting studies for assessment of inter control-area transfer capability or any other related simulation studies, thermal ratings of lines as specified in CEA's Manual on Transmission Planning Criteria 2023 are being considered as safe capacity limit of lines based on anticipated ambient temperature.

However, it is being observed in number of cases, such as in RVPN control area that the rating of terminal equipment is lower than thermal capacity of transmission line. This is leading to under-utilisation of line capacity due to limited switchgear rating and even leading to constraints in RE evacuation from Western Rajasthan RE complex.

Some of the lines in RVPN control area wherein this issue was observed are listed below:

- 400kV Bhadla-Bikaner D/C
- 400kV Jaisalmer-Kankani S/C
- 400kV Akal-Kankani S/C
- 400kV Akal-Jaisalmer S/C
- 400kV Suratgarh SCTPS-Babai D/C.

For these lines, thermal capacity is 1700MVA for design @ 75deg & 2180MVA for design @85deg. However, equipment rating is only 2kA which translates to 1.732\*400\*2= 1385MVA only, thus limiting line power transfer capacity to 1385MVA only.

Similar issues were earlier observed at **400kV Mahendragarh**, **Dhanonda and Nawada** substation in HVPN control area.

Further as per information available with NRLDC in case of **Vishnuprayag**, terminal equipment of only 1kA has been installed whereas the line is having twin moose conductor. Therefore the conductor can safely carry around 890MW of power, but due to terminal equipment rating issue, the line can only be loaded upto 400\*1.732\*1 = 693MVA only thereby reducing line capacity in difficult hilly terrain.

Similar terminal equipment rating issues were also observed in **400kV lines from NJPC and Rampur** wherein the lines such as 400kV NJPC-Panchkula D/C (further LILOed) and 400kV Rampura-Nallagarh sections of lines have equipment rating is only 2kA which translates to 1.732\*400\*2= 1385MVA only whereas transmission line has triple snowbird conductor.

The issue of lower line equipment rating has also been discussed in the past in 2018 in NRPC-OCC level wherein NPC had asked RPCs to furnish such details. It was requested that the terminal equipment ratings of STUs' and other transmission licensees' transmission lines in region, may be compiled and furnished to Grid-India with a copy to NPC Division, CEA on priority basis.

Subsequently, the agenda was discussed in number of OCC meetings and transmission utilities were asked to submit the data.

As per the data available at NRLDC, following are few transmission lines in Northern region having terminal equipments of lower capacity than conductor capacity:

Name of Transmission line	Line lengt h (km)	Owner	Conduct or Type	Conduct or Rating @45de g for 75deg design	Switchg ear rating End-1 (MVA)	Switchg ear rating End-2 (MVA)
400kV Bhadla-Bikaner D/C	189	RRVPNL	Quad Moose	1701	1386	1386
400kV Jaisalmer-Kankani S/C	177	RRVPNL	Quad Moose	1701	1386	1386
400kV Akal-Kankani S/C	223	RRVPNL	Quad Moose	1701	1386	1386
400kV Akal-Jaisalmer S/C	61	RRVPNL	Quad Moose	1701	1386	1386
400kV Suratgarh SCTPS-Babai D/C	245	RRVPNL	Quad Moose	1701	1386	1386
400kV Mahendragarh-Dhanonda D/C	5	ATIL	Quad Moose	1701	1386	1386
400kV Gr. Noida-Nawada D/C	30	POWERG RID	Quad Bersimi s	1978	1386	1386
400kV Vishnuprayag- Muzaffarnagar S/C	280	UPPTCL	Twin Moose	850	693	NA
400kV Vishnuprayag- Alakhnanda D/C	109	UPPTCL	Twin Moose	850	693	NA
400kV Rampur-Nallagarh D/C	128	POWERG RID	Triple Snowbir d	1275/ 1625*	1386	1386
400kV Jhakri-Gumma D/C	55	POWERG RID	Triple Snowbir d	1275/ 1625*	1386	NA
400kV Gumma-Panchkula D/C	112	POWERG	Triple	1275/	NA	1386

		RID	Snowbir d	1625*		
400kV Jhakri-Rampur D/C	21	POWERG RID	Triple Snowbir d	1275/ 1625*	1386	1386

<sup>\*</sup>Considering ambient temp of 40deg (lower in Hilly areas)

#### During 237 OCC meeting,

- MS NRPC stated that the lines listed above from NRLDC side are based on operational experience and accordingly concerned transmission licensees may strongly take up for upgradation of terminal equipments. It was also mentioned that line for which loading restriction has not been observed till date, their terminal equipment upgradation may be taken up subsequently.
- POWERGRID NR-2 representative stated that they are ready for switchgear upgradation but SJVNL has expressed inability to upgrade switchgear at their end due to GIS substation.
- HVPNL representative stated that terminal equipment at their substations such as Nawada, Dhanonda is being planned and likely to be completed before summer 2026.


Given the issues arising due to limited switchgear rating in lines which have higher thermal capacity, OCC forum:

- Advised all utilities to furnish the details of lines having terminal equipments of lower capacity to Grid-India /CTUIL/NRPC for consideration in future studies and planning of actions well in advance.
- Asked to plan for uprating switchgear ratings in existing lines to avoid issues in RE evacuation/ facilitating shutdowns may be studied by concerned transmission line and bay equipment owners.
- Asked for written reply through email/letter may be submitted by the concerned transmission licensees to NRPC/NRLDC.

Reply from utility side as agreed in previous OCC meeting is pending. Concerned transmission utilities and SLDCs may provide update. Members may please discuss.

#### **B.4. Winter preparedness measures 2025-26**

Winter in Northern region has started and shall continue till February end, and the challenges faced during these months are well known to all the utilities. During winter, demand of NR states except Rajasthan and hilly states is on the lower side. With decreasing temperatures and festivals, onset of winter also brings some severe challenges to NR grid operators. High ramp rate in demand during morning peak and evening peak is being observed which is likely to get further steeper.



Based on the detailed discussion held in last OCC meeting, following actions were suggested:

To carry out tap change exercise at 220kV and below voltage level. NRLDC had also reviewed tap position of 400/220kV Abdullapur, 765/400kV Mainpuri and 220/132kV Chandigarh (PG) substation. Further, study based on voltage profile of 400/220kV substations in NR for the month of Nov 2025 have been done and following tap changes are proposed:

#### Increase by 2 steps

- 400/220kV Amritsar(PG)
- 400/220kV Bhiwani(PG)
- 400/220kV Sambha(PG)
- 400/220kV Sonepat(PG)

#### Increase by 1 step

- 400/220kV Panchkula(PG)
- 400/220kV Bhiwani(PG)
- > 400/220kV Nakodar(PSTCL)

#### Decrease by 2 steps

- 400/220kV Allahabad(PG)
- > 400/220kV Hamirpur(PG)
- 400/220kV Panipat(BBMB)
- > 400/220kV Deepalpur (Indigrid)
- 400/220kV Gr. Noida(UP)
- > 400/220kV Lucknow(UP)

#### Decrease by 1 step

- ➤ 400/220kV Jalandhar(PG)
- 400/220kV Kaithal(PG)
- ➤ 400/220kV Bareilly(UP)
- > 400/220kV Unnao(UP)


 To ensure that all over flux setting of transformers and overvoltage settings of transmission lines are as per approved protection philosophy of NRPC. (HVPNL, PSTCL (partial implementation), NTPC, ADANI, Uttarakhand, J&K are yet to confirm the implementation of revised overvoltage settings (latest PSC deliberations)

- It iss requested that any planned commissioning of bus reactors may please be expedited.
- OCC expressed concern on the lack of progress of DTL reactors and asked them to expedite their works.
- Utilities to submit feedback on NRLDC reactive power document including for line reactors which can be used as bus reactors as per requirement.
- Utilities to ensure maximum availability of bus reactors and line reactors including provision of using line reactors as bus reactors in case of opening of lines on high voltage


Regarding synchronous condenser mode of operation in 237 OCC meeting it was discussed that.

- ➤ NRLDC representative requested THDC, BBMB and Punjab SLDC to confirm the availability of their machines for synchronous condenser support.
- ➤ THDC representative confirmed the availability of both Tehri Hydro Power Plant and Tehri Pumped Storage Plant generating units for synchronous condenser mode of operation. It was also confirmed that machines from both can be operated in synchronous condenser mode of operation simultaneously.
- ➤ BBMB representative confirmed through email regarding availability of Pong Hydroplant for synchronous condenser mode of operation.
- ➤ Punjab SLDC confirmed availability of RSD Unit-3 for synchronous condenser mode of operation, as per grid requirement. It was mentioned that RSD is taking measures for including other units also under synchronous condenser mode of operation and one more unit is likely to be available starting from next winter season.
- ➤ NHPC representative stated that Chamera-II HEP is having ability to run as synchronous condenser mode of operation. Mock testing would be planned shortly in coordination with concerned HEP.
- ➤ MS NRPC and CGM NRLDC stated that as now incentive is also being provided for reactive power support as per IEGC 2023, more hydro generators should come up for synchronous condenser mode of operation which would also help to control grid voltages.
- OCC forum asked NRLDC and all concerned hydro stations to carry out mock testing in synchronous condenser mode of operation at the earliest.

Tehri PSP tested for synchronous condenser mode of operation on 19.11.2025:



Tehri HPP tested for synchronous condenser mode of operation on 20.11.2025:



OCC members may provide details regarding actions taken at their end as agreed in 237 OCC meeting.

# B.5. Insulator cleaning and replacement of damaged insulators/ porcelain insulator with polymer insulators

The importance of carrying out insulator cleaning and replacement of damaged insulators was discussed in past OCC meetings and recently in 56 TCC and 81 NRPC meetings held on 30<sup>th</sup> and 31<sup>st</sup> Oct 2025. Northern Regional power transmission lines are exposed to high pollution levels along their routes. Such pollution levels with the onset of the winter season, lead to the frequent tripping and finally to breakdown and long outages of the transmission lines. These outages make the grid weak, thereby endangering the grid reliability and security.

Therefore, in order to avoid/mitigate tripping of lines during foggy (smog) weather in winter season, preventive actions like cleaning/washing of insulators, replacement of conventional insulators with polymer insulators have been recommended and are being taken every year.

This being a regular activity, all the transmission licensees in the Northern Region are being requested in monthly OCC and NRPC meetings to update line wise data for insulator replacement and cleaning in the format attached as **Annexure-B.III**. NRLDC

has already requested vide letter dated 22.09.2025 all transmission utilities to furnish the utility-wise latest status of the replacement of porcelain insulators with polymer insulators so that crucial lines for which such works are pending may be identified & prioritized. Further, the same has also been requested through emails dated 24.11.2025, 01.12.2025 & 04.12.2025. Updated list received from SLDC-UK & Adani-APL.

These tripping were also discussed in past OCC and protection subcommittee meetings, wherein actions being taken at utility end were also discussed. All concerned transmission licensees are requested to ensure:

- Priority wise cleaning & replacement is carried out. Priority to be given to the lines that have historical record of tripping during foggy weather.
- Progress on cleaning replacement of porcelain insulator with polymer insulator to be monitored and latest status may be furnished to NRPC/NRLDC. NRLDC will also try and prioritize shutdowns for crucial lines having past instances of tripping during foggy weather.
- Examination of Disturbance record/Event log data including analysis of any issues related to auto-reclosure operation (details also to be shared with NRLDC)
- Adequate manpower in control room during night shift of winter (vigilant and alert)

Utilities are requested to prepare plan for measures to be taken by them for carrying out pre-winter maintenance activities. Members may please discuss.

# **B.6.** Reactive power performance of thermal generators in Northern region

During winter season, demand of Northern region is low and high voltages are a common phenomenon predominantly in Punjab, Haryana and Delhi area. Even after several actions being taken by control centers, it is seen that there is persistent high voltage in Northern region. The reactive power absorption by generators becomes an important resource that helps in managing high voltages in the grid. However, even after continuous follow up in OCC meetings, it is seen that MVAR data telemetry is poor/ inaccurate from most of the generating stations. For some of the generators it is seen that there is inadequate reactive power absorption based on their capability curve especially during night hours. The performance of generators in absorption of reactive power for Dec-2024-Jan2025 is shown below:

S.No.	∖tati∩n	Unit No.	Capacity	Geographica I location		Absorption (+)	above (in KV)
1	Dadri	1	490		-147 to 294	-160 to 80	410
	NTPC	2	490		-147 to	-150 to 60	408

					294		
		1	200			) -15 to 5	397
		2	200	1	-60 to 120		404
		3	200	1	-60 to 120		402
	Circ and a vill	4	200		-60 to 120	) -15 to 5	400
2	Singrauli	5	200	UP	-60 to 120	-20 to 10	400
	NTPC	6	500		-150 t	<sup>0</sup> 0 to 60	405
		7	500			<sup>0</sup> 0 to 50	404
		1	500		-	<sup>0</sup> -50 to 50	398
	Rihand	2	500			<sup>0</sup> -60 to 30	397
3	NTPC	3	500	-UP		<sup>0</sup> -100 to 0	394
		4	500			<sup>0</sup> -110 to 0	394
4	, Kalisindh	1	600	Deigether		<sup>0</sup> -100 to 150	-
4	RS	2	600	Rajasthan		<sup>0</sup> -130 to 50	-
Г	Anpara C	1	600		<del> </del>	<sup>0</sup> -150 to 50	770
5	UP	2	600	UP	-180 t	0	770
		1	660		-198 t	<sup>0</sup> -210 to 0	410
6	Talwandi Saboo PB	2	660	Punjab	-198 t 396	<sup>0</sup> -210 to 0	408
		3	660		-198 t 396	0_	-
_	Kannai DC	1	660	Dais attaca	-198 t 396	<sup>0</sup> -80 to 50	404
7	Kawai RS	2	660	Rajasthan		<sup>0</sup> -90 to 50	404
		1	500		1	<sup>0</sup> -110 to 60	412
8	IGSTPP Jhajjar	2	500	Haryana	-150 t 300	<sup>0</sup> -110 to 120	415
		3	500		-150 t 300	0_	_
0	Rajpura	1	700	Dunich		<sup>0</sup> -210 to 70	405
9	(NPL)	2	700	-Punjab	-210 t 420	<sup>0</sup> -210 to 80	405
10	MCTDS	1	660	Hanyana	-198 t 396	<sup>0</sup> -130 to 40	404
10	MGTPS	2	660	Haryana	-198 t 396	<sup>0</sup> -130 to 70	405
11	Bawana	1	216	Delhi-NCR	-65 to 130	)  -	-
		2	216		-65 to 130	70 to 10	410

			_				
		3	216		-65 to 130	-	-
		4	216		-65 to 130	-	-
		5	253		-65 to 130	-70 to 10	412
		6	253		-65 to 130	-	-
		1	660		-198 to 396	-40 to 80	772,778
12	Bara PPGCL	2	660	UP	-198 to 396	-50 to 60	772,778
		3	660		-198 to 396	-70 to 50	772,778
		1	660	UP	-198 to 396	-100 to 50	760
13	Lalitpur TPS	2	660		-198 to 396	-80 to 50	765
		3	660		-198 to 396	-100 to 50	758
1.4	Anpara [	1	500	LID	-150 to 300	-	-
14	UP	2	500	UP	-150 to 300	-150 to 0	760
		1	250		-75 to 150	-50 to 50	410
		2	250		-75 to 150	-40 to 50	412
		3	250		-75 to 150	-40 to 40	410
15	Chhabra	4	250	Rajasthan	-75 to 150	_	-
13	TPS	5	660	Rajasillali	-198 to 396	-50 to 150	412
		6	660		-198 to 396	-70 to 150	412

All generating stations are requested to resolve any issues related to telemetry and make sure that MVAr absorption is as per grid requirement and capability curve of machine and there needs to be improvement in performance of thermal machines in MVAR support compared to last year.

Since with IEGC 2023 implementation, reactive energy performance also has financial impact, it is desirable that all generating stations continue to support grid voltages by having reactive power performance as per their capability curve and grid requirement.


Some of the generating units such IGSTPP Jhajjar, MGTPS Jhajjar, Bara need to explore possibility of further MVAR absorption. Further, intrastate generators in Rajasthan control area may be asked to support through adequate reactive power generation during day-time when Rajasthan grid experiences low voltage.

All generating stations are requested to resolve any issues related to telemetry and make sure that MVAr absorption is as per grid requirement and capability curve of machine. Generators may also set their Vsch (voltage set point) such that units are absorbing MVAR as per their capability and grid requirement with intimation to RLDC/SLDC.


# B.7. Severe Low voltages in J&K and N-1 violations

As expected, with the increase in winter, demand of J&K control area is on higher side and it is hovering around 3200MW. As the heating load is also picking up during early morning and night hours, the demand may further increase in the coming days. It has been observed that the 400kV as well as 220kV Bus voltages at various stations in Kashmir valley are remaining critically low also reaching 347kV and 178kV (well below the IEGC band i.e. 380KV & 198kV respectively) due to low hydro generation and heavy MVAR drawl from the ISTS nodes.

The low voltage is a perennial issue, and it has been deliberated in various meetings as well as in the recently held 56th TCC & 81 NRPC Meeting held on 30th & 31st October 2025 at Srinagar. Recent voltage plots of Amargarh, Wagoora, Wanpoh, Uri-1 and Uri-2 are shown below:



Further, loading of 400/220kV Amargarh ICTs for last one month is shown below:



J&K SLDC is requested to take appropriate measures:

 To maintain the 400kV & 220kV voltages within IEGC band in J&K control area to avoid any untoward incident.

To ensure N-1 compliance of 400/220kV Amargarh ICTs

### J&K SLDC may provide update. Members may please discuss.

## B.8. Critical operation of Rajasthan Grid during upcoming winter season:

Issues related to grid operation in Rajasthan state control area have been highlighted from NRLDC side in last several OCC/TCC/NRPC meetings. It is to be noted that such issues get aggravated during winter months when agricultural demand in state is on the higher side.

In 56 TCC and 81 NRPC meetings held on 30<sup>th</sup> and 31<sup>st</sup> Oct 2025, RRVPNL representative informed that:

- ICT at Bikaner (Raj) would be commissioned by December 2025 and at Merta end of October, Jodhpur erection and commissioning under progress..
- 151 Capacitor banks under installation and covered areas which have low power factor viz. Bikaner(Raj).
- RRVPNL informed that DISCOMs have also planned the installation of capacitor but may not come up this winter.
- 880 MVAR capacitor bank installation by Dec 2025.
- NRLDC representative highlighted that 400 KV Hindaun –Alwar sub-station, Voltages reaching lows of 320 KV.
- MS (NRPC) advised RRVPNL to run Dholpur plants and take up with their higher management in view of the present grid condition
- Low Voltages in the system also lead to huge payment under reactive energy account.
- Capacitor bank should also be installed in Bhinmal area in view of low voltages.
- SPS implementation to be expedited in priority where SPS has not been installed.
- At Heerapura ICT would be commissioned this year and SPS may not be required.
- PGCIL informed that bay construction work is under progress at various locations and ICTs would be commissioned in next year.
- SPS can be installed at PGCIL sub-stations in one month time line with feeders emanating from PG.
- Non-essential load may be shifted to Non-solar hours

Further, during 56<sup>th</sup> TCC and 81<sup>st</sup> NRPC meeting following decisions were made:

- I. Forum advised RRVPNL to take corrective actions from load side if Voltages go below 0.90 pu for ensuring safe and reliable grid operation.
- II. RRVPNL was also advised to take up with their higher management for running of Dholpur units this winter season to improve the Voltage profile.
- III. RRVPNL to expedite the commissioning of ICTs where N-1 non-compliance is observed.
- IV. Prioritise installation of capacitor banks in areas where low voltages and low power factor are observed.
- V. Installation of SPS at locations where N-1 issues were observed and take up in the upcoming OCC and PSC meetings.


VI. Rajasthan SLDC/STU to ensure compliance of grid connectivity standards of the intra-state generators which get connectivity to the grid of the state network.


Rajasthan SLDC provided following updates during 237 OCC meeting:

- New 400/220kV ICT at Merta is expected by end of Nov 2025
- New 400/220kV ICT at Bikaner is expected by end of Nov 2025
- New 400/220kV ICT at Heerapura is expected by end of Nov 2025
- New 400/220kV ICT at Jodhpur is expected by end of Dec 2025
- 151 Capacitor banks under installation and covered areas which have low power factor viz. Bikaner(Raj) would be commissioned by Dec 2025.
- RE generators are supporting grid and now injecting MVAr during day time to support grid voltages.
- RREC is also taking up with intrastate RE generators to comply with existing CEA regulations and provide reactive power support.


However, with the increased loadings in the transmission system, the operational issues have once again aggravated with poor power factor across different substations and also severe N-1 non-compliance of number of 400/220kV ICTs in Rajasthan.

ICTs MW drawl, MVAr drawl, and S/s voltage for Solar hours 09 Dec 2025, 12:30hrs for some stations are shown below:










Further, number of 400/220kV ICTs supplying power to Rajasthan are operating close to their rated limits without any n-1 compliance. For example, loading of 400/220kV Kotputli(PG) ICTs is show below where 315MVA ICTs seem to be over loaded.



List of few 400/220 kV ICTs in Rajasthan with loading beyond N-1 limits (Loading observed


(09Dec 2025 @ 12:30hrs) are mentioned below.


# List of constrained 400/220kV ICTs in Rajasthan

Constrained location	Status as available with NRLDC	Present Loading (MW)	N-1 contingency limit (MVA)
N-1 contingency of 3*315=945 MVA ICT at Bhiwadi(PG)	Additional 500MVA ICT approved in 29 CMETS on 17.05.2024	Data suspect	740
N-1 contingency of 2*315+500=1130 MVA ICT at Bassi(PG)	Additional 500MVA ICT has been approved. Same is anticipated by 14.12.2025.	800-900	730
N-1 contingency of 315+500=815 MVA ICT at Neemrana(PG)	Additional 500MVA ICT has been approved in 36 NR CMETS held on 15.01.2025.	Less loading due to S/d of 220kV Neemrana- Behror D/C	590
N-1 contingency of 2*500=1000 MVA ICT at Jaipur South(PG)	Additional 500MVA ICT has been approved in 36 NR CMETS held on 15.01.2025.	450-500	680
N-1 contingency of 2*315+500=1130 MVA ICT at Sikar(PG)	Additional 500MVA ICT has been approved in 38 NR CMETS held on 28.05.2025	900-1000	680

N-1 contingency of 3*315=945 MVA ICT at Kankroli(PG)	ICT-4 has been approved and is expected to be commissioned by Dec 2025.	600-650	670
N-1 contingency of 2*315=630 MVA ICT at Kotputli(PG)	Augmentation by 400/220 kV 500 MVA (3rd) ICT at Kotputli (PG) is expected by 31.12.2025	600-650	380
N-1 contingency of 2*315=630 MVA ICT at Deedwana(RVPN)	As per latest status shared by	350-400	350
N-1 contingency of 3*250+315=1065 MVA ICT at Heerapura(RVPN)	Rajasthan SLDC order for 10 no. ICT has been placed recently. New	600-700 (data to be checked)	890
N-1 contingency of 3*315 =945 MVA ICT at Chittorgarh (RVPN)	500MVA ICTs are expected to be commissioned at	600-650	670
N-1 contingency of 2*315 =630 MVA ICT at Ajmer (RVPN)	400/220kV Merta, Ajmer and Bikaner by Dec 2025.	550-600	370
N-1 contingency of 2*315 =630 MVA ICT at Merta (RVPN)	SPS has been implemented as temporary measure for some of the	450-500	390
N-1 contingency of 2*315 =630 MVA ICT at Bikaner (RVPN)	stations such as Chittorgarh (RVPN), Ajmer (RVPN), Merta	400-500	410
N-1 contingency of 2*315=630 MVA ICT at Suratgarh(RVPN)	(RVPN), Bikaner (RVPN), Jodhpur (RVPN), Suratgarh(RVPN),	350-400	370
N-1 contingency of 3*315=945 MVA ICT at Ratangarh(RVPN)	Ratangarh(RVPN)	600-700	640

400kV as well as 220 KV Bus voltages at Alwar, Hindaun and 220kV voltage at Dholpur are remaining critically low (on lower side of IEGC band). The 400kV bus voltages at Alwar and Hindaun are even touching precariously low level of 320kV and 330kV respectively. 220kV Dholpur voltage is also reaching low of 160kV in recent days.





Further, huge MVAR drawl by Rajasthan control area from grid is observed with MVAR drawl reaching alarming levels of >3200 MVAR. It is also pertinent to mention here that excessive MVAR drawl from the Grid would also lead to payment of reactive charges into the pool by Rajasthan control area.

### Rajasthan SLDC may provide update.

### SPS proposals in Rajasthan

Majority of 400/220kV ICTs in Rajasthan state (both interstate as well as intrastate are N-1 non-compliant).

For intrastate substations, where SPS have not been planned and implemented, the same may be taken up. List of N-1 non-compliant substations is shown below:

Constrained location	SPS Status as available with NRLDC
3*315=945 MVA ICT at Bhiwadi(PG)	Approved and to be implemented
2*315+500=1130 MVA ICT at Bassi(PG)	Approved and to be implemented

315+500=815 MVA ICT at Neemrana(PG)	Approved and to be implemented
2*500=1000 MVA ICT at Jaipur South(PG)	Approved and to be implemented
2*315+500=1130 MVA ICT at Sikar(PG)	Approved and to be implemented
3*315=945 MVA ICT at Kankroli(PG)	Approved and to be implemented
2*315=630 MVA ICT at Kotputli(PG)	Approved and to be implemented
2*315=630 MVA ICT at Deedwana(RVPN)	Not planned
3*250+315=1065 MVA ICT at Heerapura(RVPN)	Not planned
3*315 =945 MVA ICT at Chittorgarh (RVPN)	Implemented
2*315 =630 MVA ICT at Ajmer (RVPN)	Implemented
2*315 =630 MVA ICT at Merta (RVPN)	Implemented
2*315 =630 MVA ICT at Bikaner (RVPN)	Implemented
2*315 =630 MVA ICT at Jodhpur (RVPN)	Implemented
2*315=630 MVA ICT at Suratgarh(RVPN)	Implemented
3*315=945 MVA ICT at Ratangarh(RVPN)	Implemented
1*500+1*315 =815 MVA ICT at Bhilwara (RVPN)	Implemented

NRLDC vide email dated 02.12.2025 has communicated that the stage wise logic for SPS of ICTs at POWERGRID stations in Rajasthan control area was discussed in 64th PSC meeting held on 21.11.2025. The time delay logic proposed by Rajasthan was agreed and POWERGRID was requested to start the implementation process of the SPS at designated stations.

Time delay for stage-1&2 of SPS was decided as:

- 1. Stage-1: 105% loading with 1 sec delay
- 2. Stage-2: 105% loading with 1.5 sec delay

POWERGRID is requested to implement the SPS at designated stations i.e., 400/220kV Kankroli(PG), Bassi(PG), Neemrana(PG), Kotputli(PG), Bhiwadi(PG), Jaipur South(PG) and Sikar(PG) at the earliest possible.

POWERGRID and Rajasthan SLDC may provide update.

# B.9. State-wise transmission constraints during high demand season of 2025 and SPS proposals

During the high demand season, the transmission system in Northern region remains heavily loaded. Transmission constraints observed in the grid during high demand period are regularly being highlighted in OCC meetings. Same is also being submitted to CTUIL and CEA through quarterly operational feedback.

Even after several follow-ups, it is observed that progress of several transmission elements are not up to the mark and expeditious actions from transmission utilities are required so that minimal issues are observed at transmission level during the high demand season.

State-wise issues and measures required thereof are listed below. Concerned transmission utilities are requested to provide update and ensure that these transmission elements are expeditiously commissioned.

### Punjab:

During OCC 237,

NRLDC proposed to increase ATC/TTC limits of Punjab state control area by 300MW presently and keeping it under observation and in case no issues are observed with ATC/TTC limits of 10700/11200MW, decision on further increase of ATC/TTC by 200MW would be taken by NRLDC in consultation with Punjab SLDC.

Punjab SLDC representative stated that they are reassessing the ATC/TTC limit for paddy 2026. After review of ATC/TTC limits by Punjab SLDC, revised figures would be shared with NRLDC at the earliest.

Punjab SLDC may provide update.

Haryana:

SPS proposals in Haryana

For SPS at 400/220kV Hissar(PG) ICTs:

During 237 OCC meeting,

NRLDC representative asked POWERGRID to plan & implement SPS in such a manner that SPS is surely implemented by Apr 2026.

POWERGRID representative stated that only one offer has been received for DTPC panel procurement and the work is expected to be completed in next 3-4 months.

POWERGRID may provide update.

#### For SPS at 400/220kV Panipat ICTs:

During 237 OCC meeting, Haryana SLDC stated that they have taken up the matter with their TS-wing and would provide update on SPS implementation at 400/220kV Panipat(BBMB) shortly after the meeting.

OCC forum expressed concern on slow progress and asked Haryana SLDC to expedite SPS implementation at 400/220kV Panipat(BBMB).

HVPNL and Haryana SLDC may provide update.

#### **Uttar Pradesh:**

In 237 OCC meeting,

POWERGRID representative stated that 500MVA ICT-4 at Allahabad is expected to be commissioned by Dec 2025.

It was also informed by UPPTCL representative that old 240MVA ICT at Obra is expected to be revived by Nov 2025 whereas 315MVA ICTs at Obra would be revived after some time due to requirement of procurement of ICTs.

### SPS proposals in Uttar Pradesh


UP SLDC informed that work order for SPS logic of 400/220kV Bareilly S/s has been placed. SPS at both 400/220kV Panki and Bareilly substation are expected to be commissioned by Dec 2025.

OCC forum asked POWERGRID to implement SPS scheme at Agra(PG) at the earliest.

POWERGRID representative stated that SPS at Agra(PG) would be commissioned by Dec 2025 end.

### POWERGRID, UPPCL and UP SLDC are requested to provide update.

It was discussed that CERC vide their order dated 29.09.2023 has granted approval of "Detailed Procedure for Allocation of Transmission Corridor for Scheduling of General Network Access and Temporary General Network Access under Central Electricity Regulatory Commission (Connectivity and General Network Access to the inter-State Transmission System) Regulations, 2022" which requires SLDCs to submit network data as well as PSSE basecases on M-12, M-6, M-1 basis. The monitoring of submission of these data by SLDCs is being done in OCC meetings on monthly basis where response of some of the states needs improvement.



During 237 OCC meeting, Uttarakhand SLDC submitted that they had recently shared basecase file with NRLDC.

NRLDC representative stated that basecase need to submitted for four scenarios as per IEGC approved procedure. Only two scenario basecase has been received by NRLDC from Uttarakhand SLDC which was also submitted after due date.

Further, states submitting basecase with one month delay may note that the changes given by them do not get reflected in the All India/regional basecase file, as NRLDC prepares the basecase as per CERC approved timelines and goes ahead as per the data available as on date.

ATC/TTC limits of states for the month of January 2026 are attached as Annexure-B.IV of agenda. Utilities are requested to go through these limits and provide comments.

# Members may please discuss.

# B.10. Bypass of 400kV Dadri-Maharanibagh and 400kV Maharanibagh-Ballabgarh at 400kV Maharanibagh

765/400 kV Narela Substation was energized on 01.10.2025 through the LILO of the 765 kV Meerut–Bhiwani line. Subsequently, all 765/400 kV ICTs, bus reactors, and both the 765 kV and 400 kV buses at Narela have been brought into service.

Following interconnections were recently commissioned:

- 765 kV Khetri–Narela D/c line
- 400 kV Narela–Maharanibagh M/c line

Before the implementation of above arrangement, assessment of the requirement to bypass the 400 kV Ballabgarh–Dadri lines at Maharanibagh and maintain radial connectivity of Maharanibagh with Narela at 400 kV was studied at NRLDC end.

Observations from fault level assessment studies:

- a. In the Final arrangement with 400kV Dadri-Ballabgarh Not By-passed at 400kV Maharanibagh (i.e. connected), 3-Ph Fault current at 400kV Maharanibagh, 400kV Narela and 400kV Ballabgarh will increase by 10kA, 23kV and 4kA respectively, but still within 45kA, so no issue in these S/s. Further, it would also provide good fault level support at 765/400kV Narela S/s.
- b. However, 3-Ph Fault current at 400kV Dadri NCR and 400kV Dadri (PG) will increase by 5kA at each S/s and it would be ~51kA and 50kA respectively. Any issue in case of 50kA 3-Ph Fault current at 400kV Dadri S/s may be reviewed by PGCIL/NTPC.
- c. 3-Ph Fault current at 400kV Meerut S/s is 63kA in basecase itself, no major impact with By-passing 400kV Dadri-Ballabgarh at 400kV Maharanibagh.
- d. With connection of only 400kV Ballabgarh-Maharanibagh line, following are fault levels:

		Fau				
		Earlier	Present arrangemen	Connection of only 400kV	%	%
		arrangement of bypass (a)	t w/o bypass (b)	Ballabgarh -Mbagh ©	chang e (b-a)	change (c-a)
124014	[BALLABHGR- PG400.00]	30134	30475	30428	1.13%	0.98%
124027	[BALLABH_2ND	25799	28342	28126	9.86%	9.02%
144002	[MAHARANI	16104	28029	22346	74.05 %	38.76%
144015	[NARELA_400	18222	27257	23311	49.58 %	27.93%
154061	[DADR-NCR	32096	34503	30317	7.50%	-5.54%
154118	[DADRI_PG	31633	33968	29903	7.38%	-5.47%
		Fault current (kA)				

	[BALLABHGR-					
124014	PG400.00]	43.5	44.0	43.9	1.13%	0.98%
124027	[BALLABH_2ND	37.2	40.9	40.6	9.86%	9.02%
					74.05	
144002	[MAHARANI	23.2	40.5	32.3	%	38.76%
					49.58	
144015	[NARELA_400	26.3	39.3	33.6	%	27.93%
154061	[DADR-NCR	46.3	49.8	43.8	7.50%	-5.54%
154118	[DADRI_PG	45.7	49.0	43.2	7.38%	-5.47%

Accordingly, proposal of keeping 400kV Dadri-Maharanibagh-Ballabgarh remain connected at 400kV Maharanibagh may be deliberated.

### Members may please discuss.

### B.11. Ensuring availability of hydro generators for AGC support

NRLDC has been continuously pursuing intra-State Generators and IPPs (Independent Power Producers) to implement Automatic Generation Control for balancing and improving the grid frequency profile. As a part of this ongoing initiative, a one-day capacity building workshop was successfully organized by the Northern Regional Load Dispatch Centre (NRLDC) on 04th December 2025 at the NRPC Conference Hall for the benefit of Northern Region State Load Dispatch Centres (SLDCs), intra-state generating stations, and IPPs.

The primary objective of the workshop was to enhance stakeholder understanding of the technical requirements, regulatory provisions, and commercial mechanisms associated with the participation of intra-State generators in the Central Secondary Reserve Ancillary Services (SRAS) framework through AGC. During the workshop, detailed presentation was given by GRID-INDIA about how intra-State Generators can also participate under SRAS mechanism at central level and how it would be helpful to generators to earn additional revenue and help in improving reliable grid operation. Representatives from PPGCL-Bara, THDC-Khurja, and UP SLDC also shared valuable insights based on their successful AGC implementation experiences, providing practical perspectives to the participants.

However, recently it is being observed that some of the existing wired hydro stations in Northern region are not keeping their units in AGC remote mode for all the time. For example for 07 Dec 2025, it was reported that despite availability of communication, the time for which the hydro stations participated in secondary frequency control was low as shown below:

S.No.	Plant Name	% AGC Remote	% Onbar	% Communication Link Availability
1	BAIRASIUL	0	17	100
2	DHAULIGNG A	0	18	100
3	NJPC	28	26	100
4	TEHRI	33	29	100
5	CHAMERA2	37	23	100
6	SEWA2	52	16	100
7	CHAMERA1	72	14	100

8	RIHAND1	81	100	100
9	SINGRAULI	83	60	100
10	UNCHAHAR2	86	50	100

NLDC/NRLDC are pursuing with the stations to operate in AGC-remote mode whenever units are brought on bar. However, it is requested that the generating station control room personnel may be advised to keep their units in AGC remote mode whenever they are generating. This would enhance the quantum of regulating reserve in the grid for frequency control.

Members may please discuss.

### B.12. Mock testing of islanding scheme and simulation studies

Following four islanding schemes are operational in the Northern Region: NAPP Islanding Scheme (Uttar Pradesh), RAPP Islanding Scheme (Rajasthan), Bawana Islanding Scheme (Delhi), and Unchahar Islanding Scheme (Uttar Pradesh).

During 237 OCC meeting, NRLDC representative presented the latest status of actions required on various islanding schemes.

Scheme	UFR testing done	Basecase shared	SCADA display made
NAPP Islanding scheme (UP)			
RAPP Islanding scheme (Raj)			
Bawana Islanding scheme (Delhi) (Need Review)			
Unchahar Islanding scheme(UP)		<b>⊗ No</b>	

UP SLDC representative stated that Unchahar islanding scheme basecases are being prepared. Data has been requested from field and some data is pending. Basecases would be shared with NRLDC at the earliest.

NRLDC representative further stated that Bawana islanding scheme of Delhi needs review with upcoming network changes due to commissioning of 765/400kV Narela substation.

DTL representative stated that the scheme changes required due to reconfiguration would be implemented at site.

MS NRPC stated that the proposed reconfiguration of islanding scheme by DTL may be shared with NRLDC/ NRPC by next OCC meeting and thereafter changes may be done in islanding scheme.

Delhi and UP SLDC may provide update.

#### B.13. Self-audit related:

As per IEGC Clause 56.2(c),

### Quote

"The self-audit reports by users, QCAs, and SNAs shall be submitted to the concerned RLDC or SLDC, as the case may be."

### Unquote

Failure to submit the self-audit report within the stipulated timeframe would be considered a non-compliance with IEGC regulations.

During 235 OCC meeting, it was discussed that Self-audit report has been received from NHPC and Koteshwar THDC only for F.Y. 2023-24. As F.Y. 2024-25 has also completed recently, all utilities in Northern region are requested to carry out self-audit exercise and share report with NRLDC as per IEGC Clause 56.2(c).

As 31.07.2025 has already past, it is requested that all concerned users of NRLDC may carry out their self-audit and submit report to NRLDC at the earliest.

NRLDC communication in this regard to all concerned is attached as **Annexure B.V** for reference.

The self-audit report should inter alia include the following details:

- 1. Sufficient information on any instances of non-compliance, explaining how and why they occurred.
- 2. Extent of impact or damage caused by such non-compliance.
- 3. Corrective steps planned along with a timeline for rectification.
- 4. Measures taken to prevent recurrence in the future.

Self-audit reports are being received from some of the RE developers and Qualified Coordinating Agencies (QCA) but are still pending for NRLDC users which are part of OCC forum.

All concerned are requested to provide update. Members may please discuss.

# B.14. Multiple element tripping events in Northern region in the month of November 2025:

A total of **07** grid events occurred in the month of November 2025 of which **3** are of GD-1 category **01** are of GI-2 Category and **03** are of GI-1 Category. The tripping report of all the events have been issued from NRLDC. A list of all these events along with the status of DR/EL & tripping detail submission is attached at **Annexure-B.VI.** 

Maximum delayed clearance of fault observed in event of tripping event at 220/132/33kV Jammu(Gladni(J&K)) at 16:24 hrs on 11<sup>th</sup> November 2025 (As per

PMU at Kishenpur(PG), R-B phase to phase fault converted to 3-phase fault was observed with delayed fault clearing time of 1040ms).

Delayed clearance of fault (more than 100ms for 400kV and 160ms for 220kV system) observed in total **02** events out of **13** grid events occurred in the month. In **02** (no.) of grid events, there was no fault in the grid.

As per IEGC clause 37.2 (c), Disturbance Recorder (DR), station Event Logger (EL), Data Acquisition System (DAS) shall be submitted within 24 hrs of the event and as per IEGC clause 37.2 (e), the user shall submit a detailed report in the case of grid disturbance or grid incidence within one (1) week of the occurrence of event to RLDC and RPC.

It is observed that DR/EL & tripping report of most of the grid events are not being submitted as per timeline specified in IEGC 2023. Non availability to tripping details further hampers the grid event analysis at RLDC level.

Members may take necessary preventive measures to avoid such grid incidents / disturbances in future and share the report of actions taken by respective utilities. Moreover, utilities may impress upon all concerned for providing the Preliminary Report, DR/EL & Detailed Report of the events to RLDC in line with the IEGC clause 37.2 (c) & (e).

Members may like to discuss.

# B.15. Status of submission of DR/EL and tripping report of utilities for the month of November 2025:

The status of receipt of DR/EL and tripping report of utilities for the month of **November 2025** is attached at **Annexure-B.VI**I. It is to be noted that as per the IEGC provision under clause 37.2 (c), the tripping report along with DR/EL has to be furnished within 24 hrs of the occurrence of the event. However, it is evident from the submitted data that reporting status of RE stations(ADANI, RENEW, SJVN), SLDC-HP, SLDC-PS, SLDC-J&K, SLDC-Delhi, BBMB, NTPC, NHPC, Sterlite and RAPS is not satisfactory and needs improvement.

Members may please note and advise the concerned for timely submission of the information. It is requested that DR/EL of all the trippings shall be **uploaded on Web Based Tripping Monitoring System "https://postda.nrldc.in/Default.aspx"** within 24 hours of the events as per IEGC clause 37.2(c) and clause 15.3 of CEA grid standard. Apart from prints of DR outputs, the corresponding COMTRADE files (.cfg/.dat) may please also be submitted in tripping portal.

Members may like to discuss.

### B.16. Mock testing of System Protection Schemes (SPS) in Northern Region

As per IEGC clause 16.2

"For the operational SPS, RLDC or NLDC, as the case may be, in consultation with the concerned RPC(s) shall perform regular load flow and dynamic studies and mock testing for reviewing SPS parameters & functions, at least once in a year. RLDC or NLDC shall share the report of such studies and mock testing including any short comings to respective RPC(s). The data for such studies shall be provided by CTU to the concerned RPC, RLDC and NLDC."

# As per IEGC clause 16.3

"The users and SLDCs shall report about the operation of SPS immediately and detailed report shall be submitted within three days of operation to the concerned RPC and RLDC in the format specified by the respective RPCs."

There are **58 numbers of System Protection Scheme (SPS) approved** in Northern Region. These SPS are implemented at major generation complexes, important evacuating transmission lines and ICTs which are N-1 non-complaint. System Protection Scheme Document of Northern Region has been revised/updated on 31<sup>st</sup> January 2025. Revised version of the document is available on the NRLDC website in Document section and can be accessed at below link: <a href="https://nrldc.in/documents/Documents">https://nrldc.in/documents/Documents</a>.

In this regard, communication was sent to constituents through NRLDC letter dated 01.05.2024, 21.02.2025, 05.03.2025, 04.04.2025 & 28.05.2025 for conducting mock testing of SPS in their control area and continuous follow up is also being done in OCC & PSC meeting since May 2024.

During 2024-25, mock testing of 14 SPS out of total 55 SPS were not conducted. In view of high demand scenario during summer 2025-26, NLRDC vide letter dated 04.04.2025 requested all the concerned utility to conduct the mock testing of pending SPS by the end of April 2025. However, as reported, mock testing of 03 SPS out of pending 14 SPS have been done. In this regard, discussion is being continuously held in OCC & PSC meetings. PSC forum requested all the members to conduct the mock testing of all the SPS in their respective control area at the earliest.

Status of mock testing of all the SPS in NR is attached as **Annexure-B.VIII**.

Members are requested to share the updated w.r.t. their respective control area.

Status of follow-up actions w.r.t. some of the SPS are as follows:

i. SPS of HVDC Rihand-Dadri: During mock testing of SPS of HVDC Rihand-Dadri on 20.03.2025, issues i.e., faulty SPS hardware at Singrauli TPS (NTPC) and no receipt of SPS signal at 220/132kV Ratangarh(RS) were identified. Further, during recent operation of SPS on 21.05.2025 in incident of outage of both poles, desired SPS actions i.e., generation backdown at Singrauli TPS and load relief in UP, Delhi, Haryana & Punjab were not observed. Desired load / generation relief is important to ensure the security and reliability of grid during such contingency. As per details received, SPS signal was sent to all the mapped stations from POWERGRID end however either due to non receipt of signal or error in SPS

system at load / generation, SPS action didn't occur. NRLDC vide letter dated 02.07.2025, requested POWERGRID and Singrauli NTPC to take necessary remedial measures and make complete SPS system healthy.

During 233<sup>rd</sup> OCC meeting, POWERGRID representative stated that the equipment's at Singrauli TPS end is owned by NTPC and need to be revived by them. SPS system at Rihand(PG) is healthy and operational. NTPC representative stated that as per details received from site, NTPC Singrauli team have initiated necessary actions in coordination with the POWERGRID. SPS operation is crucial as it is planned for special contingencies, and its unavailability may lead to cascade tripping or major grid disturbance especially in case of high demand period.

Discussion during 237<sup>th</sup> OCC meeting:

- a) NRLDC requested NTPC Singrauli and POWERGRID to share the details of necessary corrective actions taken / planned to be taken to ensure healthiness of SPS system at Singrauli TPS and load stations.
- b) Representative from NTPC informed that existing SPS system at Singrauli TPS is defective, procurement work has been initiated. NRLDC requested NTPC to share the tentative timeline for completion of work and to expedite the remedial actions for early restoration of SPS system at Singrauli TPS.
- c) Regarding issues at load stations, POWERGRID agreed to take necessary actions in coordination with the site stations.
- d) Further, NRLDC also informed that mock testing of SPS of HVDC Rihand-Dadri has been scheduled tentatively on 19.11.2025. Concerned members were requested to ensure the readiness and share the details of coordinators.

SPS mock testing of HVDC RIhand-Dadri was conducted successfully on 19.11.2025. SPS command didn't receive at 220kV Muradnagar(UP), 220kV Merta(RS), 220kV Kota Sakatpura(RS), 220kV Dhanonda(HR) and Singrauli TPS(NTPC). SPS system at Rihand HVDC, Dadri HVDC and at remaining load and generating stations are healthy.

POWERRGID, Singrauli(NTPC) and other concerned may share the details of actions taken / planned to be taken to rectify the issues in HVDC Rihand-Dadri SPS system.

ii. SPS of Anta, Kawai, Chhabra generation complex: In one of the SPS cases i.e., N-1-1/ N-2 of 765kV Anta-Phagi 1 & 2, instantaneous generation backdown of ~2100 MW is designed as SPS action. In such scenario, to avoid overloading of WR-NR corridor and over drawl by Rajasthan, it was agreed that RVPNL shall implement the automatic load shedding of ~750 MW by 28.02.2018. However, as per details available, implementation of automatic load shedding as per SPS hasn't been done yet. This matter has already been discussed in PSC as well as OCC meetings on regular basis. The concern of grid security and reliability was also raised during request of shutdown of 765kV Anta-Phagi line. is requested to

expedite implementation of the automatic load shedding of  $\sim$ 750 MW as per SPS (N-1-1/ N-2 contingency of 765kV Anta-Phagi-1 & 2).

During 235<sup>th</sup> OCC meeting, SLDC-Rajasthan representative informed that automatic load shedding of ~750 MW has been implemented.

During 236<sup>th</sup> OCC meeting, SLDC-Rajasthan confirmed that mock testing of automatic load shedding part of the SPS has been conducted.

Discussion during 237<sup>th</sup> OCC meeting:

- a) NRLDC representative requested Rajasthan to share the mock test report of the automatic load shedding part of the SPS.
- b) RVPNL agreed to share the mock test report w.r.t. automatic load shedding part of the SPS at the earliest.

Details haven't been received yet. Rajasthan is requested to share the details at the earliest possible.

iii. **SPS of N.Jhajkri, Karcham, Rampur hydro generation complex:** Status of implementation of case-6(i) and corrective actions w.r.t case-6 (ii) need to be shared.

During 235<sup>th</sup> OCC meeting, HPPTCL representative informed that faulty communication card at Wangtoo S/s is to be replaced with new card. The case is at procurement stage, and it is estimated that work will be completed by the end of December 2025.

Karcham(JSW) and HPPTCL may share the update in this regard.

iv. **SPS of 765kV Agra-Gwalior D/C:** Mock testing of the SPS was conducted on 10.10.2025. During the testing, it was observed that there is communication issue at Bhiwadi(PG), Bamnauli(DTL), Kota, Debari, Chittorgarh, Ratangarh, Nunamajra, Safidon, Ajitwal, Dandhari-II, Ablowal substations.

NRLDC requested all the concerned states to submit the mock test report of their respective control area. Details have been received from Delhi, Rajasthan and Punjab. UP, BBMB, Haryana and POWERGRID have shared the partial details.

Further, POWERGRID was requested to share the details of actions taken / planned to be taken to resolve the issues in SPS system.

During 237 OCC meeting, POWERGRID was requested to take expeditious corrective actions to rectify the issues and make the SPS healthy and operational at all the stations.

NRLDC has also sent a letter dated 28.11.2025 to POWERGRID for expeditious corrective actions and make complete SPS system healthy and operational.

POWERRGID may share the details of actions taken / planned to be taken to rectify the issues in 765kV Agra-Gwalior D/C SPS system.

Further, Clause 16.2 of IEGC 2023 also mandates the mock testing of SPS for reviewing SPS parameters & functions, at least once a year. Mock testing of all the SPS needs to be conducted in 2025-26. In view of this following is requested:

- Concerned constituents / utility are requested to conduct the mock testing of pending SPS (whose mock testing was not conducted in 2024-25) at the earliest.
- ii. Utilities are also requested to conduct the mock testing of SPS schemes in their respective control area w.r.t. year 2025-26.
- iii. In compliance with IEGC clause 16.2, users shall ensure that mock testing along with the review of SPS logic of all the SPS is conducted at least once a year.
- iv. Further In compliance with IEGC clause 16.3, users shall also share the detailed report of SPS operation in their respective control area within 3 days of its operation. Presently, no such report is being received.

Further, during 60<sup>th</sup> PSC meeting, it was decided that the SPS which are not required from constraint point of view will not be disabled for keeping the assets associated with SPS healthy and will be treated as "reserve SPS", as may be required during prolonged outages of any system element. In case of reserve SPS for transformers (where logic was based on "tripping" of transformer) logic need to be modified based on "loading" of transformer in place of "tripping" of transformer.

The list of reserve SPS as on date are as follows:

- i. SPS for Transformers at Ballabhgarh (PG)
- ii. SPS for Transformers at Bamnauli (DTL)
- iii. SPS for Transformers at 400KV Muzaffarnagar (UP)
- iv. SPS for Transformers at 400KV Sultanpur (UPPTCL)
- v. SPS for Transformers at 400KV Gorakhpur (UPPTCL)
- vi. SPS for Transformers at 400KV Greater Noida (UPPTCL)

During 64<sup>th</sup> PSC meeting, MS-NRPC suggested that assets of "reserve SPS" can be used in new SPS to be commissioned and hence they may be removed from existing SPS list. PSC forum suggested to remove the above mentioned 06 "reserve SPS" schemes.

### Implementation of SPS in POWERGRID substations in Rajasthan control area:

SPS stage wise logic (received from Rajasthan) for SPS of ICTs at POWERGRID stations in Rajasthan control area was discussed in 64<sup>th</sup> PSC meeting. The time delay logic proposed by Rajasthan was found OK and POWERGRID was requested to start the implementation process of the SPS at designated stations.

Time delay for stage-1&2 of SPS was decided as:

- 1. Stage-1: 105% loading with 1 sec delay
- 2. Stage-2: 105% loading with 1.5 sec delay

NRLDC through mail dated 0.12.2025 requested POWERGRID to implement the SPS at designated stations i.e., 400/220kV Kankroli(PG), Bassi(PG), Neemrana(PG), Kotputli(PG), Bhiwadi(PG), Jaipur South(PG) and Sikar(PG) at the earliest possible.

POWERGRID may share the update in this regard. Mock testing report of the SPS also need to be shared after implementation.

Members may like to discuss.

# B.17. Mock trial run and testing of black start facilities at generating stations in Northern Region

As per Indian Electricity Grid Code (IEGC) clause 34.3

"Detailed procedures for restoration post partial and total blackout of each user system within a region shall be prepared by the concerned user in coordination with the concerned SLDC, RLDC or NLDC, as the case may be. The concerned user shall review the procedure every year and update the same. The user shall carry out a mock trial run of the procedure for different sub-systems including black-start of generating units along with grid forming capability of inverter based generating station and VSC based HVDC black-start support at least once a year under intimation to the concerned SLDC and RLDC. Diesel generator sets and other standalone auxiliary supply source to be used for black start shall be tested on a weekly basis and the user shall send the test reports to the concerned SLDC, RLDC and NLDC on a quarterly basis".

Hydro and gas-based plants are capable of self-black-start. Conducting periodic mock black start exercises are extremely important to ensure the healthiness of black start facilities and also to build awareness as well as confidence among the system operators.

In view of above, regional entity generating stations shall conduct the dead bus charging of their units on rotation basis as per availability of schedule under intimation to the NRLDC. Testing of Diesel generator sets and other standalone auxiliary supply source to be used for black start shall also be done on a weekly basis. SLDC shall also ensure the same in their respective control area. This will ensure the healthiness of blackstart facility at generating stations. Further, NRLDC shall coordinate with the ISGS and states to conduct the mock black start exercise of subsystems.

Therefore, regional entity generating stations and SLDCs are requested to share the annual schedule plan for conducting dead bus charging / mock black start exercise of generating stations /sub-systems during 2025-26. The present status of mock black start of generating units is attached as **Annexure-B.IX**. Constituents are also requested to share the test report of diesel generators / auxiliary supply on a quarterly basis.

Mock black start exercised conducted during FY 2025-26 are as follows:

Sr. No.	Name of Generating station	Date of Mock Black Start Exercise conducted
1.	Parbati_III HEP	17.05.2025
2.	Sewa_II HEP	16.05.2025
3.	Rihand & Obra HEP(UP)	02.06.2025
4.	Ramgarh GPS	11.05.2025
5.	RSD HEP(Punjab)	01.12.2025
6.	Tehri HEP	11.11.2025

### Therefore, ISGS and SLDCs are requested to take following actions:

- To share the tentative schedule of mock black start exercise of generating stations in their respective control area.
- SLDCs are requested to share the tentative schedule plan of mock black start exercise of generating stations in their respective control area.
- To conduct dead bus charging after self-starting the generating station if schedule with load is not available.
- To share the test report of mock black start exercise conducted along with weekly DG testing on monthly/quarterly basis.

### Members may like to discuss.

### **B.18.** Revision of document for Reactive Power Management of Northern Region:

NRLDC has been issuing 'Reactive Power document of Northern Region' on annual basis. Reactive Power Management document for Northern region was last revised on 31<sup>st</sup> Dec 2024 & updated document is available on NRLDC website in document section, the weblink of the same is as below:

### https://nrldc.in/documents/Documents

The document is password protected and password has already been informed to all the NR constituents.

In view of new addition/modification of transmission & generation element in NR grid since Dec'24, the document is being reviewed for update.

Constituents were requested to share the details by 03.12.2025, however details have been pending from all the SLDCs, BBMB, transmission licensees and other utilities.

Details have been received from Karcham & Baspa HEP, Tehri HEP & Tehri PSP, Luni HEP, Gumma(HP) S/s, APCPL Jhajjar TPS, Singoli Bhatwari HEP, Budhil HEP, Koldam HEP only

All the constituents / utilities are again requested to share the details w.r.t. your respective control area at the earliest possible, so that Reactive Power Document 2026 can be updated and compiled within stipulated time.

Constituents are requested to provide feedback, suggestion and updated information w.r.t. Reactive Power Document 2026 at the earliest possible.

# B.19. Revision of document for System Restoration Procedure Document of Northern Region:

NRLDC has been issuing 'System Restoration Procedure Document of Northern Region' on annual basis. The document was last revised on 31<sup>st</sup> Jan 2025 & updated document is available on NRLDC website in document section, the weblink of the same is as below:

### https://nrldc.in/documents/Documents

The document is password protected and password has already been informed to all the NR constituents.

In view of new addition/modification of transmission & generation element in NR grid since Jan'25, the document is being reviewed for update.

Constituents are requested to provide feedback, suggestion and updated information by 15<sup>th</sup> Jan 2025.

# B.20. Revision of document for System Protection Scheme Document of Northern Region:

NRLDC has been issuing 'System Protection Scheme Document of Northern Region' on annual basis. The document was last revised on 31<sup>st</sup> Jan 2025 & updated document is available on NRLDC website in document section, the weblink of the same is as below:

### https://nrldc.in/documents/Documents

The document is password protected and password has already been informed to all the NR constituents.

In view of new addition/modification of transmission & generation element in NR grid and revision in existing SPS, addition of new SPS and review of SPS, since Jan'25, the document is being reviewed for update.

Constituents are requested to provide feedback, suggestion and updated information by 15<sup>th</sup> Jan 2025.

 	म् सम्बद्धाः स्टिनिकी २२९	· ·	

1/57660/2025

CEA-GO-17-11/1/2023-NRPC

# Status of action taken on decision of 237<sup>th</sup> OCC meeting of NRPC

S.N.	Agenda	Decision of 237 <sup>th</sup> OCC	Status of action taken
		meeting of NRPC	
1.	A.12. Interim charging (rated voltage) of 765 kV D/C Bhadla III Ramgarh line and Ramgarh SS (PS) (Agenda by Powergrid NR-1)	OCC forum agreed that the proposal may be reviewed after the charging of 765 KV Khetri- Narela DC line.	CTU and NRLDC to update status.
2.	A.15. Utilisation of dynamic capability of SVCs and STATCOM to maintain GRID voltage (Agenda by Powergrid NR-2)	OCC forum asked POWERGRID to provide inputs to CTUIL regarding suitable locations for installing SVCs based on space availability for long-term planning. Further, OCC forum agreed that CTUIL may carry out the study in coordination with J&K and POWERGRID to assess the requirement of reactive power devices in J&K.	POWERGRID and CTUIL may update the status.
3.	A.16. Increase in fault level at 400/220KV Substation Ludhiana and Moga Substations (Agenda by Powergrid NR-2)	OCC forum asked CTUIL, NRLDC and POWERGRID to conduct a site visit before next OCC meeting to assess the feasibility of installation of Bus sectionalizer at Ludhiana and Moga Substations. Forum requested POWERGRID to coordinate and facilitate the site visit. Further, forum asked NRLDC and CTUIL to study jointly and suggest necessary measures for fault level control at these substations.	NRLDC and CTUIL may update the status.

# Status of action taken on decision of 237<sup>th</sup> OCC meeting of NRPC

4.	AA.1 Action Taken Report with respect to the past recommendations of the Standing Committee of Experts on EHV Tower Failures (Agenda by NRPC Secretariat)	NRSS XXXVI and PGCIL to submit Action Taken Report	UPPTCL, RVPNL, NTPC, NRSS XXXVI and PGCIL may update the status.
5.	AA.3 Details of allocation of Power to States and UTs of NR and tieups from Long Term arrangement for FY 2026-27 (Agenda by NRPC Secretariat)	OCC forum asked all SLDCs of NR to submit the details of allocation of Power to their control area and tie-ups from Long Term and Medium-Term arrangements along with banking and bilateral arrangements for FY 2026-27 within a week.	SLDC's to update the status.

1	Down Stream network by State utilities from ISTS Station	Augmentation of transformation capacity in various existing substations, addition of new substations along with line bays as well as requirement of line bays by STUs for downstream network are under implementation at various locations in Northern Region. Further, 220kV bays have already been commissioned at various substations in NR. For its utilization, downstream 220kV system needs to be commissioned.		networks is enclosed in
2	Progress of installing new capacitors and repair of defective capacitors	Information regarding installation of new capacitors and repair of defective capacitors is to be submitted to NRPC Secretariat.	Data upto following various states / UT  CHANDIGARH DELHI HARYANA HP J&K and LADAKH PUNJAB	
3	Healthiness of	Report of mock exercise for healthiness	<pre></pre>	-
	defence mechanism: Self-certification	of UFRs carried out by utilities themselves on quarterly basis is to be submitted to NRPC Secretariat and NRLDC. All utilities were advised to certify specifically, in the report that "All the UFRs are checked and found functional".	various states / UT  CHANDIGARH DELHI HARYANA HP J&K and LADAKH PUNJAB RAJASTHAN UP UTTARAKHAND BBMB All States/UTs are update status for h	Not Available Sep-2025 Sep-2025 Sep-2025 Not Available Sep-2025 Sep-2025 Nov-2025 Sep-2025 Sep-2025 Sep-2025 Sep-2025 requested to ealthiness of UFRs on slanding schemes and on
		In compliance of NPC decision, NR states/constituents agreed to raise the AUFR settings by 0.2 Hz in 47th TCC/49th NRPC meetings.	Guartely basis for Status:  CHANDIGARH DELHI HARYANA HP J&K and LADAKH PUNJAB RAJASTHAN UP UTTARAKHAND BBMB	Not Available Increased

4	Status of Automatic Demand Management	which	is man	dated	imple in cla	use 5.	4.2	e status of ADMS closed in <b>Annexu</b>	implementation in NR is							
	System in NR states/UT's			C/SEB/D ng tabl	ISCOMs e:	is pr	esen	ted in	0	DELHI	Scheme Implemented but operated in manual mode.					
									0	HARYANA	Scheme not implemented					
								HP	Scheme not implemented							
								PUNJAB	Scheme not implemented							
									RAJASTHAN	Under implementation.						
									0	UP	Scheme implemented by NPCIL only					
									0	UTTARAKHAND	Scheme not implemented					
5	Status of availability of ERS towers in NR	211th monitor rolling	OCC oring ng/foll regulan	meeti is ow-up r mon	ng, beii agenda	ERS ang in O	avail take CC n ERS	ability. n as neetings under	dii upo in	As per the information received from different utilities in Northern region, updated status of availability of ERS tower in Northern Region attached as <b>Annexure-A.II.III.</b>						
6	Submission of breakup	A11 st	ates/I	Ts are	regue	sted t	0		Sta	atus of the infor	mation submission (month)					
	of Energy Consumption by the states	submit billed	the r	equisi inform	-	a as p	er tl			from states / utilities is as under:						
										State / UT	Upto					
			Consumption	Consumption	Consumption	Consumption	Traction			CHANDIGARH	Not Submitted					
		Category→	by Domestic	by Commercial	by Agricultural	by Industrial	supply	Miscellaneous / Others	_	DELHI	0ct-25					
			Loads	Loads	Loads	Loads	load	7 041010		HARYANA HP	0ct-25 0ct-25					
		<month></month>							_	J&K and LADAKH	JPDCL- Mar' 24					
										3	KPDCL- Not Submitted					
									0	PUNJAB	Ju1-25					
										RAJASTHAN	Aug-25					
									UP	0ct-25						
									© UTTARAKHAND Feb−25							
								Chandigarh is requested to submit the requisite data w.e.f. April 2018 as per the billed data information in the given format								

9	Reactive compen	sation at 220 kV	/ 400 kV level at 5 substations	
	State / Utility	Substation	Reactor	Status
i	DTL	Mundka	1x125 MVAr at 400 kV & 1x25 MVAr at 220 kV	Bay work completed on 25.03.2023. Reactor part tender is dropped and at present same is under revision.
ii	DTL	Bamnauli	2x25 MVAr at 220 kV	Bay work completed on 25.03.2023. Reactor part tender is dropped and at present same is under revision.
iii	DTL	Indraprastha	2x25 MVAr at 220 kV	Bay work completed on 07.11.2023. Reactor part tender is dropped and at present same is under revision.
iv	DTL	Electric Lane	1x50 MVAr at 220 kV	Under Re-tendering due to Single Bid
V	PTCUL	Kashipur	1x125 MVAR at 400 kV	The Letter of Award for "Procurement of 125 MVAR Reactor, Online DGA, ODS, NIFPS along with its accessories at 400 KV Sub-station Kashipur" against Tender Specification no. PTCUL/E-Tender/C&P-II/SS-12/2024-25 has been issued to M/s Bharat Heavy Electricals Limited, New Delhi on 26.06.2025.

1. D	own Stream network	by State utilities from ISTS	Station:			Annexure-A-II.I				
SI. No.	Substation	Downstream network bays	Status of bays	Planned 220 kV system and Implementation status	Revised Target	Remarks				
1	400/220kV, 3x315 MVA Samba	Commissioned: 8 Total: 8	Utilized: 6 Unutilized: 2	Network to be planned for 2 bays.	-	02 No. of bays shall be utilized for LILO-II of 220kV Jatwal-Bishnah Transmission Line, the work of which is expected to begin on 16th July 2025. Updated in 233rd OCC by JKPTCL.				
2	400/220kV, 2x315 MVA New Wanpoh	Commissioned: 6 Total: 6	Utilized: 2 Unutilized: 4	• 220 kV New Wanpoh - Alusteng D/c Line	Mar'25	02 No. of bays are to be utilized for connecting 220kV New Wanpoh-Alusteng D/c Line. RoW issues persisting; At present new-wampoh-mirbazar 5km and harwan-alstung 16km have been completed, expected date of completion is Mar 2025 subject to availability of funds and resolving of RoW issues), Updated in 214th OCC by JKPTCL.				
		Total. 0	Ondanized. 4	• 220 kV New Wanpoh - Mattan D/c Line	End of 2024	02 No. of bays are to be utilized for connecting 220kV New Wanpoh-Mattan D/c Line. The funding source for the project is being identified and the project is expected to be completed by ending 2024. Updated in 204th OCC by JKPTCL.				
3	400/220KV, 2X315 MVA Amargarh	Commissioned: 6 Total: 6	Utilized: 4 Unutilized: 2	220kV D/C line from 400/220kV Kunzar - 220/33kV Sheeri	End of 2024	02 No. of bays are proposed to be utilized for connecting 220/132 kV GSS Loolipora. The funding source for the project is being identified and the project is expected to be completed by ending 2024. Updated in 204th OCC by JKPTCL.				
4	MVA Kurukshetra	Commissioned: 8 Total: 8	Utilized: 6 Unutilized: 2	• 220kV Bhadson (Kurukshetra) – Ramana Ramani D/c line	Commissioned	Updated by HVPNL in 235th OCC.				
5	MVA Dehradun	Commissioned: 6 Total: 6	Utilized: 2 Unutilized: 4	Network to be planned for 4 bays	-	PTCUL to update the status.				
6	Shahjahanpur, 2x315	Commissioned: 6	Utilized: 7	• 220 kV D/C Shahajahanpur (PG) - Gola line	Commissioned	Energization date: 26.10.2023 updated by UPPTCL in 215th OCC				
	MVA 400/220 kV	Approved/Under Implementation:1		LILO of Sitapur – Shahjahanpur 220 kV SC line at Shahjahanpur (PG)	Commissioned	Energization date: 25.02.2022 updated by UPPTCL in 196th OCC				
7	Sub-station	Commissioned: 8 Total: 8	Utilized: 4 Unutilized: 4	• 220 kV Hamirpur-Dehan D/c line	Commissioned	HPPTCL has commissioned the Planned 220kV Dehan- Hamirpur TL utilizing 2 No. 220kV Bays.Commisioned date: 09.06.2022. Updated in 198th OCC by HPPTCL				
				Network to be planned for 4 bays     LILO of 220 kV Sikar (220 kV GSS)-Dhod S/c	HPPTCL to update the status.  LILO of 220 kV S/C Sikar-Dhod line at 400 kV GSS					
8	Sikar 400/220kV, 1x 315 MVA S/s	Commissioned: 8 Total: 8	Utilized: 6 Unutilized: 2	Iline at Sikar (PG)  Network to be planned for 2 bays.	Commissioned -	PGCIL, Sikar has been charged on dt. 31.03.2022 Against the 3rd ICT at 400 kV GSS Sikar, only 2 bays were constructed and same has been utilized by RVPN by constructing LILO of 220 kV S/C Sikar – Dhod line as updated by RVPNL in 195th OCC				
				• 220 kV D/C line Bhiwani (PG) – Bhiwani (HVPNL) line	Commissioned	Updated in 202nd OCC by HVPNL				
9	Bhiwani 400/220kV	Commissioned: 6 Total: 6	Utilized: 2 Unutilized: 4	• 220 kV Bhiwani (PG) - Isherwal (HVPNL) D/c line.	Dec'25	Issue related to ROW as intimated in 228th OCC by HVPNL.  Status:  Work was stalled since 29.07.2021 due to ROW issues and farmers agitation and further restarted on 9.10.2023 with the help of district administration. Now, work was again stalled since30.11.2023 due to severe ROW issues.  Expected to be completed by 31.03.2025. Foundation 209/212. Erection 193/212. Stinging 37.8/50.3 km				
				220 kV Bhiwani (PG) - Dadhibana (HVPNL) D/c line.	Mar'26	Line work awarded to M/s R S Infra Projects Pvt. Ltd. Noida, Uttar Pardesh on dated 09.03.2024. Work of route plan and route alignment has been started by the firm as intimated in 234th OCC by HVPNL.				
10	Jind 400/220kV S/s	Commissioned: 4 Approved:4 Total: 8	Utilized: 4 Unutilized: 0	LILO of both circuits of 220 kV Jind HVPNL to PTPS D/C line at 400 kV substation PGCIL Khatkar (Jind) with 0.5 sq inch ACSR conductor	Sep'25	Erection and stringing work completed. The signing of Connection agreement amongst the Utilities is pending. Updated in 234th OCC by HVPNL.				
11	400/220kV Tughlakabad	Commissioned: 6	Utilized: 6	RK Puram – Tughlakabad (UG Cable) 220kV D/c line – March 2023.	Commissioned	Updated in 216th OCC by DTL				
		Under Implementation: 4	Unutilized: 0 Utilized: 2	Masjid Mor – Tughlakabad 220kV D/c line.     HPPTCL has planned one no. of 220kV D/c	Commissioned	Updated in 216th OCC by DTL				
12		Commissioned: 6	Unutilized: 2	line from Kala Amb 400/220kV S/s to 220/132kV Kala Amb S/s  • HPPTCL has planned one no. of 220kV D/c	Commissioned	Energization date: 31.05.2024 updated by HPPTCL in 220th OCC				
12	(TBCB) Total: 6 Under		Under Implementation:2	Iine from Kala Amb 400/220kV S/s to 220/132kV Giri S/s	-	Tendering process is yet to be started.Updated in 219th OCC by HPPTCL				
13	400/220kV Kadarpur	Commissioned: 8	Utilized: 0	Network to be planned for 2 bays      D/C line Kadarpur - Pali D/C line Kadarpur -	- Commissioned	HPPTCL to update the status. Updated in 232nd OCC by HVPNL Status:-				
	ISub-station	Total: 8	Unutilized: 8	Sec-65		A-formats for FTC of line submitted on FTC portal of NRLDC on dated 09.04.25.				

SI. No.	Substation	Downstream network bays	Status of bays	Planned 220 kV system and Implementation status	Revised Target	Remarks
				LILO of both circuits of 220kV D/c Sohna- Rangla Rajpur at Roj Ka Meo line at 400kV Sohna Road	Oct'25	Line work completed, but commissioning of 220kV substation Roj ka Meo is pending till now. However, this arrangement will not lead to usage of additional bays i.e. no of utilitised bays at Sohna road will remain same.Updated in 230th OCC by HVPNL
14	Road Sub-station		Utilized: 4 Unutilized: 4	LILO of both circuits of 220kV D/c Badshahpur-Sec77 line at 400kV Sohna Road		The matter is subjudice in Hon'ble Punjab & Haryana High court, Chandigarh Updated in 228th OCC by HVPNL. Status:- Earlier 02 nos 220 kV line bays were to be utilized for the 220 kV GIS S/Stn. Sec-77, Gurugram but due to denotification of land of the 220 kV GIS S/Stn. Sec-77 the said substation is now going to be dismantled and a new substation is proposed at Sec-75A, Gurugram. Now, these 02 no. 220 kV line bays may be utilized at 220 kV GIS S/Stn Sec-75A, Gurugram.
				220kV D/C line from Prithla to Harfali with LILO of one circuit at 220kV Meerpur Kurali	Dec'25	Contract awarded on 08.08.23 to M/s Skipper with completion in December 25.Updated in 230th OCC by HVPNL
			Litilizad: 4	LILO of both ckt of 220kV D/c Ranga Rajpur     Palwal line	Commissioned	Energization date: 31.12.2021. Updated in 198th OCC by HVPNL
	400/220kV Prithla	Commissioned: 8	Utilized: 4 Unutilized: 4	220kV D/C for Sector78, Faridabad	Dec'25	Issue related to ROW and Pending crossing approval from Northern Railways and DFCCIL. as intimated in 228th OCC by HVPNL.
	Sub-station	Total: 10	Under Implementation:2	Prithla - Sector 89 Faridabad 220kV D/c line	Dec'25	The work for construction of 220kV D/C Prithla-Sector-78 Faridabad line on multi circuit towers is delayed mainly due to severe resistance by local villagers & ROW problem at site during construction. Due to delay in construction of 220kV D/C Prithla-Sector-78 Faridabad line, the work for construction of 220kV D/C Prithla-Sector 89 Faridabad line might delayUpdated in 230th OCC by HVPNL
				LILO of both circuits of 220kV Samalkha -     Mohana line at Sonepat	Commissioned	Commissioned as updated by HVPNL in 233rd OCC
		Commissioned: 6	Utilized: 2	Sonepat - HSIISC Rai 220kV D/c line	Commissioned	Energization date: 31.05.2024 updated by HVPNL in 220th OCC
16	400/220kV Sonepat Sub-station	Under Implementation:2	Unutilized: 4 Under Implementation:2	Sonepat - Kharkhoda Pocket A 220kV D/c line	Nov'25	Updated in 232nd OCC by HVPNL.  Status:  Work order has been issued to M/s R.S Infra on dated 09.08.2023 by O/o CE/PD&C, Panchkula for construction of line.  Both bays are under construction and erection of electrical equipment is under progress.
17	400/220kV Neemrana		Utilized: 4 Unutilized: 2	LILO of Bhiwadi - Neemrana 220kV S/c line at Neemrana (PG)	-	Work is under progres. Stub Setting: 14/2017. Permission for Highway is awaited from concerned department as updated in 218th OCC by RVPNL.
18	400/220kV Kotputli		Utilized: 2 Unutilized: 2	Kotputli - Pathreda 220kV D/c line	-	Date of bid opening has been extended up to 30.04.2024 as updated in 218th OCC by RVPNL.
19	400/220kV Jallandhar Sub-station	Commissioned: 10 Total: 10	Utilized: 8 Unutilized: 2	LILO of 220 kV BBMB Jalandhar - Butari line at 400 kV PGCIL Jalandhar	-	LILO of 220 kV BBMB Jalandhar - Butari line at 400 kV PGCIL Jalandhar being planned. Route plan and estimate of work sanctioned, DNIT has been sent to float tender as updated by PSTCL in 227th OCC
20	Sub-station	Commissioned: 6 Total: 6	Utilized: 4 Unutilized: 2	Roorkee (PG)-Pirankaliyar 220kV D/c line	Commissioned	Roorkee (PG)-Pirankaliyar 220kV D/c line commissioned in 2020 as intimated by PTCUL in 197th OCC
21	400/220kV Lucknow	Commissioned: 8	Utilized: 4 Unutilized: 4	Network to be planned for 2 bays	Commissioned	Lucknow -Kanduni, 220 kV D/C line work energized on 05.10.2023. Updated in 212th OCC by UPPTCL.      No planning for 2 no. of bays upated by UPPTCL in 196th OCC. The same has been communicated to Powergrid.
22	Sub-station		Utilized: 4 Unutilized: 2	Network to be planned for 2 bays	Commissioned	Gorakhpur(PG)- Maharajganj, 220 kV D/C line energized on 27.09.2023 updated by UPPTCL in 212th OCC
23	400/220kV Fatehpur Sub-station	Commissioned: 8 Under Implementation:2	Utilized: 6 Unutilized: 2 Under Implementation:2	Network to be planned for 2 bays	-	UPPTCL intimated that 02 no. of bays under finalization stage. In 201st OCC, UPPTCL intimated that it is finalized that Khaga s/s will be connected (tentative time 1.5 years).      No planning for 2 no. of bays updated by UPPTCL in 196th OCC. The same has been communicated to Powergrid.
	400/220kV Abdullapur Sub- station	Under Implementation:2	Utilized: 10 Unutilized: 0 Under Implementation:2	Abdullapur – Rajokheri 220kV D/c line	Commissioned	Ckt-1 commissioned at 16:13hrs on dated 06.08.24 & Ckt-2 commissioned at 20:10 hrs on dated 05.08.24. Updated in 223rd OCC by HVPNL
		Commissioned: 8	Utilized: 2	Panchkula – Pinjore 220kV D/c line     Panchkula – Scater 23 230kV D/c line	Commissioned	Updated in 218th OCC by HVPNL Energization date: 24.05.2024 updated by HVPNL in
	400/220kV Pachkula	Under tender:2	Unutilized: 4	Panchkula – Sector-32 220kV D/c line      Panchkula – Raiwali 220kV D/c line	Commissioned  Commissioned	220th OCC Updated in 194th OCC by HVPNL
			Under Implementation:2	Panchkula – Raiwaii 220kV D/c line      Panchkula – Sadhaura 220kV D/c line: Sep'23	Nov'25	Revised target date as confirmed by concerned XEN TS, Panchkula.Updated in 234th OCC by HVPNL
		Out of these 10 nos. 220kV				

SI. No.	Substation	Downstream network bays	Status of bays	Planned 220 kV system and Implementation status	Revised Target	Remarks
26	400/220kV Amritsar S/s	Commissioned:7 Approved in 50th NRPC- 1 no.	Utilized: 6 Under	Amritsar – Patti 220kV S/c line	-	Draft connectivity agreements for 220kV Rashiana- Amritsar has been received from CTU and the same under processing. Draft connectivity agreements for 220kV Patti-Amritsar line is under consideration by CTU. CTU is processing the agreement and PSTCL has provided with the requisite inputs/data to CTU. Updated in 232nd OCC by PSTCL.
		Total: 8	Implementation:2	Amritsar – Rashiana 220kV S/c line (2 bays shall be required for above lines. However, 1 unutilized bay shall be used for Patti and requirement of one additional bay approved for Rashiana by NRPC)	-	Draft connectivity agreements for 220kV Rashiana- Amritsar & 220kV Patti-Amritsar lines are under consideration by CTU. CTU is processing the agreement and PSTCL has provided with the requisite inputs/data to CTU. Updated in 232nd OCC by PSTCL.
27	400/220kV Bagpat S/s	Commissioned: 8 Total: 8	Utilized:6 Unutilized: 2	Bagpat - Modipuram 220kV D/c line	Commissioned	Updated in 201st OCC by UPPTCL
				LILO of 220 kV Nunamajra- Daultabad S/c line at 400 kV Bahadurgarh PGCIL	-	Proposal turned down by CEA.Updated in 230th OCC by HVPNL.
28	400/220kV Bahardurgarh S/s	Commissioned: 4 Approved: 4 Total: 8	Utilized:2 Unutilized: 2	Bahadurgarh - METL 220kV D/c line (Deposit work of M/s METL)	15.06.2026	Updated in 230th OCC by HVPNL.  Status: The work stands awarded to the M/s KRR and the execution work has been started at site. Partial route stands approved by the competant authority of the HVPNL. Further, 06 no. Foundation has been casted.
				Bahadurgarh - Kharkhoda Pocket B 220kV D/c line	30.11.2025	Updated in 234th OCC by HVPNL.  Status:  RoW issues which are being resolved with the help of Duty Magistrate.
29	400/220kV Jaipur (South) S/s	Commissioned: 4 Total: 4	Utilized:2 Unutilized: 2	LILO of 220 kV S/C Dausa – Sawai Madhopur line at 400 kV GSS Jaipur South (PG)	06.10.2025	Work order has been issued on 06.10.2023, work under progress as updated by RVPNL in 215th OCC
				Sohawal - Barabanki 220kV D/c line	Commissioned	Energization date: 14.04.2018 updated by UPPTCL in 196th OCC
	400/220kV Sohawal	Commissioned: 8	Utilized: 8	Sohawal - New Tanda 220kV D/c line	Commissioned	Energization date: 28.05.2019 updated by UPPTCL in 196th OCC
30	S/s	Total: 8		Network to be planned for 2 bays	Commissioned	Sohawal - Gonda 220kV S/c line (Energization date: 27.04.2020) updated by UPPTCL in 196th OCC     Sohawal - Bahraich 220kV S/c line (Energization date: 15.02.2021) updated by UPPTCL in 196th OCC
31	400/220kV, Kankroli	Commissioned: 6 Total: 6	Utilized: 4 Unutilized: 2	• 220 kV D/C Kankroli(PG) - Nathdwara line	Standard bid document has been finalized on 13.08.2024 and bid is under preparation as updated by RVPN in 222nd OCC.	
32	400/220kV, Manesar	Commissioned: 8 Total: 8	Utilized: 4 Unutilized: 4	Network to be planned for 2 bays	-	Status:- A proposal is being prepared for the creation of another 220kV D/C line from the 400kV substation Panchgaon (PG) to the 220kV substation Panchgaon (HVPNL), along with the LILO of one circuit of the 220kV D/C Panchgaon (PG) – Mau line at the 220kV substation Panchgaon to utilize two bays at the 400kV substation Panchgaon. The load flow study for this has already been completed.
33	400/220kV, Saharanpur	Commissioned: 6 Under Implementation:2 Total: 8	Utilized: 6 Unutilized: 0 Under Implementation:2	Network to be planned for 2 bays	Commissioned	Saharanpur(PG)-Devband D/c line (Energization date: 20.04.2023) updated by UPPTCL in 207th OCC
34	400/220kV, Wagoora	Commissioned: 10 Total: 10	Utilized: 6 Unutilized: 4	Network to be planned for 4 bays	-	PDD, J&K to update the status.
35	400/220kV, Ludhiana	Commissioned: 9 Total: 9	Utilized: 8 Unutilized: 1	Network to be planned for 1 bay	Commissioned	Direct circuit from 220 kV Lalton Kalan to Dhandari Kalan to be diverted to 400 kV PGCIL Ludhiana. Work completed , final agrrement is expected to be signed by May'24. Updated in 218th OCC by PSTCL.
36	400/220kV, Chamba (Chamera Pool)	Commissioned: 3 Under tender:1 Total: 4	Utilized:3 Unutilized: 0 Under tender:1	Stringing of 2nd ckt of Chamera Pool – Karian 220kV D/c line	Commissioned	Stringing of 2nd Circuit of Chamera Pool-Karian Tansmission line has been completed & terminal bay at 400/220 kV chamera pooling substation (PGCIL) is commissioned on 20.01.2024. Updated in 217th OCC by HPPTCL.
37	400/220kV, Mainpuri	Commissioned: 6 Under Implementation:2 Total: 8	Utilized: 6 Unutilized: 0 Under Implementation:2	Network to be planned for 2 bays	02 no. of bays under finalization stage updated by UPPTCL in 196th OCC. Mainpuri S/s planned. Land is not finalized, therefore timeline not available as intimated by UPPTCL in 201st OCC.	
38	400/220kV, Patiala	Commissioned: 8 Total: 8	Utilized: 6 Unutilized: 2	• 400 kV PGCIL Patiala - 220 kV Bhadson (D/C)	-	2 Nos. bays for 400 kV PGCIL Patiala - 220 kV Bhadson (D/C) line being planned. Construction of boundary wall has started at 220 kv ss bhadson.yard work could not be started as approval for dismantaling existing 517 no tress is pending at district level committee which is competent for giving approval of dismantling of trees. Chairman of committee is DC pataiala as updated by PSTCL in 233th OCC meeting

Status of ADMS implementation in NR:

SI. No.	State / UT	Status	Remarks									
1	DELHI	Scheme Implemented but operated in manual mode.	In 236th OCC meeting, Delhi SLDC representative stated that as informed by BRPL and BYPL, SCADA upgradation work of would be completed by Dec'25. Further, SCADA upgradation work of TPDDL would be completed by Dec'26.									
2	HARYANA	Scheme not implemented	Haryana SLDC intimated that as per Joint Roadmap of implementation of ADMS in Haryana supplied to NRPC vide memo dated 17.10.2023 (Annexure-II), the implementation plan was proposed to be carried out in two parts, as mentioned below:  PART-I: Control with Transmission Utility  PART-II: Control with Distribution Utility  It is pertinent to mention that as part of upcoming SCADA-EMS system i.e. upgradation of SCADA-EMS system, a feature in the name of LSS (Load Shedding Software)/ ADMS is part of the Technical Specification of project to be delivered. Therefore, the functionalities of ADMS application will be covered under 'Part-I: Control with Transmission Utility' will already be covered using the RTUs available at select substations along with the ADMS software being delivered by M/s GE under SCADA upgradation project.  Hence, there is no need to acquire a separate ADMS application & associated hardware for data centre for implementation of PART-I.  Further for Part -II a committee has been constituted for further finalization of the ADMS module with control with Discoms is under discussions for preparation of DPR.									
3	НР	Scheme not implemented	In 237th OCC meeting, HPSDLC representative informed that vide letter dated 25.10.2025 they have requested HPSEBL to expedite the feeder list. However, reply of HPSEBL is awaited. Further, they have also requested MD, HPSEBL for a suitable date for a meeting in this regard.									
4	PUNJAB	Scheme not implemented	In 236th OCC meeting, Punjab SLDC representative informed that testing of SCADA upgradation under ULDC phase III is underway. It is likely to be completed by Dec'25.									
5	RAJASTHAN	Under implementation	RVPN has pilot tested the logic of ADMS which is to be implemented for Rajasthan. In 232 OCC meeting, RVPN informed that 351 nos. of circuit breakers have been mapped to ADM all 351 circuit breakers tested upto yard individually. Total 650CBs are to be mapped phased manner.									
6	UP	Scheme implemented by NPCIL only	In 236th OCC meeting, UP SLDC representative stated that 300 No. of 132 KV Substations have been integrated with SCADA. SCADA upgradation under ULDC phase III is likely to be completed in the next 3 to 4 months. List of 33kV feeders to be mapped under ADMS is required from the Discoms. In the meeting held in Aug'25, UPSLDC had requested Discoms to provide the feeders list. Reminders were also sent to Discoms. However, 33 kV feeder list is still pending from the Discoms.  MS, NRPC asked UPSLDC to have and meeting with Discoms in its control areas and finalize of feeder list before next OCC meeting.  In 237th OCC meeting, UPSLDC representative mentioned that they are planning to have a									
7	UTTARAKHAND	Scheme not implemented	meeting with higher management of Discom's by the end of Nov'25.  i. UPCL has prepared a system architecture in which all the non-monitored sub-stions have been selected and 11kV feeders have been considered for ADMS operation. For the scheme, discom has also done group-wise selection of feeders and quantum of MW relief to be given for automatic demand response at 11kV level has also been decided. UPCL has awarded the tender for implementation of the aforementioned scheme to M/s Metergy Pvt.Ltd.  ii. As per the status report submitted by M/s Metergy Pvt.Ltd, the survey work of 30 nos. incomer sites have been completed and order has been placed by UPCL for hardware equipments.  iii. Uttarakhand SLDC informed that feeder list at 11kV level has been finalized and logic of ADMS implementation is under finalization.  iv. Uttarakhand has intimated that It is bring to your notice that installation MFT( Multi Function Transducers) at various interstate points at PTCUL Substations under ADRS Project of UPCL is in progress.  v. First Phase- Data Acquisition of 32 interstate points completed.  vi. Second Phase-95 distribution side Substation work is on progress.  vii In 230th OCC meeting Uttarakhand SLDC representative informed that Harbour installation and communication establishment has been done on 35 11kV feeders out of total 195 11kV feeders. The work is expected to be completed by December, 2025.									

### Status of availability of ERS towers in NR

		1	T	1			
SI. No.	Transmission Utility	Voltage Level (220kV/400kV/765k V/ 500 kV HVDC etc.)	Length of the transmission lines owned by the Utility (Ckt. Kms.)	Number of ERS Sets ( towers) available (Nos.)	ERS Set ( towers) required as per the Govt. norms.	Location	Remarks
1	PTCUL	400kV	418.394	NIL			Tender has been scraped due to single bidder.
		220kV	1045.135	NIL	1		
2	Powergrid NR-1	220 KV	1842.88	NIL	1		
2	r owergind (VIX-)	400 KV	11074.26	12 Towers	3	All 400kV ERS at Ballabhgarh	make-Lindsey
		765 KV	4721.85	15 Towers	1	All 765kV ERS at Meerut	Make-SBB
		500 KV HVDC	653.88	NIL	1		
		800 KV HVDC	416.58	NIL	1		
3	Powergrid NR-2	66 KV	37.56	Nil	1		ERS tower available for 400KV rating can be
		132 KV	262.7	Nil	1		used in place of lower as well as higher voltage Towers. In case used for 765KV Line, No of
		220 KV	2152	Nil	1		towers can be erected will reduce due to
		400 KV	8097.3	02 Set (32 Towers)	2	Kishenpur & Jalandhar	increase in Tower Hight.
		765 KV	337.5	Nil	1		
4	Powergrid NR-3		2205	NIL	1		_
		500KV HVDC	2566	NIL	1		_
		765KV	4396	NIL	1		400KV ERS will be also be used in other
		400KV	12254	26 Towers	3	Kanpur	voltage level lines
		220KV	1541	NIL	1		
		132KV	207	NIL	1		
5	PARBATI KOLDAM TRANSMISSION COMPANY LIMITED	400kV	457	NIL	1		Procurement under process.
6	PATRAN TRANSMISSION COMPANY LTD	400kV	0.4	NIL	1		Not available, will tie up based on the
7	NRSS-XXIX TRANSMISSION LTD	400kV	853	NIL	1	is moved across	requirements in future. However the parent company IndiGrid owns one set of ERS for all
8	GURGAON PALWAL TRANSMISSION LTD	400kV	272	NIL	1	region	five regions.
9	RAPP Transmission Company Limited.	400kV	402	NIL	1	9	
10	NRSS XXXVI Transmission Limited	400kV	301.924	NIL	1		Element I - Operational comprising of 3 kms. Element II - Work Under Progress comprising of 221.924 kms. Element II - Work Under Progress comprising of 77 kms.
11	HPPTCL	220 kV	659	NIL	1		
		400 kV	75.7	NIL	1		
12	RVPN	132 kV	18969.958		4	0444 500	ERS proposed: 01 Set at 400 kV GSS,
		220 kV	16227.979	7	3	01 No. ERS available at 220	Jodhpur. 01 set at 400 kV GSS Ajmer.
		400 kV	6899.386	1	2	kV GSS	
		765 kV	425.498		1	Heerapura, Jaipur	
					1		

SI. No.	Transmission Utility	Voltage Level (220kV/400kV/765k V/ 500 kV HVDC etc.)	Length of the transmission lines owned by the Utility (Ckt. Kms.)	Number of ERS Sets ( towers) available (Nos.)	ERS Set ( towers) required as per the Govt. norms.	Location	Remarks
13	DTL	220kV	915.498	NIL	1	400kV Bamnauli	ERS tower available for 400KV rating can also be used for lower voltage lines as well
		400kV	249.19	02 Sets (32 towers)	1	Sub station	be used for lower voltage liftes as well
14	JKPTCL	15511		(32 33 (32 33 33 3)			JKPTCL, Jammu: being procured JKPTCL, Kashmir:10 tower procured (out of which 3 on loan to JKPTCL, Jammu)
15	HVPN						HVPN has apprised that purchase order for procurement of 2 sets of Emergency Restoration System (ERS) in HVPNL has been issued to M/s Jost's Engineering Company Ltd., Mumbai
16	PSTCL	400 kV	1666.43	2	2		
	LIPPTOL 4 M	220 kV	7921.991				
17	UPPTCL 1- Meerut	132KV	27508.321	24 Nos(15 Running+9		400 kV S/s Gr.	ERS will be also be used in other voltage level
		220KV	14973.453	Angle)		Noida	lines.
	LIBRTOL O.B.	400KV	6922.828				
	UPPTCL 2-Prayagraj	765KV	839.37	1			
		400KV	1804.257	24 Towers		220 kv S/s phulpur	ERS will also be used in other voltage lines.
		220KV	2578.932	_			
10	DOWED NIK	132KV	4714.768				
18	POWERLINK						
19	POWERGRID HIMACHAL TRANSMISSION LTD						
20	Powergrid Ajmer Phagi Transmission Limited						
21	Powergrid Fatehgarh Transmission Limited						
22	POWERGRID KALA AMB TRANSMISSION LTD						
23	Powergrid Unchahar Transmission Ltd						
24	Powergrid Khetri Transmission Limited						
25	POWERGRID VARANASI TRANSMISSION SYSTEM LTD						
26	ADANI TRANSMISSION INDIA LIMITED		2090				Make-Lindsey ERS set available for 400KV & 500KV rating can be used for lower as well as higher voltage
27	BIKANER KHETRI TRANSMISSION LIMITED FATEHGARH BHADLA TRANSMISSION LIMITED		482	1 Set (12 towers)	1 set (12 towers)	Sami (Gujarat)	Towers. In case used for 765KV Line, No of
28		500 kV HVDC 400 kV HVAC	291				towers can reduce due to increase in Tower Height & nos of conductors.
29	NRSS-XXXI(B) TRANSMISSION LTD	400 kV	577.74	Not Available	Not Available		Tied up with M/s INDIGRID for providing ERS on need basis.
30	ARAVALI POWER COMPANY PVT LTD	765 kv HVAC					

<sup>\*</sup>The transmission Utility with line length less than 500 ckt kms (of 400 KV lines) may be given option either to procure ERS or have agreement with other transmission utilities for providing ERS on mutually agreed terms, when need arises. (As per MoP directions)

#### MIS Report for Status of Islanding Schemes

	SI. No.	Islanding Scheme	SLDC	Status	Submission of Self Certification of Healitheness		SCADA Display Page	Remarks
ſ	1	NAPS IS	UP	Implemented	Yes (08-10-2021)	Yes	Yes	-
Ī	2	RAPS IS	Rajasthan	Implemented	16-Aug-21	Yes	Yes	List of officials in-charge, format for generation, islanding scheme sld and relays in RAPP IS submitted by RVPN on 04.12.2021.
	3	Delhi IS	Delhi	Implemented				
	4	Lucknow-Unchahar IS	UP	Implemented				UPPTCL representative apprised forum that 132 KV S/S Husainganj line is on H-pole therefore OPGW laying is not possible on this line. However, the data of 132 KV S/S Husainganj is made available through GPRS.

Under Implementation/ Newly Proposed/Under Discussion Timelines Status - Proposed/Actual

Design Approval Procurement DPR for PSDF funding (Required / Not Required) Details of progress In 236th OCC meeting MS, NRPC asked PSTCL to get the designing aspect of both the islanding schemes in Punjab control area vetted by Punjab SLDC and thereafter submit the proposal to NRPC with the undertaking that earlier PSDF funding was not availed for these schemes. In the 237th OCC meeting, the Punjab SLDC representative informed both schemes would be taken up for discussion in their State OCC meeting scheduled on 20.11.2025. Punjab 20.11.2025.

Scheme has been approved in 71th NRPC meeting held on 29.01.2024. In 228th OCC, UPPTCL representative apprised forum that management is of view that procurement of UFRs for the Lafipur-Agra islanding scheme should be explored through PSDF funding. During the meeting held on 07.03.2025, PSDF Secretariat raised some queries regarding the scheme and UPPTCL was asked to submit their board approval. In 238th OCC meeting, UPPTCL representative informed the forum that the proposal has been resubmitted to the PSDF Secretariat for funding under PSDF. following approval by the UPPTCL Board 2 Agra IS UP Under Implementation Scheme has been approved in 60th NRPC meeting held on 30.11.2022. In 228th OCC, RRVPNL representative mentioned that they have submitted their proposal of Jodhpur-Barmer-Rajwest islanding scheme to PSDF Secretariat on 16.01.2025 for PSDF funding. During the meeting held on 07.03.2025, PSDF Secretariat raised some queries regarding the scheme. In 232nd OCC, RRVPNL representative informed that responses to these queries have been replied on 30.05.2025. Jodhpur-Barmer-Rajwest IS Scheme has been approved in 60th NRPC meeting held on 30.11.2022. In 228th OCC, RRVPNL representative mentioned that DPR for implementation of Suratgarh islanding scheme would be submitted after confirmation of status of PSDF funding from PSDF Sectt for Jodhpur-Barmer Rajwest IS. Suratgarh IS Under Implementation Scheme has been approved in 60th NRPC meeting held on 30.11.2022. In 236th OCC meeting MS, NRPC asked PSTCL to get the designing aspect of both the islanding schemes in Punjab control area vetted by Punjab SLDC control area vetted by Punjab SLDC and thereafter submit the proposal to NRPC with the undertaking that earlier PSDF funding was not availed for these schemes. In the 237th OCC meeting, the Punjab SLDC representative informed both schemes would be taken up for discussion in their State OCC meeting scheduled on 20.11.2025. 5 Punjab Under Imple Rajpura IS Scheme has been approved in 60th NRPC meeting held on 30.11.2022. In 231st OCC, HPSLDC representative of State PSDF has provided approval for State PSDF funding for implementation of proposed UFs scheme for Kullu- Manail islanding scheme for Kullu- Manail islanding scheme for Kullu- Manail islanding scheme in the meeting held on 22nd April, 2025. In the 237th OCC meeting, the HPSLDC representative informed that HPSEBL has awarded the tender for implementation of both schemes on 27.10.2025, with a work completion period of six months. Kullu-Manali-Mandi IS HP Under Implementation Scheme has been approved in 60th NRPC meeting held on 30.11.2022. In 232nd OCC, HPSLIDC representative informed that HPSEBL has done the testing and requisite frequency settings of their generators for Shimia-Solan islanding scheme. HPSLIDC representative further informed that the Monitoring committee of State PSDF funding for implementation of proposed UFR scheme for Shimia-Solan islanding scheme in the meeting held on 22nd April, 2025. In the 237th OCC meeting, the HPSLIDC representative informed that HPSEBL has awarded the tender for implementation of both schemes on 27.10.2025, with a work completion period of six months. Shimla-Solan IS HP Under Implementation

S No.	Name of Plant	Unit	Installed		Make of	COD		GT Details  Tap Ratio of						Mode of Fuel Transpor t (Pit	Name of Utility	Sector	Control	Tyne		and Reactive		Control Techi	ent of Reac Capability a nical Standa connectivi	ards for	Model Validation the complete System in	d Excitation	Turbine/G	iovernor an	d verification of d Load Control quency Control ns.	performa	ng of Gover ance and Au eration Con	tomatic	Revised Simulation	on Models		
3.1101		O.III.	Capacity	Rating	Units		Voltage Ratio	GT MVA Capacity	Tap Ratio of GT (Present Tap/Total Taps)	Head/No n Pit- head)		Sector	Area	te (de	Area t	Area	Area	" Туре	t (d	ea ''	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/ yyyy)		Tentative Schedule date	Last tested on (dd/mm/yyyy)	Tentative Schedule date	Last tested on (dd/mm/y yyy)	Whether due?	Calcadada dasa	Last tested on (dd/mm/ yyyy)	Whether	Tentativ e Schedule date	Whether Revised Models Submitted?	Remarks
1																																				
2																																				
3																																				
4																																				
5																																				
6																																				
7																																				
8																																				
9																																				
10																																				

# Hydro Generators

Name of Plant	Unit	Installed			con		GT Deta	ils	Type (Pondag	Name of Heilitus	Sector	Control		nd Reactive bility assess		Control C		s per CEA rds for		lete Generat tion System	or and	verification and Load Power/f	Control or requency (	Governor Active	performa		Automatic
value of Flant	Oille	Capacity	Rating	Units	COD			Tap Ratio of GT (Present Tap/Total Taps)	e/RoR etc.)	Name of Junty	Jector	Area	Last tested on (dd/mm/ yyyy)		Tentative Schedule date	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)			Last tested on (dd/mm/y yyy)	Whether due?	Schedule	on	Whether due?	Tentativ e Schedule date
Mahi Power House-I	UNIT-I	25 MW	27.778 MVA	BHEL, Bhopal	22/01/1986	11kV/13 2kV	31.5 MVA	3/5	RoR	RVUN	Power/ Energy																
Mahi Power House-I	UNIT-II	25 MW	27.778 MVA	BHEL, Bhopal	06/02/1986	11kV/13 2kV	31.5 MVA	3/5	RoR	RVUN	Power/ Energy																
																											_
																											+
1	House-I Mahi Power	Mahi Power House-I  Wahi Power UNIT-I	Mahi Power UNIT-I 25 MW Mahi Power UNIT-I 25 MW	Mahi Power UNIT-I 25 MW 27.778 Mahi Power UNIT-I 25 MW 27.778	Mahi Power UNIT-II 25 MW 27.778 BHEL, Mahi Power UNIT-II 25 MW 27.778 BHEL	Mahi Power House-I UNIT-I 25 MW 27.778 BHEL, Bhopal 22/01/1986	Mahi Power	Capacity   Rating   Units   COD	Capacity   Rating   Units   CUD	Mahi   Power	Mahi   Power	Mahi Power   UNIT-I   25 MW   27.778   BHEL   06/03/1086   11kV/13   31.5   3	Amail   Power	Amail   Power	Mahi Power   Unit-    25 MW   27.778   BHEL   Mahi Power   Unit-    27.778   BHEL   06/03/096   11kV/13   31.5   2/6   0.000	Mahi Power   UNIT-    25 MW   27.778   BHEL   06/03/1096   11kV/13   31.5   2/F   0.84   0.	ame of Plant Unit Installed Capacity Rating Units Installed Capacity Floring GT MVA Rating Units Power House-II Unit-II 25 MW 27.778 BHEL, 06/03/1986 11kV/13 31.5 2/6 RoR ROR RVUN Power/ MANIPOWER UNIT-II 25 MW 27.778 BHEL, 06/03/1986 11kV/13 31.5 3/6 ROR ROR RVUN Power/ MANIPOWER UNIT-II 25 MW 27.778 BHEL, 06/03/1986 11kV/13 31.5 3/6 ROR ROR RVUN Power/ Energy Washington Power/ MANIPOWER UNIT-II 25 MW 27.778 BHEL, 06/03/1986 11kV/13 31.5 3/6 ROR RVUN Power/ Energy	Amail   Power	## Amin Power House-II Unit- 25 MW 27.778   BHEL   22/01/1986   11kV/13   31.5	Amail   Power     Unit   25 MW   27.778     BHEL     22/01/1986   21 kW/13   31.5   21.5   Ror   Ror	Installed Capacity   Install	Amail   Power   House-II   Unit   25 MW   27.778   BHEL   22/01/1986   11kV/13   31.5   21.5   Ror   Ror	ame of Plant Unit Installed Capacity WA Rating Units Power House-II Unit Installed Last Easted On House-II Unit Installed Capacity WA Rating Units Power House-II Unit Installed Capacity WA Rating Units Power House-II Units Power House-II Units Power House-II Units Power Water Units Power Water Units Power House-II Units Power Water Water Power Water Units Power Water Wa	## Amin Power House-II Unit   18   18   18   18   19   19   19   19	Amail   Power     Unit     25 MW   27.778     BhEL     22/01/1986     11kV/13   31.5   21.5     Ror     Ror   Ror     Ror   Ro	Amail   Power   House-II   Unit   25 MW   27.778   BHEL   22/01/1986   11kV/13   31.5   31.	Amail   Power   House-II   Unit   25 MW   27.778   BHEL   22/01/1986   11kV/13   31.5   2/5   Ror   Ror

Revised Simulation Models

Vhether Revised

As per guidelines the OEM representative must remain present at the time of Generator periodic testing hence looking to the age and present status of Units at Mahi HH-I, Letters Dated 12/07/2024 and 19/12/2024 have been sent to the OEM M/S BHEI, Bhopal, and accordingly the plan may be scheduled.

## **Nuclear Generators**

	No.	Name of Plant	Unit	Installed		Make of	COD		GT Deta	ails	Туре	Name of Utility	Sector	Control	Туре		and Reactiv		Control C	ent of Reac Capability a lical Standa connectivi	as per CEA ards for	Model Validati for the com Exci mode		ator and m	verification and Loa Power/	el Validatio n of Turbine d Control o frequency Functions.	/Governor r Active Control	performa	ng of Gove nce and Au eration Cor	utomatic	Revised Simulatio	n Models
			O.III.	Capacity	Rating	Units	600	Voltage Ratio	GT MVA Capacity	Tap Ratio of GT (Present Tap/Total Taps)	Турс	The state of the s	, seas.	Area	Пре	Last tested on (dd/mm yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy	Whether due?	Tentative Schedule date	Last tested on (dd/mm/y yyy)	Whether due?	Scheaule	Last tested on (dd/mm/ yyyy)	Whether	Tentativ e Schedule date	Whether Revised Models Submitted?	Remarks
_																	-	-														
$\vdash$				-									-	-			+	-														

### Gas Based Generators

S No.	Name of Plant	Unit	Installed		Make of	COD		GT Deta		Name of Utility	Sector	Control	Туре		nd Reactiv bility asses	e Power	Control ( Techr		as per CEA ards for			ator and m	verification and Load Power/	l Validatio of Turbine d Control of frequency Functions	e/Governor or Active Control	performa	ng of Gove nce and A eration Co	utomatic	Revised Simulatio	on Models
5.110.		S.int	Capacity	Rating	Units		Voltage Ratio	GT MVA Capacity	Tap Ratio of GT (Present Tap/Total Taps)	name or ount,	Section	Area	Турс	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy	Whether due?	Tentative Schedule date	Last tested on (dd/mm/y yyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/ yyyy)	Whether due?		Whether Revised Models Submitted?	Remarks

# Renewable Energy Plants

S. No	Name of Plant	Pooling Station Name	Installed Capacity	Type (Solar/Wind)	COD	Owner	Sector	Control Area	Inverter/ WTG Make	Inverter/ WTG Model	PPC Make	Real and React	ive Power C Generator	apability for	Power Plant Co	ntroller Fu	nction Test	Frequenc	cy Response	Test	Active Power	Set Point c	hange test	Reactive Power Q) Set	(Voltage / Po	ower Factor / e test
									make	mouci		Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	wnetner	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date
	_																									$\vdash$
	-																									
	+																									

Revised Simulation Models

Whether Revised Models Submitted?

# **HVDC** Links

S. No	Name of Link	Type (LCC/VSC/Bac k-to-Back)	HVDC_Voltag e (kV)	Conver	ter-1	Conve	rter-2	Master Converter Station	Pole_numbe	Lengt h	Capacit y (MW)	Owner		Forward Directi	ion		Reverse Directi	on		ver Controll apability IVDC/FACTS			lequacy assessme ondition, in consu NLDC.		Revised Simulation	ın Models
		K-to-backy		Station Name	Region	Station Name	Region	Station		(Kill)			Maximum Capacity	Minimum Capacity         Ground_return_capacity           500         1250           500         1250		Maximum Capacity	Minimum Capacity	Ground_return_ capacity	Last tested on (dd/mm/yyyy)	Whether	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Whether Revised Models Submitted?	Remarks
1			500	APL-Mundra	WR	Mohindargarh	NR		1	989	1,250	ATIL	150	500	1250					Due			Due		1	
2			500	APL-Mundra		Mohindargarh			2	989	1,250	ATIL	150	500	1250					Due			Due		1	
3		LCC	800	Champa_HVDC	WR	Kurukshetra	NR	Champa_HVDC	1	1,306	1,500	POWERGRID	150	1,500	DMR path	NA	NA	NA		Due	Apr-2025		Due		1	
4		LCC	800	Champa_HVDC	WR	Kurukshetra	NR	Champa_HVDC	2		1,500	POWERGRID	150	1,500	DMR path	NA	NA	NA NA		Due	Apr-2025		Due		1	
5		LCC	800	Champa_HVDC	WR	Kurukshetra	NR	Champa_HVDC	3	1,306	1,500	POWERGRID	150	1,500	DMR path	NA	NA	NA NA		Due	Apr-2025		Due		1	
6		LCC	800	Champa_HVDC	WR	Kurukshetra	NR	Champa_HVDC	4	1,306	1,500	POWERGRID	150	1,500	DMR path	NA	NA	NA NA		Due	Apr-2025		Due		1	
																									1	
																									1	
																									1	
																									1	

## STATCOMs/SVCs

S.No	Station	Statcom	Capacity (MVAR)	Owner	Make	Reactive Powe	r Controller (F or HVDC/FACT		Filter bank adeq present grid con			Validation of	response by FAC per settings.	TS devices as
						Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date
1	Kurukshetra	TCR	500	POWERGRID	GE Vernova T&D	NA	NA	NA	NA	NA	NA	Nov-2023	No	Sep-2028
2	Fatehgarh-2	STATCOM	.+/-600	POWERGRID	SIEMENS	Oct-2023	No	Sep-2028	NA	NA	NA	Oct-2023	No	Sep-2028
3	Bhadla-2	STATCOM	.+/-600	POWERGRID	SIEMENS	Jun-2023	No	May-2028	NA	NA	NA	Jun-2023	No	May-2028
4	Bikaner-2	STATCOM	.+/-300	POWERGRID	SIEMENS	Jul-2023	No	Jun-2028	NA	NA	NA	Jul-2023	No	Jun-2028

Revised Simulation Models

Vhether Revised

## FSCs/TCSCs

S. No	End 1	End 2	Line No.	Compensato r Location	Make	Fixed Compensation	Variable Compensation	Variable Compensatio	Reactive Power for	Controller (RI HVDC/FACTS		based on		assessment condition, in h NLDC	Validation of re	sponse by FAC per settings.	TS devices as	Revised Simulation Models	
140			NO.	recedion		Compensation	Positive	n Negative	Last tested on (dd/mm/yyyy)		Tentative Schedule date	Last tested on (dd/mm/ yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Whether Revised Models Submitted?	
					· ·														

## Series Reactor

	S.No	End 1	End 2	Line No.	End	Capacity	Make	Reactive Power for	Controller ( HVDC/FAC		Filter bank adeq present grid cond			Validation of res	ponse by FA er settings.	CTS devices as	Revised Simulati	on Mode
								Last tested on (dd/mm/yyyy)			Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Whether Revised Models Submitted?	Rema
ı	1							(,) 11111	d/mm/yyyy) due? Sc		(,, 1111)	Luc.	zanazaic dute	(,) 11111				

#### **Hydro Generators**

S. N	o. Name of Plant	Unit	Installed	MVA Rating	Make of Units	COD		GT Details		Туре	Name of Utility	Sector	Control Area	Real and Reac	tive Power Capability sessment.		Reactive Power Control CEA Technical Standards for onnectivity	Model Validation a complete Genera model		ation System	Turbine/Governor	ion and verification of and Load Control or Acti ncy Control Functions.	e Testing of 0	Governor per	formance	Automati	c Generation Co	entrol	Revised Simula
3.14	. Realite of Plant	Oint	Capacity	MVA Rating	make of ones		Voltage Ratio	GT MVA Capacity	Tap Ratio of GT (Present Tap/Total Taps)	. (Pondage/RoR etc.)	Name of Outley	Sector	Consol Area	Last tested on (dd/mm/yyyy)	Whether Tentative due? Schedule da	Last tested on te (dd/mm/yyyy)	Whether due? Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due? Schedule da	Last tested on e (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Whether Revised Models Submitted?
1	Bairasiul	UNIT-I	60 MW	67 MVA	M/S BHEL	18.05.1980	11kV/220kV	25 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
2	Bairasiul	UNIT-II	60 MW	67 MVA	M/S BHEL	19.05.1980	11kV/220kV	25 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
3	Bairasiul	UNIT-III	60 MW	67 MVA	M/S BHEL	13.09.1981	11kV/220kV	25 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
4	Salal	UNIT-I	115 MW	127.8 MVA	M/S BHEL	November'87	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
5	Salal	UNIT-II	115 MW	127.8 MVA	M/S BHEL	November'87	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
6	Salai	UNIT-III	115 MW	127.8 MVA	M/S BHEL	November'87	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
7	Salai	UNIT-IV	115 MW	127.8 MVA	M/S BHEL	March'93	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
8	Salai	UNIT-V	115 MW	127.8 MVA	M/S BHEL	May'94	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
9	Salai	UNIT-VI	115 MW	127.8 MVA	M/S BHEL	February'95	11kV/220kV	43.33 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
10	Tanakpur	UNIT-I	31.4 MW	45 MVA	M/S BHEL	31.03.1992	11kV/220kV	49.5 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
11	Tanakpur	UNIT-II	31.4 MW	45 MVA	M/S BHEL	06.04.1992	11kV/220kV	49.5 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
12	Tanakpur	UNIT-III	31.4 MW	45 MVA	M/S BHEL	04.04.1992	11kV/220kV	49.5 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
13	Chamera-I	UNIT-I	180 MW	200 MVA	GE, Canada	28.04.1992	13.8KV/400 KV	75 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
14	Chamera-I	UNIT-II	180 MW	200 MVA	GE, Canada	25.04.1993	13.8KV/400 KV	75 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
15	Chamera-I	UNIT-III	180 MW	200 MVA	GE, Canada	22.04.1994	13.8KV/400 KV	75 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
16	Uri-I	UNIT-I	120 MW	136 MVA	ABB	10.04.1997	13.8KV/400 KV	50 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
17	Uri-I	UNIT-II	120 MW	136 MVA	ABB	27.01.1997	13.8KV/400 KV	50 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
18		UNIT-III	120 MW	136 MVA	ABB	03.03.1997	13.8KV/400 KV			RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	-	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202			Jan-Feb 2026			Jan-Feb 2026	
19	Uri-I	UNIT-IV	120 MW	136 MVA	ABB	13.03.1997	13.8KV/400 KV	50 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
20	Chamera-II	UNIT-I	100 MW	111.1 MVA	GE	04.10.2003	11KV/400 KV	41 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
21		UNIT-II	100 MW	111.1 MVA	GE	05.12.2003	11KV/400 KV	41 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202			Jan-Feb 2026			Jan-Feb 2026	
22		UNIT-III	100 MW	111.1 MVA	GE	26.02.2004	11KV/400 KV	41 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	+	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
23		UNIT-I	130 MW	145 MVA	GEC ALSTHOM	28.03.2007	11KV/400 KV	48.33 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
24	Dulhasti	UNIT-II	130 MW	145 MVA	GEC ALSTHOM	28.02.2007	11KV/400 KV	48.33 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
25		UNIT-III	130 MW	145 MVA	GEC ALSTHOM	18.03.2007	11KV/400 KV	48.33 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
26		UNIT-I	70 MW	78 MVA	Alstom/GE	14.10.2005	11kV/220kV	29 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	-	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
27		UNIT-II	70 MW	78 MVA	Alstom/GE	01.09.2005	11kV/220kV	29 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	-	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
28		UNIT-III	70 MW	78 MVA	Alstom/GE	28.07.2005	11kV/220kV	29 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
29		UNIT-IV	70 MW	78 MVA	Alstom/GE	26.07.2005	11kV/220kV	29 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202			Jan-Feb 2026			Jan-Feb 2026	
30		UNIT-I	40 MW	50 MVA	M/S BHEL	27.06.2010	11kV/132kV	50 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
31		UNIT-II	40 MW	50 MVA	M/S BHEL	10.07.2010	11kV/132kV	50 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
32		UNIT-III	40 MW	50 MVA	M/S BHEL	27.07.2010	11kV/132kV	50 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202			Jan-Feb 2026			Jan-Feb 2026	
33		UNIT-I	60 MW	67 MVA	Alstom	25.09.2013	11KV/400 KV	25 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
34		UNIT-II	60 MW	67 MVA	Alstom	25.11.2013	11KV/400 KV	25 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5	-	Jan-Feb 2026			Jan-Feb 2026	
35		UNIT-III	60 MW	67 MVA	Alstom	27.09.2013	11KV/400 KV	25 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202			Jan-Feb 2026			Jan-Feb 2026	
36	Uri-II	UNIT-IV	60 MW	67 MVA	Alstom	02.02.2014	11KV/400 KV	25 MVA		RoR	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
37		UNIT-I	77 MW	85.56 MVA	Alstom	27.06.2012	11kV/220kV	32 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202		Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	
38	Chamera-III	UNIT-II	77 MW	85.56 MVA	Alstom	10.06.2012	11kV/220kV	32 MVA		Pondage	NHPC	Power/Energy	Northern		Yes Jan-Feb 202	6	Jan-Feb 2026			Jan-Feb 2026		Jan-Feb 202	5		Jan-Feb 2026			Jan-Feb 2026	

39	Chamera-III	UNIT-III	77 MW	85.56 MVA	Alstom	07.06.2012	11kV/220kV	32 MVA		Pondage	NHPC	Power/Energy	Northern		Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026		1	Jan-Feb 2026			Jan-Feb 2026
40	Parbati-III	UNIT-I	130 MW	145 MVA	M/S BHEL	17.02.2014	13.8KV/400 KV	53 MVA		Pondage	NHPC	Power/Energy	Northern		Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
41	Parbati-III	UNIT-II	130 MW	145 MVA	M/S BHEL	27.02.2014	13.8KV/400 KV	53 MVA		Pondage	NHPC	Power/Energy	Northern		Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
42	Parbati-III	UNIT-III	130 MW	145 MVA	M/S BHEL	15.03.2014	13.8KV/400 KV	53 MVA		Pondage	NHPC	Power/Energy	Northern		Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
43	Parbati-III	UNIT-IV	130 MW	145 MVA	M/S BHEL	22.05.2014	13.8KV/400 KV	53 MVA		Pondage	NHPC	Power/Energy	Northern		Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
44	Kishanganga	UNIT-I	110 MW	122.22 MVA	M/S BHEL	13.03.2018	13.8KV/220 KV	45 MVA		Pondage	NHPC	Power/Energy	Northern	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
45	Kishanganga	UNIT-II	110 MW	122.22 MVA	M/S BHEL	21.03.2018	13.8KV/220 KV	45 MVA		Pondage	NHPC	Power/Energy	Northern	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
46	Kishanganga	UNIT-III	110 MW	122.22 MVA	M/S BHEL	30.03.2018	13.8KV/220 KV	45 MVA		Pondage	NHPC	Power/Energy	Northern	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026	03/01/2018	Yes	Jan-Feb 2026			Jan-Feb 2026			Jan-Feb 2026
47	Parbati-II	UNIT-I	200 MW	222.22 MVA	M/S BHEL	01.04.2025	13.8KV/400 KV	82 MVA		Pondage	NHPC	Power/Energy	Northern	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030
48	Parbati-II	UNIT-II	200 MW	222.22 MVA	M/S BHEL	01.04.2025	13.8KV/400 KV	82 MVA		Pondage	NHPC	Power/Energy	Northern	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030
49	Parbati-II	UNIT-III	200 MW	222.22 MVA	M/S BHEL	01.04.2025	13.8KV/400 KV	82 MVA		Pondage	NHPC	Power/Energy	Northern	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030
50	Parbati-II	UNIT-IV	200 MW	222.22 MVA	M/S BHEL	16.04.2025	13.8KV/400 KV	82 MVA		Pondage	NHPC	Power/Energy	Northern	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No	2030	March/April 2025	No		March/April 2025	No	2030	March/April 2025	No	2030
																											_				
51		1	250 MW	278 MVA		09.07.2007	420/15.75 kV	306	0.4 (2/5)																						
52	Tehri HPP(4*250 MW)	2	250 MW	278 MVA	Power Machine	30.03.2007	420/15.75 kV	306	0.4 (2/5)		THDC India	Power Gonomi	Northern		V	Mar-26	_	Van	Mar-26	_	Ven	Mar-26	Anr. 22	No	Mar-28	Ans. 22	No	Ma- 20	Mar-2021	V	Mar-26
53	1 cmi fipp (4-230 MW)	3	250 MW	278 MVA	r ower Machine	09.11.2006	420/15.75 kV	306	0.4 (2/5)		Limited	Power Generation	Nonnem	_	Yes	Mar-20	-	Yes	Har-20	-	Yes	Mar-20	Apr-23	NO	Mar-28	Apr-23	No	Mar-28	MBF-2021	Yes	Mar-20
54		4	250 MW	278 MVA		22.09.2006	420/15.75 kV	306	0.4 (2/5)																						
55	NJHPS					18.05.2004					SIVN		NRLDC	18.02.2023	No		18.02.2023	No		18.02.2023	No		05.05.2022	No		09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
56	NJHPS	2	250 MW 250 MW	278 MVA 278 MVA		06.05.2004					SJVN		NRLDC	28.02.2023	No	-	28.02.2023	No No	-	28.02.2023	No	-	05.05.2022	No No	-	09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
57	NJHPS	3	250 MW	278 MVA	EUCONA (Voith Siemens(Germany),	31.03.2004	15.75kV/				SIVN		NRLDC	20.02.2023	No		20.02.2023	No		20.02.2023	No		05.05.2022	No		09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
58	NJHPS	4	250 MW	278 MVA	GE Hydro (Oslo/Norway), Alstom(Germany), VA	30.03.2004	15.75kV/ 400kV	3 x 102 MVA	Tap Ratio - 2/S	RoR	SIVN	Power/Energy	NRLDC	19.02.2023	No	-	19.02.2023	No	-	19.02.2023	No	-	05.05.2022	No	-	09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
59	NJHPS	5	250 MW	278 MVA	Tech(Italy), BHEL(India)}	06.10.2003					SIVN		NRLDC	10.02.2023	No	-	10.02.2023	No	-	10.02.2023	No	-	05.05.2022	No	-	09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
60	NJHPS	6	250 MW	278 MVA		02.01.2004					SJVN		NRLDC	11.02.2023	No	-	11.02.2023	No	-	11.02.2023	No	-	03.11.2023	No	-	09.02.2021	Yes	08.02.2026	09.02.2021	Yes	08.02.2026
61		1	25 MW								SJVN		NRLDC	June. 2023	Yes	June. 2028	June. 2023	Yes	June. 2028	June. 2023	Yes	June. 2028	Nov. 2023	Yes	Nov. 2028	Nov. 2023	Yes	Nov. 2028			
62		2	25 MW								SIVN		NRLDC NRLDC	June. 2024	Yes Yes	June. 2028 June. 2028	June. 2024	Yes Yes	June. 2028	June. 2024	Yes	June. 2028 June. 2028	Nov. 2023 Nov. 2023	Yes	Nov. 2028 Nov. 2028	Nov. 2023 Nov. 2023	Yes	Nov. 2028 Nov. 2028			
63 64	Rampur HPS, SJVNL	4	25 MW								SIVN	Power/Energy	NRLDC	June. 2025 June. 2026	Yes	June. 2028 June. 2028	June. 2025 June. 2026	Yes	June. 2028 June. 2028	June. 2025 June. 2026	Yes Yes	June. 2028 June. 2028	Nov. 2023 Jun. 2022	Yes	Nov. 2028 Jan. 2027	Nov. 2023 Jun. 2022	Yes Yes	Nov. 2028 Jan. 2027			
65		5	25 MW								SJVN		NRLDC	June. 2027	Yes	June. 2028	June. 2027		June. 2028	June. 2027	Yes	June. 2028	Jun. 2022	Yes	Jan. 2027	Jun. 2022	Yes	Jan. 2027			
66		6	25 MW								SIVN		NRLDC	June. 2028	Yes	June. 2028	June. 2028	Yes	June. 2028	June. 2028	Yes	June. 2028	Jun. 2022	Yes	Jan. 2027	Jun. 2022	Yes	Jan. 2027			
67		1	261.25 MW								JSW Hydro		NRLDC		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027			
68	Karcham Wangtoo Hydro-	2	261.25 MW								JSW Hydro	Power/Energy	NRLDC		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to			
69	Electric Plant	3	261.25 MW								JSW Hydro	. ower/Energy	NRLDC		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027			
70		4	261.25 MW								JSW Hydro		NRLDC		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027		Yes	Dec 2026 to Feb 2027			
71	AD Hydro	Unit-1	96MW	106.667	BHEL	16.09.2010	11kv/	135MVA	4/9	ROR	AD Hydro	Power/	NRLDC			Nov 26			Nov 26	02/09/2021		Nov 26	07/10/2021		Nov 26	N.A	N.A	N.A	N.A	N.A	N.A
72	Power Ltd.  AD Hydro	Unit-2	96MW	MVA 106.667 MVA	BHOPAL BHEL BHOPAL	18.09.2010	220kv	135MVA	4/9	ROR	AD Hydro	Energy Power/	NRLDC			Nov 26			Nov 26	02/09/2021		Nov 26	07/10/2021		Nov 26	N.A	N.A	N.A	N.A	N.A	N.A
	Power Ltd.  Notice: 1. Only PSS RG Mo 2. AGC not implen	testing done		MVA	BHUPAL		220kv	<u> </u>			Power Ltd.	Energy		<u> </u>						,			-					<u> </u>			
73	MPCL	Unit-1	43MW	57.5 MVA	BHEL BHOPAI	05.07.2001	11kV/ 132kV	58MVA	3/9	ROR	MPCL	Power/	HPSLDC			Nav 26			Nov 26	06/11/2023		Nov 26			Nov 26	N.A	N.A	N.A	N.A	N.A	N.A
74	MPCL	Unit-2	43MW	57.5 MVA	BHEL BHOPAL	05.07.2001	11kV/ 132kV	58MVA	3/9	ROR	MPCL	Power/	HPSLDC			Nav 26			Nov 26	06/11/2023		Nov 26			Nov 26	N.A	N.A	N.A	N.A	N.A	N.A
75		1 2	33	36.67	Voith	19.11.2020 29.12.2020	132kV 11/220 KV 11/220 KV	42 42	06-Mar		ReNew Jal Urja	Energy																	N.A	N.A	N.A
76	Singoli Bhatwari HEP	2	60MW 60MW	36.67 66.7 MVA 66.7 MVA	Voith GE Hydro GE Hydro	01.01.2021 28/03/22 28/03/22	11/220 KV 11KV/220KV 11KV/220KV	42 81 MVA 81 MVA	06-Mar 05-Feb 05-Feb	ROR ROR ROR	Private Limited NA NA	Power/Energy Power/Energy		05.04.22 09.04.22	YES No No	31.03.2026 27-Mar 27-Mar	30.03.22 30.03.22	No No	27-Mar	30.03.22	YES No No	31.03.2026 27-Mar 27-Mar	31.05.22 31.05.22	YES No No	31.03.2026 27-Mar 31 27-Mar 31	1.05.22	YES NO NO	31.03.2026 27-Mar 27-Mar	N.A	N.A	N.A
	Bajoli Holi	3	60MW	66.7 MVA	GE Hydro	28/03/22	11KV/220KV	81 MVA	05-Feb	ROR	NA	Power/Energy		02.04.22	No	27-Mar	30.03.22	No	27-Mar	30.03.22	No	27-Mar	31.05.22	No	27-Mar 31	1.05.22	NO	27-Mar			

Notice: 1. Only RG Mo testing done in 2023 2. AGC not implemented

#### Thermal Generators

S. N	o. Nar	me of Plant	Unit	Installed Capacity	MVA Rating	Make of Units	COD	Gī	F Details		Mode of Fuel Transport (Pit	Name of Utility	Sector	Control Area	Туре	Real and Rea a	ctive Powe ssessment	er Capability	Assessment of Reactive F Capability as per CEA Tech for connectivi	nical Standards	Model Validation complete Gener mod		tation System	Turbine/Gov	ernor and Lo	erification of pad Control or ontrol Functions.	Testing of Governor performatic Generation		Revised Simulation	on Models
				Capacity	Kating			Voltage Ratio	GT MVA Capacity	Tap Ratio of GT (Present Tap/Total Taps)						Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy) Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)	Whether due?	Tentative Schedule date	Last tested on (dd/mm/yyyy)		Tentative Schedule date	Last tested on (dd/mm/yyyy) Whether due?	Tentative Schedule date	Whether Revised Models Submitted?	Remarks
1		Power Supply Co Ltd	Ţ	300 MW	353	Shanghai Electric Co Ltd, China	12.03.2010 00:00 Hrs	20KV / 220 KV	370 OFAF	5	Non-Pit Head	Rosa Power Supply Co Ltd	Private	Reliance Power	Coal Based		of Reactive Power bility assessment completed during FY 2028-29		FY 2028-29	24.09.2024		FY 2028-29	Load Control	or Active	FY 2028-29	·	FY 2028-29	No		
2		Power Supply Co Ltd	п	300 MW	353	Shanghai Electric Co Ltd, China	30.06.2010	20KV / 220 KV	370 OFAF	5	Non-Pit Head	Rosa Power Supply Co Ltd	Private	Reliance Power	Coal Based	was completed unit commisio	d during ning.All	FY 2028-29	Reactive Power Control Capability as per CEA Technical Standards for	FY 2028-29	15.01.2022		FY 2028-29	working fin	enabled & e in all	FY 2028-29	Governor performance testing done during comssioning of the units	FY 2028-29	No	
3		Power Supply Co Ltd	Ш	300 MW	353	Shanghai Electric Co Ltd, China	01.01.2012 24:00 hrs	20 KV / 400 KV	370 OFAF	5	Non-Pit Head	Rosa Power Supply Co Ltd	Private	Reliance Power	Coal Based	units are runing channel auto m with governor	iode AVR in auto	FY 2028-29	connectivity was completed during unit commisioning	FY 2028-29	Not Tested		FY 2028-29	variation is e	requency nabled &	FY 2028-29	, also all units are runing in auto governor mode.	FY 2028-29	No	
4		Power Supply Co Ltd	IV	300 MW	353	Shanghai Electric Co Ltd, China	31.03.2012 24:00 hrs	20 KV / 400 KV	370 OFAF	5	Non-Pit Head	Rosa Power Supply Co Ltd	Private	Reliance Power	Coal Based	control mo	ode.	FY 2028-29		FY 2028-29	05.10.2021		FY 2028-29	same has bee by UPSL		FY 2028-29		FY 2028-29	No	
			_						_			1	_	1																
5		ngsar Thermal wer Station	1	125	147	BHEL	20.01.2012	230/10.5	150	7/9	Pit Head	JdVVNL, AVVNL, JVVNL	Distributi	SLDC	SLDC		Yes	31.01.2026	Yes	31.01.2026		Yes	31.01.2026		Yes	31.01.2026	Yes	31.01.2026		
6		ngsar Thermal wer Station	п	125	147	BHEL	29.12.2011	230/10.5	150	7/9	Pit Head	JdVVNL, AVVNL, JVVNL	Distributi	SLDC	SLDC		Yes	31.01.2026	Yes	31.01.2026		Yes	31.01.2026		Yes	31.01.2026	Yes	31.01.2026		
Rema	irks															OC Yes 31.01.2026		rks: As per OEM	(BHEL) recommendations, ab	ove tests may be	completed by 31.0	)1.2026		recomment procedure to under develop after April-2	carry out the ment, and m	ne modelling e above tests is nay be available e tests may be	Remarks: AGC is not a part Main plant Erection packa same may be excluded fr tesing to be carried out by t possibilities will be exp completion of Testing of performance by 31.0	ge, hence the om the list of BTPS. However slored for of Governer		
		LPGCL.	,	660	777	BHEL.	01-Oct-15	800/√3/21/√3	3x275	0505	Railway	LPGCL Lalitour	Delicerte	Northen region		Not applicable		10/25/2026	Not applicable	10/25/2026	Not applicable		10/25/2026	Not applicable	1 1	10/25/2026	Not applicable	10/25/2026		
- / 8		LPGCL LPGCL	2	660	777	BHEL	14-Oct-16	800/√3/21/√3 800/√3/21/√3	3x275	05/05	Railway	LPGCL, Lantpur LPGCL, Lalitpur		Northen region		Not applicable		01/20/2027	Not applicable  Not applicable	01/20/2027	Not applicable			Not applicable				01/20/2027		
9		LPGCL.	3	660	777	BHEL	23-Dec-16	800/√3/21/√3	3x275	05/05	Railway	LPGCL, Lalitpur		Northen region		Not applicable		12/15/2027	Not applicable	12/15/2027	Not applicable		12/15/2027				Not applicable	12/15/2027		
10		PPGCL	i	660 MW	777	BHEL	29.02.2016	21KV / 765 KV	3X275	4 out of 5	Head	PPGCL, Prayagraj	IPP	SLDC Lucknow		-	-	2026		2026	Nov 2022	No	27-Nov	13-11-2024		-	09/15/2025 -	-		
11	. 1	PPGCL		660 MW	777	BHEL	10.09.2016	21KV / 765 KV	3X275	4 out of 5	Head	PPGCL, Prayagraj	IPP	SLDC Lucknow		-	-	2027		2027	Nov 2022	No	27-Nov	14-11-2024	-	-	09/15/2025 -	-		
12		PPGCL	III	660 MW	777	BHEL	26.05.2017	21KV / 765 KV	3X275	4 out of 5	Head	PPGCL, Prayagraj	IPP	SLDC Lucknow	STU	- 7	-	2026		2026	Nov 2022	No	27-Nov	-	Yes	26-Nov	09/15/2025 -	-		

#### **HVDC Links**

S. No		Name of Link	Type (LCC/VSC/ Back- to-Back)	HVDC_Voltage (kV)	Converte	er-1	Conv	erter-2	Master Converter Station	Pole_number	Length (km)	Capacity (MW)	Owner	Forward Di	rection	Reverse Di	rection		ower Contr Capability r HVDC/FAC			adequacy assessr on id condition, in co with NLDC.		Revised Simula Models	tion
					Station Name	Region	Station Name	Region						Minimum Capacity		Minimum Capacity	Ground_return_c	con (dd/mm/y vvy)	Whether	I Tentative	Last tested on (dd/mm/y vyy)	Whether due?	Tentative Schedule date	Whether Revised Models Submitted?	Remarks
	Ri	ihand - Dadri LCC																							
	Cl	hampa-Kurukshetra LCC																							
	Bi	allia-Bhiwadi LCC																							
	Vi	indhyachal BtB																							
		•																							

Tentative schedule for Periodic testing of HVDC/Facts Devices iro NR-III Region of POWERGRID

Sr. No.	HVDC Link/ FACTS	Proposed date of periodic testing
1	Rihand - Dadri LCC	Mar'26
2	Ballia- Bhiwadi LCC	Apr'26
3	NEA LCC	Aug'25
4	Vindhyachal BtB	Sep'26
5	Lucknow STATCOM	Apr'26

### STATCOMs/SVCs

S.No	Station	Statcom	Capacity (MVAR)	Owner	Make		Power Contro Capability or HVDC/FAC Whether due?	` '	preser	t adequacy a based on at grid condit nsultation w NLDC Whether due?	ion, in		of response devices as per settings. Whether due?	•	Revised Simulati Whether Revised Models	on Models Remarks
						(dd/mm/yy			(dd/mm/yy yy)			(dd/mm/yy yy)		date	Submitted?	
1	Bhadla-2	STATCOM- 1&2	.+/- 600 MVAr, 400kV	POWERGRI D	SIEMENS	July-2023.	NO	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	July-2023.	NO	NOT APPLICABLE		
2	Fatehgarh- 2	STATCOM- 1&2	.+/- 600 MVAr, 400kV	POWERGRI D	SIEMENS	Oct-2023.	NO	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	Oct-2023.	NO	NOT APPLICABLE		
3	Bikaner-2	STATCOM	.+/- 300 MVAr, 400kV	POWERGRI D	SIEMENS	Aug-2023.	NO	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	Aug-2023.	NO	NOT APPLICABLE		
4	KANKROLI	svc	.+400 MVAr, - 300MVAr, 400kV	POWERGRI D	SIEMENS	Dec-2016.	YES	Nov-2025.	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE	Dec-2016.	YES	Nov-2025.		
5	Nalagarh	STATCOM											YES	Oct-25		
6		SVC											YES	Oct-25		
7	New Wanpoh	SVC											YES	Oct-25		
8	Lucknow	STATCOM											YES	26-Apr		

State/UT		Stage-1 49.4 Hz (5%) Stage-1 Relief	Stage-2 49.2 Hz (6%) Stage-2 Relief	Stage-3 49.0 Hz (7%) Stage-3 Relief	Stage-4 48.8 Hz (7%) Stage-4 Relief	Total
	DI 1 (3.433)					00
	Planned (MW)	17	21	24	24	86
Charles I	Actual (MW)	0	0	0	0	0
Chandigarh	Difference (MW)	-17	-21	-24	-24	-86
	Difference (%)	-100%	-100%	-100%	-100%	-100%
	Planned (MW)	334	400	467	467	1668
	Actual (MW)	322	399	442	434	1597
Delhi	Difference (MW)	-11	-1	-25	-33	-71
	Difference (%)	-3%	0%	-5%	-7%	-4%
	Planned (MW)	586	704			2931
	Actual (MW)	735	730	815	897	3175
Haryana	Difference (MW)	148	26		76	244
	Difference (%)	25%	4%	-1%	9%	8%
	Planned (MW)	101	122			507
Himachal	Actual (MW)	432	365	183	97	1077
Pradesh	Difference (MW)	331	244	41	-45	570
	Difference (%)	326%	200%	29%	-32%	112%
	Planned (MW)	140	168	196	196	700
UT J&K &	Actual (MW)	156	204	204	214	778
Ladhak	Difference (MW)	16	36	8	18	78
	Difference (%)	11%	22%	4%	9%	11%
	Planned (MW)	645	773	902	902	3223
	Actual (MW)	584	715	855	859	3014
Punjab	Difference (MW)	-61	-58	-47	-43	-209
	Difference (%)	-9%	-8%	-5%	-5%	-6%
	Planned (MW)	853	1024	1194		4266
	Actual (MW)	812	974	1138	1142	4066
Rajasthan	Difference (MW)	-41	-50	-56	-52	-200
	Difference (%)	-5%				-5%
	Planned (MW)	1297	1557			6486
	Actual (MW)	2580	2188	2013	1757	8538
Uttar Pradesh	Difference (MW)	1283		197		2052
	Difference (%)	99%				32%
	Planned (MW)	127	152			633
	Actual (MW)	319	138	167	241	865
Uttarakhand	Difference (MW)	192			64	232
	Difference (%)	152%				37%
	Planned (MW)	4100				20499
	Actual (MW)	5940	5713	5816	5642	23111
Total	Difference (MW)	1840				2612
	Difference (%)	45%	16%	1%	-2%	13%

	Out	age Details			c	utage	of Line			0			Restorati	on of Li	ne				
Month	Outage Date & Time	Restoratio n Date & Time	Total Outag e Durati on	Outage Punch Time at NRLDC Portal.	Outage Code isued Time ( OMS Portal)	RLDC Code Proce ss	PTW issued Time	PTW Issue time taken by PGCIL	Suppo rting Mails (Annex ure- Numb er)	Charging Punch time at NRLDC Portal	Charging Code issued Time ( As Per OMS portal)	RLDC Code Proces s	PTW cancellati on time as per mail informati on	Chargi ng Proces s time	Effec tive time utiliz ed for Work	Supp orting Mails (Anne xure- Num ber)	tion	Remar ks	Extra Hours not Utilize d by Licens ee
Jul-25	24-07-25 17:34	24-07-25 22:33	4:59	24-07-25 15:54	24-07-25 16:59	1:05	24-07-25 18:53	1:19	Mail -1 july	24-07-25 20:05	24-07-25 21:09	1:04	24-07-25 19:59	1:24	1:06	Mail - 1 july	4.59	765kV Bikane r- Khetri CKT-1	3:53
Jul-25	24-07-25 23:03	25-07-25 5:33	6:30	24-07-25 15:56	24-07-25 22:51	6:55	25-07-25 0:05	1:02	Mail -2 july	25-07-25 4:58	25-07-25 5:16	0:18	25-07-25 4:48	0:17	4:43	Mail - 2 july	6:30	765kV Bikane r- Khetri CKT-2	1:47
Jul-25	26-07-25 17:56	27-07-25 0:56	7:00	26-07-25 14:41	26-07-25 17:49	3:08	26-07-25 18:43	0:47	Mail -3 july	27-07-25 0:11	27-07-25 0:20	0:09	26-07-25 23:54	0:36	5:11	Mail - 3 july	7:00	765kV Bikane r- Khetri CKT-2	1:49
Jul-25	27-07-25 1:44	27-07-25 9:00	7:16	26-07-25 14:34	27-07-25 1:17	10:43	27-07-25 2:37	0:53	Mail -4 july	27-07-25 4:54	27-07-25 8:15	3:21	27-07-25 4:48	0:45	2:11	Mail - 4 july	7:16	765kV Bikane r- Khetri CKT-1	5:05
Jul-25	30-07-25 18:03	30-07-25 23:41	5:38	30-07-25 16:07	30-07-25 17:53	1:46	30-07-25 18:56	0:53	Mail -5 july	30-07-25 22:23	30-07-25 22:35	0:12	30-07-25 22:21	1:06	3:25	Mail - 5 july	5:38	765kV Bikane r- Khetri CKT-2	2:13
Aug-25	06-08-25 18:28	06-08-25 23:01	4:33	06-08-25 15:06	06-08-25 18:01	2:55	06-08-25 19:41	1:13	Mail -1 aug	06-08-25 21:54	06-08-25 22:23	0:29	06-08-25 21:45	0:38	2:04	Mail - 1 aug	4:33	765kV Bikane r- Khetri CKT-2	2:29
Aug-25	20-08-25 17:38	20-08-25 23:56	6:18	20-08-25 15:58	20-08-25 17:12	1:14	20-08-25 18:30	0:52	Mail -2 aug	20-08-25 22:13	20-08-25 22:40	0:27	20-08-25 22:08	1:16	3:38	Mail - 2 aug	4:33	765kV Bikane r- Khetri CKT-1	2:40
Aug-25	21-08-25 0:42	21-08-25 8:21	7:39	21-08-25 0:17	21-08-25 0:26	0:09	21-08-25 2:09	1:27	Mail -3 aug	21-08-25 4:55	21-08-25 5:16	0:21	21-08-25 4:48	3:05	2:39	Mail - 3 aug	4:33	765kV Bikane r- Khetri CKT-2	5:00

							FORMAT-A	
				Captive Power Pla	nt Details	-		
	Name of Captive Power	Name and Contact	Complete Address with	Gross Generation	Net Generation		<b>Electricity Consumption</b>	
S.No.	Plant	Number of Nodal Officer	postal code	Gross Generation	Net Generation	Power Drawl from Grid	Net injection of power to Grid	Captive Consumption
				(kwh)	(kwh)	(kwh)	(kwh)	(kwh)
1								
2								

		FORMAT-B
	Open Access I	<b>Details</b>
S.No.	Name of Utility	Open Access
		(kWh)
1		
2		

			FORMAT-C
		<b>Rooftop Solar Generation Details</b>	
S.No.	Name of Utility	Rooftop Solar Generation	Exchange with Grid
		(kWh)	(kWh)
1			
2			

# Resource Adequacy

PRAS results- Northern Region Month ahead for Jan-2026

# Resource Adequacy - PRAS


- The Probabilistic Resource Adequacy Study (PRAS) for the month of Jan 2026 has been carried out for the Northern Region to assess the sufficiency of available generation resources to meet the projected demand under varying scenarios. The study was conducted using 1000 probabilistic scenarios, with median results presented to reflect expected system behavior under typical conditions.
- To evaluate the net load that must be met by dispatchable thermal generation, the projected regional demand for Jan 2026 was first estimated. From this demand, the expected contribution from nonthermal resources solar, wind, hydro, and nuclear was subtracted, based on historical generation profiles observed for these sources during the same period in past years. This approach ensures that the inherent variability and diurnal patterns of renewable generation are accurately captured in the analysis.
- For thermal generation, a detailed availability assessment was carried out using the following assumptions:


# **Planned Outages:**

Unit-wise planned outages for the month of Jan 2026 were incorporated as per the data available in the latest LGBR. This reflects scheduled maintenance and other operational constraints known in advance.

# **Forced Outages:**


A Monte Carlo simulation approach was adopted to model forced outages of thermal generating units. This stochastic simulation utilized historical outage and revival rates specific to each unit and capacity. The probabilistic nature of this method allows for modeling of unplanned events, enhancing the robustness of the adequacy assessment.






# 2. (A) Resource Adequacy results

Probability of Shortage per Hour across 1000 Scenarios




# 2. (B) Resource Adequacy results


EUE Heat-Map - Median\_LOLP (EUE\_Simulation\_21)



# 2.(C) Resource Adequacy results



# 2. (D) Resource Adequacy results (with Jan 2024 IR schedule)



S. No	Points discussed in the Meeting held on 29.08.2025 (09/SM/2024)	Action taken and Current Status	Punjab	Delhi	Haryana	Rajasthan	Uttar Pradesh	Uttarakhand	Himachal Pradesh	J&K (UT) and Ladakh (UT)	Chandigarh
1	Adequacy of workforce: The issue of the shortage of manpower across all the SLDCs in the northern region was discussed. SLDCs have submitted that they are taking up the issue of additional manpower as per the MoP Guidelines. HPSLDC mentioned that their manpower position has been restricted to 42 by the HPSLCR. Rajasthan SLDC mentioned that with the higher renewable penetration in Rajasthan, they are fazing issues specifically in the field of cyber security, market operation and IT logistics.  Representative of UPSLDC submitted that UPSLDC has framed an HB Management and Development Policy which aimed to structure the movement of officers in specialised functions without disrupting operations. Representative from Gos informed that the recruitment of additional 26 personnel will be carried out.  Punjab SLDC suggested that the minimum tenure of staff in SLDCs should be at least 5 years. It was discussed that all the SLDCs may develop a separate HR opidicy and at ranker coolicy for the SLDC staff.	Details of the action taken regarding the increase in manpower as per the Ministry of Power (MoP) guidelines. Kindly also confirm whether a separate HR and transfer policy, similar to the one framed by UP SLDC, has been formulated.									·
2	Training and Certification of the SLDC staff: It was discussed that all the executives of SLDCs are required be adequately trained and certified. Representative of DPSLDC pointed out that basic level training is good but there are some gaps in advanced level training due to unavailability of SLDC. Slots. UPSLDC has a round 20 staff who are to be trained. Punjab SLDC also added that they have the same number of staff who are to be trained. Grid-India was a sked to take up the issue with the NPTI. It was also suggested during the discussion that ideally, the trained staff should not be shifted from the SLDCs, and catter the staff for working in SLDCs, incentive provisions can be incorporated under the Fee and Charges of the SLDCs. In addition to the above, it was also suggested that, cyber security is a critical area and with the growing concerns of cyber security threats, adequate staff are required to be trained in this area. With regard to the gap in advanced-level training dots of this concerns the required to the cases with NPTI.	Introduction of Posting criteria, tenure policies and appropriate staff incentives at SLDC.									
3	lacking down of intra-state thermal generating units:  Haryana SLDC submitted that the Panipat old units are not able to operate at  MTL of SSR. Rajasthan SLDC mentioned that they have started giving the schedule of SSS in some thermal generating stations. In this regard, it was suggested that representatives of intra-state thermal generating stations may visit NTPC plants, as even the older units of NTPC are able to operate at a MTL of SSW.  It was also suggested that the states should come up with a part-load compensation mechanism for thermal power plants and also explore the possibilities for the two-shift operation of the thermal generating stations keeping in view the large Re Integration.	Backing down of intra-state thermal generating units upto 55%									
4	Demand estimation and Resource Adequacy data submission: State SLOCs have submitted that there was some lag in data submission, and they are trying to improve. It was emphasized that the States needs to be prepared for a sudden change in demand and generation for which proper operational planning is required. The adequate quantum of Power may be tied up on a long term, medium term and short rerm basis.	Portal has been developed by NRLDC to collect data from SLDCs. Status of submission either by mail or portal shall be provided.									
5	Alignment of the State Grid Code with the Indian Electricity Grid Code 2023: It was discussed that CERC has notified the new Grid Code, which contains the various provisions with respect to AGC, Reserve requirement and part load compensation for the thermal generating stations. The state SERCs may align their respective Grid Code with the 2023 Grid Code of CERC.	Updated status shall be shared									
7	It was discussed that wherever the SAMAST has not been implemented yet, there is a need to speed up its implementation.  Fee and Charge Regulations for SIONED: It was discussed that SERCs may formulate separate Fee and Charges Regulations for State Load Despatch Centers wherein the provision regarding	Updated status of implementation shall be shared  Status of availabilty of regulations along with training and incentive									
8	negotiations for State Code uspation Letties is writer that provisions regarding training of the SLOC staff, as well as incentive provisions, can be incorporated. Enablement of AGC in Intra-state generating stations: It was suggested that SLOCs need to impress the generators to enable AGC in Intra-state generating stations. SRCs may also make suitable provisions for incentives under State Regulations in line with provisions under CERC Regulations. Adoption of AGC would offer dual benefits—generators would be able to earn revenue from AGC operations, while states would be able to maintain reverse within their own boundaries.	provisions.  Status of Enablement of AGC in intra-state generating stations.									
9	Ophersecurity preparedness: A power system is a critical infrastructure that must be safeguarded against opheraticals. State SLDCs do not have adequate manpower in the area of ophersecurity. With the growing concern of opher threats, an adequate number of staff may be deployed in the area of opher security. Further, the staff may be	Actions taken pertaining to the cyber preparedness and deployment of dedicated manpower at SLDC.									
10	mandatorily trained on cyber security.  Strengthening of intra-state transmission network:  Most of the Grid disturbances are occurring due to radial connectivity issues, which require the strengthening of the intra-state transmission network to enhance reliability and reduce such disturbances.	Actions taken pertaining to improvement of intra-state network									

_							
Г	Maintaining adequate Reserves:						i
- 1	No state is actually maintaining reserves, and even in cases where states claim						i l
- 1	to have reserves, these are scheduled during peak hours, defeating the purpose.						i l
- 1	It was informed that in the event a state falls short in maintaining the reserves,						i l
- 1	NLDC is to procure reserve capacity as allocated to such State and allocate the						i l
- 1	cost of procurement to that State as per the CERC (Indian Electricity Grid Code)						i l
- 1	Regulations 2023, Eurther, as per CERC (Deviation Settlement Mechanism and	Status of Maintaining adequate					i l
- 1		Reserves					i l
- 1		Action plan to ensure primary					i l
- 1	allocated by NLDC to States, to meet the deficit in the Deviation and Ancillary	response.					i l
- 1	Service Pool Accounts. Such allocation by NLDC may prove costly for the states,						i l
- 1	as NLDC may need to maintain reserves in costlier gas-based plants. Hence,						i l
- 1	states were urged to maintain their own reserves. States are required to meet the expected demand						i l
- 1	as well as keep the necessary reserve so that any load loss would not occur in case of any						i l
- 1	contingency						<i>i</i> 1

Α				

												Annexure-II
S.No.	Voltage Level	Name of Line	Circuit	Tower	Line	OEM by		cy at	Type of conductor	Remarks	Replaced with	Additional Remarks
			ID	Configura	Length		End-I	End-II			Polymer Insulator (As a % of Total Line)	
I. HV	DC lines											
											4	
ISTS LII											4	
A. POWE	± 800kV	Agra-Bishwanath Chariali Pole-I	1 1	Bi-pole	1728	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	HVDC capcacity 6000	Partial (11%)	
2	± 800kV	Agra-Bishwanath Chariali Pole-II	2	Bi-pole Bi-pole	1728	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	MW, only two physical	Partial (11%)	
3	± 800kV	Agra-Alipurduar Pole-I	1	Bi-pole	1296*	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	lines	Partial (11%)	
4	± 800kV	Agra-Alipurduar Pole-II	2	Bi-pole	1296*	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	1	Partial (11%)	
5	± 800kV	Kurukshetra-Champa Pole-I	1	Bi-pole	1305	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	HVDC capcacity 6000	Partial (11%)	
6	± 800kV	Kurukshetra-Champa Pole-II	2	Bi-pole	1305	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	MW, only two physical	Partial (11%)	
7	± 800kV	Kurukshetra-Champa Pole-III	3	Bi-pole	1305	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing	lines	Partial (11%)	
8	± 800kV	Kurukshetra-Champa Pole-IV	4	Bi-pole	1305	POWERGRID	POWERGRID	POWERGRID	Hexagon Lapwing		Partial (11%)	
9	± 500kV	Balia-Bhiwadi Pole-I	1	Bi-pole	790	POWERGRID	POWERGRID	POWERGRID	ACSR Quad Bersimis	HVDC capacity 2500	Partial (15%)	
10	± 500kV	Balia-Bhiwadi Pole-II	1	Bi-pole	790	POWERGRID	POWERGRID	POWERGRID	1000 0 10 10	MW	Partial (15%)	
11 12	± 500kV ± 500kV	Rihand-Dadri Pole-I Rihand-Dadri Pole-II	2	Bi-pole Bi-pole	815 815	POWERGRID POWERGRID	POWERGRID POWERGRID	POWERGRID POWERGRID	ACSR Quad Bersimis	HVDC capacity 1500 MW	Partial (62%) Partial (43%)	
	Power Ltd (Adani Tran			ы-рые	013	FOWERDID	FOWERDRID	FOWERGRID	1	17100	Faruar (43%)	
1	± 500kV	Adani Mundra - Mahindergarh Pole-I	1	Bi-pole	990	ATIL	APL Mundra	ATIL	ACSR Quad Bersimis	HVDC capacity 2500	Partial (43%)	
2	± 500kV	Adani Mundra - Mahindergarh Pole-II	2	Bi-pole	990	ATIL	APL Mundra	ATIL	1	MW	Partial (43%)	
2, 765	kV Transmissi		•		•	•		•	•			
											-	
ISTS LII											_	
A. POW												
1	765kV	Agra-Aligarh	1	D/C	123	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	LILO of Agra-Gr. Noida	Polymer Insulator	
2	765kV	Aligarh-Gr.Noida	1	D/C	51	POWERGRID	POWERGRID	WUPPTCL	Quad Bersimis	at Aligarh (LILO portion	Polymer Insulator	
3	765kV	Agra-Fatehpur	1	S/C	335	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Conventional	
_	765kV 765kV	Agra-Fatehpur Agra-Jhatikara	2	S/C S/C	334 252	POWERGRID POWERGRID	POWERGRID POWERGRID	POWERGRID POWERGRID	Quad Bersimis  Quad Bersimis		Conventional	
5 6	765kV 765kV	Ajmer-Chittorgarh	1	D/C	252	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Polymer Insulator Not Available	
7	765kV	Ajmer-Chittorgarh	2	D/C	211	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
- 8	70384	Ajmer emtorgam		5,0	211	TOWERGRID	TOWERGRID	TOWERORD	TICAG ZCDIG	LILO of 765kV D/C	140t Available	
0	765kV	Ajmer-Bhadla II	1	D/C	326	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra	Ajmer-Bikaner-1 at Bhadla II(PG)	Not Available	
9	765kV	Ajmer-Bhadla II	2	D/C	326	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra	LILO of 765kV D/C Ajmer-Bikaner-2 at Bhadla II(PG)	Not Available	
10	765kV	Balia - Lucknow765 (N)	1	S/C	319	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Conventional	
11	765kV	Bikaner - Bhadla	1	D/C	167	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
12	765kV	Bikaner - Bhadla	2	D/C	167	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
13	765kV	Bikaner- Moga	1	D/C	367	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
14	765kV	Bikaner- Moga	2	D/C	367	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra	171.0 - C 7CELV D/C	Not Available	
15	765kV	Bikaner-Bhadla II	1	D/C	197	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra	LILO of 765kV D/C Ajmer-Bikaner-1 at Bhadla II(PG)	Not Available	
16	765kV	Bikaner-Bhadla II	2	D/C	197	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra	LILO of 765kV D/C Ajmer-Bikaner-2 at Bhadla II(PG)	Not Available	
17	765kV	Kanpur(GIS)-Aligarh	1	D/C	322	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	LILO of Kanpur-	Polymer Insulator	
18	765kV	Aligarh-Jhatikara	1	D/C	158	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	Jhatikara at Aligarh	Polymer Insulator	
19	765kV	Jhatikara-Bhiwani (PG)	1	S/C	85	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Polymer Insulator	
20	765kV	Koteshwar(PG)-Meerut	1	S/C	176	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	Earlier charged at	Not Available	
21	765kV	Koteshwar(PG)-Meerut	2	S/C	176	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	400kV	Not Available	
22	765kV	Lucknow-Bareilly	1	S/C	252	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Conventional	
23 24	765kV 765kV	Meerut-Bhiwani(PG)  Meerut-Gr.Noida	1	s/c	174	POWERGRID POWERGRID	POWERGRID POWERGRID	POWERGRID WUPPTCL	Quad Bersimis  Quad Bersimis	Agra-Meerut LILOed at G. Noida by UPPTCL	Partial (99%) Polymer Insulator	
			1						1			
25	765kV	Moga- Bhiwani (PG)	1	S/C	273	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Partial (96%)	
26	765kV	Moga-Meerut	1	S/C	338	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Polymer Insulator	
27	765kV	Orai-Aligarh	1	D/C	331	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
28	765kV 765kV	Orai-Aligarh	2	D/C S/C	331	POWERGRID POWERGRID	POWERGRID RRVPNL	POWERGRID POWERGRID	Hexa Zebra  Quad Bersimis		Not Available Partial (18%)	
29	/bokv	Phagi-Bhiwani(PG)	1	3/C	272	POWERGRID	KKVPINL	POWERGRID	Quad Bersimis		Partial (18%)	

30	765kV	Phagi-Bhiwani(PG)	2	S/C	277	POWERGRID	RRVPNL	POWERGRID	Quad Bersimis		Partial (16%)	
31	765kV	Varanasi-Balia	1	S/C	166	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis		Conventional	
32	70384	varanasi bana	1	3,0	100	TOWERORD	TOWERGRID	TOWERORD	Quad Dersinis	LILO of Gaya (ER)- Fatehpur	Conventional	
32	765kV	Varanasi-Fatehpur	1	s/c	223	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	at Varanasi	Conventional	
	70384	varariasi-i ateripui	1 -	3/0	223	FOWENDRID	FOWERGRID	FOWERGRID	Quau bersiiiiis	at varariasi	Conventional	
33	765kV	Varanasi-Kanpur(GIS)	1	S/C	326	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Polymer Insulator	
34	765kV	Varanasi-Kanpur(GIS)	2	S/C	326	POWERGRID	POWERGRID	POWERGRID	Hexa Zebra		Polymer Insulator	
B. PKTSL	70384	varariasi-karipur(Ol3)		3/0	320	FOWERGRID	FOWERGRID	FOWERGRID	TIEXA ZEDIA		Folyinei Insulatoi	
1	765kV	Khetri-Jhatikara	1 1	D/C	146	PKTSL	PKTSL	POWERGRID	Hexa Zebra		Not Available	
2	765kV	Khetri-Jhatikara	2	D/C	146	PKTSL	PKTSL	POWERGRID	Hexa Zebra		Not Available	
C. PFTL	703KV	KIIEUI-JIIaukara		D/C	140	PRISE	PRISE	POWERGRID	пеха дерга		NOT Available	
1	765kV	Fatehgarh II-Bhadla II	1 1	D/C	186	PFTL	POWERGRID	POWERGRID	Hexa Zebra	1	Not Available	
-	765kV	Fatehgarh II-Bhadla II	2	D/C	186	PFTL	POWERGRID	POWERGRID	Hexa Zebra		Not Available	
D. FBTL	703KV	Faterigatii ii-Bilaula ii		D/C	180	PFIL	POWERGRID	POWERGRID	пеха дерга		NOT Available	
1	765kV	Fatabasah II Bhadla	1 1	D/C	175	FBTL	POWERGRID	POWERGRID	11a 7ab		Delumen Treudeten	1
_	765kV	Fatehgarh II-Bhadla	2	D/C D/C	175 175	FBTL	POWERGRID	POWERGRID	Hexa Zebra	Loop in of 400kV Fatehgarh (FBTL)-	Polymer Insulator Polymer Insulator	
E. BKTL	/65KV	Fatehgarh II-Bhadla		D/C	1/5	FBIL	POWERGRID	POWERGRID	Hexa Zebra	raterigarii (FBTL)-	Polymer Insulator	
1	765kV	Bikaner-Khetri	1 1	D/C	241	BKTL	POWERGRID	PKTSL	Hexa Zebra	1	Polymer Insulator	
2	765kV	Bikaner-Khetri	2	D/C		BKTL	POWERGRID	PKTSL	Hexa Zebra		Polymer Insulator	
F. PAPTL	/65KV	Bikaner-knetri	2	D/C	241	BKIL	POWERGRID	PKISL	пеха дерга		Polymer Insulator	
1 1	765kV	Aissau Dhani	1 1	D/C	1 124	DARTI	DOMEDODIS	I DDVDNU I	Have Zahas	F	Net Assileble	
		Ajmer-Phagi	1	D/C	134	PAPTL PAPTL	POWERGRID POWERGRID	RRVPNL RRVPNL	Hexa Zebra	<del> </del>	Not Available Not Available	
2	765kV	Ajmer-Phagi	2	D/C	134	PAPIL	POWERGRID	KKVPINL	Hexa Zebra	+	NOT AVAILABLE	
G. PASTL			1	1		1	1					
1	765kV	Aligarh(PG)-SIKAR_2	1	D/C	265	PASTL	PSTL	POWERGRID	Hexa Zebra	Anti theft charged	Not Available	
2	765kV	Aligarh(PG)-SIKAR_2	2	D/C	265	PASTL	PSTL	POWERGRID	Hexa Zebra	from Aligarh(PG) Upto	Not Available	
-		Aligaiti(PG)-SIKAK_Z		D/C	203	PASIL	PSIL	POWERGRID	пеха дерга	ITOTTI Aligarii(PG) Opto	NOT Available	
STATE L												
A. UPPTC												
1	765kV	Agra Fatehabad-Ghatampur	1	S/C	229	UPPTCL	UPPTCL	UPPTCL	Quad Bersimis		Not Available	
2	765kV	Agra Fatehabad-Gr. Noida	1	S/C	159	UPPTCL	UPPTCL	UPPTCL	ACSR Quad Bersimis		Not Available	
3	765kV	Agra(Fatehbad)-Lalitpur	1	S/C	337	UPPTCL	UPPTCL	LPGCL	Quad Bersimis		Not Available	
4	765kV	Agra(Fatehbad)-Lalitpur	2	s/c	335	UPPTCL	UPPTCL	LPGCL	Quad Bersimis		Not Available	
5	765kV	AnparaC-AnparaD	1	S/C	3	UPPTCL	LANCO	UPRVUNL	Quad Bersimis		Not Available	
6	765kV	AnparaC-Unnao	1	S/C	409	UPPTCL	LANCO	UPPTCL	Quad Bersimis		Conventional	AnparaB-Unnao shifted
												to AnparaC and charged
							1					at 765kV
							1	I I				
7	765kV	AnparaD-Obra_C	1	D/C	53	UPPTCL	UPRVUNL	UPPTCL	Quad Bersimis	After LILO of 765 KV	Not Available	
8	765kV	Obra_C-Unnao	1	D/C	390	UPPTCL	UPRVUNL	UPPTCL	Quad Bersimis	After LILO of 765 KV ANPARA D-UNNAO LINE	Not Available	
8 9	765kV 765kV	Obra_C-Unnao Bara-Mainpuri	1	D/C S/C	390 377	UPPTCL UPPTCL	UPRVUNL UPPTCL	UPPTCL UPPTCL	Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE	Not Available Not Available	
8 9 10	765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL	1 1 1	D/C S/C S/C	390 377 100	UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE After LILO of 765 KV	Not Available Not Available Not Available	
8 9 10 11	765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur	1 1 1 1	D/C S/C S/C S/C	390 377 100 37	UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV  GREATER NOIDA	Not Available Not Available Not Available Not Available	
8 9 10 11 12	765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur	1 1 1 1 1	D/C S/C S/C S/C D/C	390 377 100 37 162	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV	Not Available Not Available Not Available Not Available Not Available	
8 9 10 11	765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur	1 1 1 1	D/C S/C S/C S/C	390 377 100 37	UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)-	Not Available Not Available Not Available Not Available	
8 9 10 11 12	765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur	1 1 1 1 1	D/C S/C S/C S/C D/C	390 377 100 37 162	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)-  LILO of 765kV Hapur-	Not Available Not Available Not Available Not Available Not Available	
8 9 10 11 12 13	765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri	1 1 1 1 1	D/C S/C S/C S/C D/C D/C	390 377 100 37 162 40	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765kV Hapur- Ghatampur at Rampur.	Not Available	
8 9 10 11 12	765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur	1 1 1 1 1	D/C S/C S/C S/C D/C	390 377 100 37 162	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Not Available Not Available Not Available Not Available	
8 9 10 11 12 13	765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri	1 1 1 1 1	D/C S/C S/C S/C D/C D/C	390 377 100 37 162 40	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765kV Hapur- Ghatampur at Rampur.	Not Available	
8 9 10 11 12 13	765kV 765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)	1 1 1 1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C D/C	390 377 100 37 162 40	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13	765kV 765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri	1 1 1 1 1	D/C S/C S/C S/C D/C D/C	390 377 100 37 162 40	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13	765kV 765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP) Mainpuri(UP)-Hapur(UP)	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	D/C S/C S/C S/C S/C D/C D/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 B. RRVPN	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi	1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C S/C S/C S/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 B. RRVPN 1 2	765kV 765kV 765kV 765kV 765kV 765kV 765kV	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	D/C S/C S/C S/C S/C D/C D/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 8. RRVPN 1 2	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV KV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi	1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C S/C S/C S/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 B. RRVPN 1 2	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV KV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi	1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C S/C S/C S/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 8. RRVPN 1 2	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV kV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi	1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C S/C S/C S/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 14 15 B. RRVPN 1 2 3. 765I ISTS LIN A. POWER	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV kV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV	1 1 1 1 1 1 1	D/C S/C S/C S/C D/C D/C D/C S/C S/C S/C S/C	390 377 100 37 162 40 230 217	UPPTCL  UPPTCL  RRVPNL RRVPNL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  RRVPNL  RRVPNL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 14 15 B. RRVPN 1 2 2 3. 765 ISTS LIN A. POWEF 1	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV kV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi	1 1 1 1 1 1 1 1 1 2	D/C S/C S/C S/C D/C D/C D/C S/C S/C S/C S/C S/C S/C S/C	390 377 100 37 162 40 230	UPPTCL	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID	UPPTCL	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available	
8 9 10 11 12 13 13 14 15 B. RRVPN 1 2 2 3. 765 IISTS LIN A. POWEF 1 2 2	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV 1L 765kV kV Transmissi	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV	1 1 1 1 1 1 1 1 2 2	D/C S/C S/C S/C D/C D/C D/C S/C S/C S/C S/C	390 377 100 37 162 40 230 217 214 212	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  PPTCL  PPTCL  RRVPNL  RRVPNL  RRVPNL  POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%)	
8 9 10 11 12 13 14 14 15 B. RRVPN 1 2 3. 765 ISTS LIN A. POWEF 1 2 2 3 3	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  765kV  KV Transmissi  IES  RGRID	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV  Kishenpur-Moga Kishenpur-Moga	1 1 1 1 1 1 1 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 1 2 1	D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%) Partial (1%) Conventional	
8 9 10 11 12 13 14 14 15 B. RRVPN 1 2 3. 765 ISTS LIN A. POWEF 1 2 3 3 1	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  765kV  800 800 800 800 800 800 800 800 800 8	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri  Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi Inne charged at 400kV  Kishenpur-Moga Kishenpur-Moga Tehri-Koteshwar(PG)	1 1 1 1 1 1 1 1 1 2 2 1 1 1 1 1 1 1 1 1	D/C   S/C   S/C   D/C   D/C   D/C   D/C   D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287 15	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL POWERGRID POWERGRID THDC	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  RRVPNL  RRVPNL  RRVPNL  POWERGRID POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Port Available Not Available Not Available Not Available Not Available	
8 9 10 11 12 13 14 14 15 B. RRVPN 1 2 3. 765 IISTS LIN A. POWEF 1 2 3 4 4 1	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  765kV  800 800 800 800 800 800 800 800 800 8	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV  Kishenpur-Moga Kishenpur-Moga Tehri-Koteshwar(PG) Tehri-Koteshwar(PG)	1 1 1 1 1 1 1 1 1 1 1 2	D/C   S/C   S/C   D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287 15	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID THDC THDC	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%) Partial (1%) Conventional Conventional	
8 9 10 11 12 13 14 15 B. RRVPN 1 2 2 3 . 765 1 1 2 2 3 4 4 5 6 6	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  10 11 12 13 14 15 15 16 16 16 16 17 16 17 16 18 18 18 18 18 18 18 18 18 18 18 18 18	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV  Kishenpur-Moga Kishenpur-Moga Tehri-Koteshwar(PG) Tehri-Koteshwar(PG) Rihand-Vindhyachal Pool Rihand-Vindhyachal Pool	1 1 1 1 1 1 1 1 1 1 2 2 1 1 1 2 2 1	D/C   S/C   S/C   D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287 15 17 31	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID THDC THDC NTPC	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  PPTCL  RRVPNL  RRVPNL  POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%) Partial (1%) Conventional Conventional Not Available	
8 9 10 11 12 13 14 15 B. RRVPN 1 2 2 3. 765 ISTS LIN A. POWEF 1 2 3 4 4 5 6 4. 400	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  10 11 15 16 17 17 17 18 18 18 18 18 18 18 18 18 18 18 18 18	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV  Kishenpur-Moga Kishenpur-Moga Tehri-Koteshwar(PG) Tehri-Koteshwar(PG) Rihand-Vindhyachal Pool	1 1 1 1 1 1 1 1 1 1 2 2 1 1 1 2 2 1	D/C   S/C   S/C   D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287 15 17 31	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID THDC THDC NTPC	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  PPTCL  RRVPNL  RRVPNL  POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%) Partial (1%) Conventional Conventional Not Available	
8 9 10 11 12 13 14 15 B. RRVPN 1 2 2 3 . 765 1 1 2 2 3 4 4 5 6 6	765kV 765kV 765kV 765kV 765kV 765kV 765kV 765kV  765kV  10 11 15 16 17 17 17 18 18 18 18 18 18 18 18 18 18 18 18 18	Obra_C-Unnao Bara-Mainpuri Gr. Noida-Meerut_PMSTL Meerut_PMSTL-Hapur Gr. Noida-Jawaharpur Jawaharpur-Mainpuri Hapur(UP)-Rampur_PRSTL (UP)  Mainpuri(UP)-Hapur(UP)  Anta-Phagi Anta-Phagi ion Line charged at 400kV  Kishenpur-Moga Kishenpur-Moga Tehri-Koteshwar(PG) Tehri-Koteshwar(PG) Rihand-Vindhyachal Pool Rihand-Vindhyachal Pool	1 1 1 1 1 1 1 1 1 1 2 2 1 1 1 2 2 1	D/C   S/C   S/C   D/C   S/C   S/C	390 377 100 37 162 40 230 217 214 212 275 287 15 17 31	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	UPRVUNL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  RRVPNL RRVPNL RRVPNL POWERGRID POWERGRID THDC THDC NTPC	UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL UPPTCL  UPPTCL  PPTCL  RRVPNL  RRVPNL  POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	Quad Bersimis	ANPARA D-UNNAO LINE  After LILO of 765 KV GREATER NOIDA  After LILO of 765 KV MAINPURI(SEUPPTCL)- LILO of 765KV Hapur- Ghatampur at Rampur. LILO portion is on D/C	Not Available Partial (1%) Partial (1%) Conventional Conventional Not Available	

A. POWE	RGRID											
1	400kV	Abdullapur- Bawana	1	D/C	167	POWERGRID	POWERGRID	DTL	Triple Snowbird		Partial (99%)	
2	400kV	Abdullapur- Deepalpur	1	D/C	141	POWERGRID	POWERGRID	KT Jhajjar	Triple Snowbird	LILO of Abdullapur- Bawana one ckt at Deepalpur by Jhajjar KT	Partial (99%)	LILO of Abdullapur- Bawana one ckt at Deepalpur
3	400kV	Abdullapur-Kurukshetra	1	D/C	52	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird+Twin HTLS for LILO	LILO of Abdullapur-Sonipat line at Kurukshetra	Polymer Insulator	LILO of Abdullapur- Sonepat ckts at
4	400kV	Abdullapur-Kurukshetra	2	D/C	52	POWERGRID	POWERGRID	POWERGRID		LILO of Abdullapur-Sonipat line at Kurukshetra	Polymer Insulator	Kurukshetra
5	400kV	Agra-Agra(Fatehbad)	1	S/C	45	POWERGRID	POWERGRID	UPPTCL	Twin Moose	LILO of Agra(PG)-Agra(UP) ckt-	Polymer Insulator	
6	400kV	Agra(UP)-Agra(Fatehbad)	1	S/C	56	POWERGRID	UPPTCL	UPPTCL	Twin Moose	2 at Fatehabad (765kV Agra UP)	Polymer Insulator	
7	400kV	Agra-Agra(UP)	1	D/C	30	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Polymer Insulator	
8	400kV	Agra-Ballabgarh	1	S/C	181	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
9	400kV	Agra-Bassi	1	s/c	211	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	Planned for insulator replacement in 321nos towers under NR3
10	400kV	Agra-Bhiwadi	1	D/C	209	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
11	400kV	Agra-Bhiwadi	2	D/C	209	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
12	400kV	Agra-Jaipur South	1	D/C	254	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Agra-Bassi D/C at Jaipur South	Partial (4%)	LILO of Agra-Bassi D/C at Jaipur South
13	400kV	Agra-Jaipur South	2	D/C	254	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Agra-Bassi D/C at Jaipur South	Partial (4%)	
14	400kV	Agra-Sikar	1	D/C	386	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (3%)	
15	400kV	Agra-Sikar	2	D/C	386	POWERGRID	POWERGRID	POWERGRID	Twin Moose	]	Partial (3%)	
16	400kV	Ajmer-Ajmer(PG)	1	D/C	66	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
17	400kV	Ajmer-Ajmer(PG)	2	D/C	66	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
18	400kV	Allahabad-Fatehpur	3	S/C	154	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Allahabad-Kanpur one ckt at Fatehpur	Polymer Insulator	
19	400kV	Allahabad-Fatehpur	1	D/C	140	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Lilo of Allahabad-Mainpuri (PG) D/C at Fatehpur	Conventional	
20	400kV	Allahabad-Fatehpur	2	D/C	140	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Lilo of Allahabad-Mainpuri (PG) D/C at Fatehpur	Conventional	
21	400kV	Allahabad-Varanasi	1	D/C	99	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Allahabad-Sarnath shifted from Sarnath to Varanasi	Conventional	
22	400kV	Allahabad-Kanpur	1	S/C	225	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
23	400kV	Allahabad-Kanpur(New 765)	1	D/C	240	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
24	400kV	Allahabad-Kanpur(New 765)	2	D/C	240	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
25	400kV	Allahabad-Meja(NTPC)	1	D/C	28	POWERGRID	POWERGRID	MUNPL	Twin Moose		Polymer Insulator	MUNPL is joint venture
26	400kV	Allahabad-Meja(NTPC)	2	D/C	28	POWERGRID	POWERGRID	MUNPL	Twin Moose		Polymer Insulator	between NTPC and
27	400kV	Amritsar-Jalandhar	1	S/C	60	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
28	400kV	Amritsar-Jalandhar	2	D/C	71	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	LILO of 400kV Amritsar- Hamirpur at Jalandhar
29	400kV	Amritsar-ParbatiPooling (Banala)	1	D/C	251	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (49%)	
30	400kV	Auraiya-Agra	1	D/C	166	POWERGRID	NTPC	POWERGRID	Twin Moose		Partial (86%)	
31	400kV	Auraiya-Agra	2	D/C	166	POWERGRID	NTPC	POWERGRID	Twin Moose		Partial (90%)	
32	400kV	Baglihar II-Kishenpur	1	s/c	130	POWERGRID	JKSPDCL	POWERGRID	Twin Moose	LILO of 400kV Kishenpur-New Wanpoh ckt-2 at Baglihar. LILO portion is of JK PDD	Conventional	
33	400kV	Baghlihar II-New Wanpoh	1	S/C	130	POWERGRID	JKSPDCL	POWERGRID	Twin Moose		Not Available	
34	400kV	Bagpat-Kaithal	1	D/C	154	POWERGRID	POWERGRID	POWERGRID	Quad Moose	LILO of Meerut-Kaithal DC at Baghpat	Polymer Insulator	
35	400kV	Bagpat-Kaithal	2	D/C	154	POWERGRID	POWERGRID	POWERGRID	Quad Moose	LILO of Meerut-Kaithal DC at Baghpat	Polymer Insulator	
36	400kV	Bagpat-Saharanpur	1	D/C	121	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Partial (41%)	
37	400kV	Bagpat-Dehradun	1	D/C	165	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Partial (40%)	
38	400kV	Bahadurgarh-Kabulpur	1	S/C	42	POWERGRID	POWERGRID	HVPNL	Twin Moose		Polymer Insulator	LILO of Bahadurgarh- Bhiwani at Kabulpur
39	400kV	Bahadurgarh-Sonepat	1	D/C	53	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	

40	400kV	Bahadurgarh-Sonepat	2	D/C	53	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	
41	400kV	Balia-Mau	1	D/C	9	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Conventional	
42	400kV	Balia-Sohawal	1	D/C	229	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Balia- LUCKNOW D/C at Sohawal	Conventional	LILO of Balia-Lucknow (316 KM) D/C at Sohawal
43	400kV	Balia-Sohawal	2	D/C	229	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Balia- LUCKNOW D/C at Sohawal	Conventional	LILO of Balia-Lucknow (316 KM) D/C at Sohawal
44	400kV	Ballabgarh-Tughlakabad	1	M/C	40	DTL	POWERGRID	POWERGRID	HTLS INVAR (LILO portion) & Bersimis (before	Tower is quad circuit tower	Polymer	
45	400kV	Ballabgarh-Tughlakabad	2	M/C	40	DTL	POWERGRID	POWERGRID	LILO)	Tower is quad circuit tower	Polymer	
46	400kV	Ballabhgarh-Gurgaon	1	S/C	43	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
47	400kV	Ballabhgarh-Maharanibagh	1	D/C	61	POWERGRID	POWERGRID	POWERGRID	Quad Bersimis	Bypassed at Maharanibagh to form Dadri-Ballabgarh	Polymer Insulator	
48	400kV	Ballabhgarh-Nawada	1	D/C	13	POWERGRID	POWERGRID	HVPNL	Quad Bersimis		Polymer Insulator	Ballabhgarh-Gnoida LILOed at Nawada (Faridabad,Haryana)
49	400kV	Bareilly PG-Moradabad	1	D/C	93	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Partial (3%)	
50	400kV	Bareilly PG-Rampur_PRSTL	1	S/C	40	POWERGRID	POWERGRID	UPPTCL	Twin Moose	After LILO of 400 KV BAREILLY(PG)- MORADABAD(UPPTCL) CIRCUIT-II at RAMPUR(PRSTL)	Not Available	
51	400kV	Rampur_PRSTL-Moradabad	1	s/c	57	POWERGRID	UPPTCL	UPPTCL	Twin Moose	After LILO of 400 KV BAREILLY(PG)- MORADABAD(UPPTCL) CIRCUIT-II at RAMPUR(PRSTL)	Not Available	
52	400kV	Bareilly PG-Bareilly (765kV)	1	D/C	2	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Conventional	
53	400kV	Bareilly PG-Bareilly (765kV)	2	D/C	2	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Conventional	
54	400kV	Bareilly PG(765kV)-Kashipur	1	D/C	101	POWERGRID	POWERGRID	PTCUL	Quad Moose		Partial (90%)	
55	400kV	Bareilly PG(765kV)-Kashipur	2	D/C	101	POWERGRID	POWERGRID	PTCUL	Quad Moose		Partial (90%)	
56	400kV	Bassi-Bhiwadi	2	S/C	220	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
57	400kV	Bassi-Heerapura	1	D/C	48	POWERGRID	POWERGRID	RRVPNL	Twin Moose		Polymer Insulator	
58	400kV	Bassi-Heerapura	2	D/C	49	POWERGRID	POWERGRID	RRVPNL	Twin Moose		Polymer Insulator	
59	400kV	Bassi-Kotputli	1	s/c	106	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
60	400kV	Bassi-Phagi	1	D/C	48	POWERGRID	POWERGRID	RRVPNL	Quad Moose		Partial (26%)	
61	400kV	Bassi-Phagi	2	D/C	48	POWERGRID	POWERGRID	RRVPNL	Quad Moose		Partial (26%)	
62	400kV	Bassi-Sikar	1	D/C	170	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (16%)	
63	400kV	Bassi-Sikar	2	D/C	170	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (17%)	
64	400kV	Bawana(CCGT)-Bahadurgarh	1	D/C	49	POWERGRID	DTL/Pragati CCGT	POWERGRID	Twin Moose		Polymer Insulator	
65	400kV	Bhadla-Bhadla(PG)	1	D/C	27	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
66	400kV	Bhadla-Bhadla(PG)	2	D/C	27	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
67	400kV	Bhadla-Bhadla II	1	D/C	52	POWERGRID	POWERGRID	POWERGRID	Twin HTLS+Hexa Zebra	48.309KM Twin HTLS conductor of	Not Available	
68	400kV	Bhadla-Bhadla II	2	D/C	52	POWERGRID	POWERGRID	POWERGRID	Twin HTLS+Hexa Zebra	POWERGRID and 3.73 KM HEXA Zebra of FBTL	Not Available	
69	400kV	Bhinmal-Kankroli	1	D/C	202	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Bhinmal to form 400kV Kankroli Zerda ckt-2	Polymer Insulator	
70	400kV	Bhiwadi-Gurgaon	1	S/C	83	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
71	400kV	Bhiwadi-Hissar	1	S/C	212	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
72	400kV	Bhiwadi-Hissar	2	D/C	144	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	LILO of Bhiwadi-Moga both ckts at Hisar
73	400kV	Bhiwadi-Hissar	3	D/C	144	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
74	400kV	Bhiwadi-NeemranaPG	1	D/C	48	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
75	400kV	Bhiwadi-NeemranaPG	2	D/C	48	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Hissar to	Polymer Insulator	
76	400kV	Bhiwani BBMB - Hissar	1	S/C	35	POWERGRID	POWERGRID	POWERGRID	Twin Moose	form Bhiwani BBMB- Fatehabad	Polymer Insulator	

										_ <del>_</del>		
77	400kV	Bhiwani (PG) - Hissar	1	s/c	64	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Hissar to form Moga- Bhiwani(PG)	Polymer Insulator	LILO of Bawana-Hisar (132KM) at Bhiwani PG
78	400kV	Bhiwani (PG) - Hissar	2	D/C	57	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at	Polymer Insulator	
79	400kV	Bhiwani (PG) - Hissar	3	D/C	57	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bhiwani(PG) to form	Polymer Insulator	
80	400kV	Bhiwani PG - Jind	1	D/C	82	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
81	400kV	Bhiwani PG - Jind	2	D/C	82	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
82	400kV	Bhiwani PG- BawanaCCGT	1	D/C	97	POWERGRID	POWERGRID	DTL/ CCGT	Twin Moose		Polymer Insulator	LILO of Bawana-Hisar (132KM) at Bhiwani PG
83	400kV	Bhiwani PG- Bhiwani BBMB	1	s/c	34	POWERGRID	POWERGRID	ВВМВ	Twin Moose		Polymer Insulator	LILO of Bhiwani (BBMB)- Bahadurgarh (84km) at Bhiwani (PG)
84	400kV	Bhiwani PG-Kabulpur	1	S/C	48	POWERGRID	POWERGRID	HVPNL	Twin Moose		Polymer Insulator	LILO of Bahadurgarh- Bhiwani at Kabulpur
85	400kV	Bikaner_2 (PBTSL)-Bikaner(PG)	1	D/C	43	POWERGRID	PBTSL	POWERGRID	Quad Moose		Not Available	
86	400kV	Bikaner_2 (PBTSL)-Bikaner(PG)	2	D/C	43	POWERGRID	PBTSL	POWERGRID	Quad Moose		Not Available	
87	400kV	Chamba pool - Jalandhar	1	D/C	162	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (48%)	
88	400kV	Chamba pool - Jalandhar	2	D/C	162	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (48%)	
89	400kV	Chamera-II - Chamba Pool	1	S/C	0.38	POWERGRID	NHPC	POWERGRID	Twin Moose		Conventional	Two tower is S/C and one tower is D/C
90	400kV	Chamera-II-Chamera-I	1	S/C	36	POWERGRID	NHPC	NHPC	Twin Moose		Conventional	
91	400kV	Chamera-II-Kishenpur	1	S/C	135	POWERGRID	NHPC	POWERGRID	Twin Moose		Conventional	
92	400kV	Chamera-I-Jalandhar	1	D/C	152	POWERGRID	NHPC	POWERGRID	Twin ACAR		Partial (43%)	
93	400kV	Chamera-I-Jalandhar	2	D/C	152	POWERGRID	NHPC	POWERGRID	Twin ACAR		Partial (43%)	
94	400kV	Chittorgarh-Chittorgarh(PG)	1	D/C	49	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
95	400kV	Chittorgarh-Chittorgarh(PG)	2	D/C	49	POWERGRID	RRVPNL	POWERGRID	Quad Moose		Not Available	
96	400kV	Chittorgarh-Kankroli	1	D/C	71	POWERGRID	RRVPNL	POWERGRID	Twin Moose		Polymer Insulator	LILO of 400 kV Rapp C- Kankroli at Chhitorgarh
97	400kV	Dadri NCTPP-G. Noida	1	D/C	13	POWERGRID	NTPC	UPPCL	Quad Bersimis		Polymer Insulator	
98	400kV	Dadri NCTPP-Maharanibagh	1	D/C	54	POWERGRID	NTPC	POWERGRID	Quad Bersimis	Bypassed at Maharanibagh to form Dadri-Ballabgarh	Polymer Insulator	
99	400kV	Dadri NCTPP-Kaithal	1	S/C	213	POWERGRID	NTPC	POWERGRID	Twin Moose	LILO of Dadri- Malerkotla at Kaithal	Polymer Insulator	
100	400kV	Dadri NCTPP-Mandola	1	D/C	46	POWERGRID	NTPC	POWERGRID	Quad Bersimis		Polymer Insulator	
101	400kV	Dadri NCTPP-Mandola	2	D/C	46	POWERGRID	NTPC	POWERGRID	Quad Bersimis		Polymer Insulator	
102	400kV	Dadri NCTPP-Muradnagar New	1	s/c	33	POWERGRID	NTPC	UPPTCL	Twin Moose		Polymer Insulator	Line shifted from Muradnagar to Muradnagar New (UPPTCL)
103	400kV	Dadri NCTPP-Panipat	1	S/C	112	POWERGRID	NTPC	BBMB	Twin Moose		Polymer Insulator	
104	400kV	Dadri NCTPP-Panipat	2	S/C	117	POWERGRID	NTPC	BBMB	Twin Moose		Polymer Insulator	
105	400kV	Deepalpur-Bawana	1	D/C	26	POWERGRID	KT-Jhajjar	DTL	Triple Snowbird	LILO of 400kV Bawana- Abdullapur one circuit at Deepalpur by Jhajjar KT	Polymer Insulator	
106	400kV	Dehradun-Abdullapur	1	D/C	89	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Not Available	
107	400kV	Dehradun-Abdullapur	2	D/C	89	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Not Available	
108	400kV	Dulhasti-Kishenpur	1	S/C	120	POWERGRID	NHPC	POWERGRID	Quad Moose		Conventional	
109	400kV	Dulhasti-Kishenpur	2	S/C	120	POWERGRID	NHPC	POWERGRID	Quad Moose		Conventional	
110	400kV	Dwarka-Jhatikara	1	S/C	18	POWERGRID	POWERGRID	POWERGRID	Twin HTLS	After LILO of 400KV	Not Available	
111	400kV	Dwarka-Bamnauli	1	S/C	10	POWERGRID	POWERGRID	DTL	Twin HTLS	Jhatikara-Bamnoli-I at	Not Available	
112	400kV	Fatehbad PG-Hissar	1	D/C	89	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Hissar to form Bhiwani BBMB- Fatehabad	Polymer Insulator	
113	400kV	Fatehpur-Kanpur	1	S/C	100	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Kanpur to	Polymer Insulator	LILO of Singrauli-
114	400kV	Fatehpur-Kanpur	2	s/c	107	POWERGRID	POWERGRID	POWERGRID	Twin Moose	form Fatehpur-Panki	Partial (64%)	LILO of Allahabad- Kanpur one ckt at Fatehpur
115	400kV	Kanpur-Panki	1	S/C	6	POWERGRID	POWERGRID	UPPTCL	Twin Moose	Bypassed at Kanpur to	Polymer Insulator	. Etc. pa
116	400kV	Kanpur-Panki	2	S/C	6	POWERGRID	POWERGRID	UPPTCL	Twin Moose	form Fatehpur-Panki	Polymer Insulator	
		1 - 1		-, -	<u> </u>						,	

132   400kV   58thpur Mainpurt   2   01/C   250   POWERGRID   POWERGRID   Twin Moore   Lill of Ballabgarh-   Continue							1					
138							1	1		1		LILO of Allahabad- Mainpuri (363 KM) D/C
138												at Fatehpur
1	400kV	Fatehpur-Mainpuri	1	D/C	260	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	Series compensated line
1												(Degree of comp 40%)
1	400kV	Fatehpur-Mainpuri	2	D/C	260	POWERGRID	POWFRGRID	POWERGRID	Twin Moose	+	Conventional	-
19				-, -	200					Lilo of Ballabgarh-	Conventional	Ballabhgarh-Gnoida
121   121   122   123	400kV	G.Noida-Nawada	1	D/C	30	POWERGRID	UPPTCL	HVPNL	Quad Bersimis		Polymer Insulator	LILOed at Nawada
121   121   122   123												(Faridabad, Haryana)
ADDAY   Gorakhpur PG-Lucknow PG	400kV	Gorakhpur PG-Gorakhpur UP	1	D/C	46	POWERGRID	POWERGRID	UPPCL	Twin Moose		Polymer Insulator	Partial Planning has
ADDAY   Gorakhpur PG-Lucknow PG												been completed
123	400kV	Gorakhpur PG-Gorakhpur UP	2	D/C	46	POWERGRID	POWERGRID	UPPCL	Twin Moose		Polymer Insulator	Partial Planning has
124												been completed
124   400kV   Gorakhpur PG-Basti (UP)   1   D/C   117   POWERGRID   POWERGRID   UPFTCL   Twin Moose   Cock 4 at Basti (UP)   LUC of 400kV						<del></del>					Partial (3%)	At crossing
124   400kV   Gorakhpur PG-Basti (UP)   1   D/C   117   POWERGRID   POWERGRID   UPPTCL   Twin Moose   Corakhpur PG-Basti (UP)   LILO   portion is of UP   LILO   portion is	400kV	Gorakhpur PG-Lucknow PG	2	D/C	264	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (3%)	At crossing
126												
125												
125	400kV	Gorakhpur PG-Basti (UP)	1	D/C	117	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Not Available	
125												
126	4001-17	Caralibaria DC Basti (UD)	2	D/C	400	DOMEDOND	DOMEDOND	LIDDTCI	Turin Manne		Not Available	
126	400KV	Goraknpur PG-Basti (OP)	2	D/C	108	POWERGRID	POWERGRID	UPPICE	i win ivioose		NOT Available	
126												
127										LILO portion is or or		
128	400kV	Basti (UP)-Lucknow PG	1	D/C	204	POWERGRID	UPPTCL	POWERGRID	Twin Moose		Not Available	
129   400kV	400kV	Gurgaon-Sohna Road	1	D/C	7	POWERGRID	POWERGRID	GPTL	Quad Moose	LILO of 400kV Gurgaon	Not Available	
130   400kV   Jaipur South-Bassi   1   D/C   37   POWERGRID   POWERGRID   POWERGRID   POWERGRID   Twin Moose   LILO of Agra-Bassi D/C at Jaipur South	400kV	Gurgaon-Sohna Road	2	D/C	7	POWERGRID	POWERGRID	GPTL	Quad Moose	Manesar D/C at Sohna	Not Available	
130												LILO of Amritsar- Banala
131 400kV Jaipur South-Bassi 2 D/C 37 POWERGRID POWERGRID POWERGRID Twin Moose LILO of Agra-Bassi D/C Poly at Jaipur South-Kota 1 D/C 180 POWERGRID POWERGRID POWERGRID Twin Moose LILO of Agra-Bassi D/C Poly at Jaipur South-Kota 1 D/C 180 POWERGRID POWERGRID POWERGRID Twin Moose MR 133 400kV Jaipur South-RAPP D 1 D/C 228 POWERGRID POWERGRID NPCIL Twin Moose Not 134 400kV Jaindhar-Nakodar 1 D/C 42 POWERGRID POWERGRID POWERGRID PSTCL Quad Moose Poly 135 400kV Jaindhar-Hamirpur 1 D/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly 135 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 137 400kV Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly 139 400kV Kankroli-Jodhpur 1 S/C 138 POWERGRID POWERGRID POWERGRID Twin Moose Poly 140 400kV Kankroli-Jodhpur 1 S/C 240 POWERGRID POWERGRID POWERGRID Twin Moose C 141 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C 141 400kV Kanpur-Ayraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose C	400kV	Hamirpur-ParbatiPooling (Banala)	1	D/C	77	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	1 at Hamirpur
131   400kV   Jaipur South-Bassi   2   D/C   37   POWERGRID   POWERGRID   POWERGRID   Twin Moose   LILO of Agra-Bassi D/C at Jaipur South   1   D/C   180   POWERGRID   POWERGRID   POWERGRID   Twin Moose   LILO of Agra-Bassi D/C at Jaipur South   1   D/C   180   POWERGRID   POWERGRID   POWERGRID   Twin Moose   No.   133   400kV   Jaipur South-RAPP D   1   D/C   228   POWERGRID   POWERGRID   NPCIL   Twin Moose   No.   No.   134   400kV   Jailandhar-Nakodar   1   D/C   42   POWERGRID   POWERGRID   PSTCL   Quad Moose   Poly   135   400kV   Jailandhar-Hamirpur   1   D/C   135   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Poly   136   400kV   Kaithal-Hissar   1   D/C   113   POWERGRID   POWERGRID   POWERGRID   Triple Snowbird   LILO of at Kaithal   137   400kV   Kaithal-Hissar   2   D/C   113   POWERGRID   POWERGRID   POWERGRID   Triple Snowbird   LILO of at Kaithal   138   400kV   Kaithal-Malerkotla   1   S/C   135   POWERGRID   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Poly   139   400kV   Kanthal-Malerkotla   1   S/C   135   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Poly   139   400kV   Kanthal-Malerkotla   1   S/C   188   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV   Kanpur-Auraiya   1   D/C   73   POWERGRID   POWERGRID   NTPC   Twin Moose   Compared   141   400kV	400kV	Jaipur South-Bassi	1	D/C	37	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	LILO of Agra-Bassi D/C at Jaipur South
132	400kV	Jaipur South-Bassi	2	D/C	37	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	de salpai sodai
132 400kV Jaipur South-Kota 1 D/C 180 POWERGRID POWERGRID POWERGRID Twin Moose No. 133 400kV Jaipur South-RAPP D 1 D/C 228 POWERGRID POWERGRID NPCIL Twin Moose No. 134 400kV Jalandhar-Nakodar 1 D/C 42 POWERGRID POWERGRID POWERGRID PSTCL Quad Moose Poly. 135 400kV Jalandhar-Hamirpur 1 D/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly. 136 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal-138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly. 139 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly. 139 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID POWERGRID Twin Moose Co. 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Co.			_	, ,							.,	
134 400kV Jalandhar-Nakodar 1 D/C 42 POWERGRID POWERGRID PSTCL Quad Moose Poly 135 400kV Jalandhar-Hamirpur 1 D/C 135 POWERGRID POWERGRID POWERGRID Twin Moose  136 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaitha 137 400kV Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaitha 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaitha 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly 139 400kV Kantroli-Jodhpur 1 S/C 188 POWERGRID POWERGRID RRVPNL Twin HTLS Co 140 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID Twin Moose Co 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID Twin Moose Co	400kV	Jaipur South-Kota	1	D/C	180	POWERGRID	POWERGRID	POWERGRID	Twin Moose	· ·	Not Available	
135 400kV Jalandhar-Hamirpur 1 D/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Part 136 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 137 400kV Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Poly 139 400kV Kanthal-Malerkotla 1 S/C 188 POWERGRID POWERGRID RRVPNL Twin HTLS COLUMN 140 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID POWERGRID Twin Moose Column 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Column 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Column 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Column 145 Co	400kV	Jaipur South-RAPP D	1	D/C	228	POWERGRID	POWERGRID	NPCIL	Twin Moose		Not Available	
136 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 137 400kV Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Polyl 139 400kV Kankroli-Jodhpur 1 S/C 188 POWERGRID POWERGRID RRVPNL Twin HTLS Ca 140 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID Twin Moose Ca 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Ca 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Ca 150 August 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose	400kV	Jalandhar-Nakodar	1	D/C	42	POWERGRID	POWERGRID	PSTCL	Quad Moose		Polymer Insulator	
136 400kV Kaithal-Hissar 1 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 137 400kV Kaithal-Hissar 2 D/C 113 POWERGRID POWERGRID POWERGRID Triple Snowbird LILO of at Kaithal 138 400kV Kaithal-Malerkotla 1 S/C 135 POWERGRID POWERGRID POWERGRID Twin Moose Polyl 139 400kV Kankroli-Jodhpur 1 S/C 188 POWERGRID POWERGRID RRVPNL Twin HTLS Ca 140 400kV Kanpur-Agra 1 S/C 240 POWERGRID POWERGRID Twin Moose Ca 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Ca 141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Ca 150 August 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose												LILO of 400kV Amritsar-
137	400kV	Jalandhar-Hamirpur	1	D/C	135	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (43%)	Hamirpur at Jalandhar
137												
137         400kV         Kaithal-Hissar         2         D/C         113         POWERGRID         POWERGRID         POWERGRID         Triple Snowbird         LILO of at Kaithal           138         400kV         Kaithal-Malerkotla         1         S/C         135         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Poly           139         400kV         Kankroli-Jodhpur         1         S/C         188         POWERGRID         POWERGRID         RRVPNL         Twin HTLS         Co           140         400kV         Kanpur-Agra         1         S/C         240         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co           141         400kV         Kanpur-Auraiya         1         D/C         73         POWERGRID         POWERGRID         NTPC         Twin Moose         Co	400kV	Kaithal-Hissar	1	D/C	113	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		LILO of Patiala-Hissar	
138   400kV   Kaithal-Malerkotla   1   S/C   135   POWERGRID   POWERGRID   POWERGRID   Twin Moose   Polyv				- /-								
138         400kV         Kaithal-Malerkotla         1         S/C         135         POWERGRID         POWERGRID         Twin Moose         Polys           139         400kV         Kankroli-Jodhpur         1         S/C         188         POWERGRID         POWERGRID         RRVPNL         Twin HTLS         Co           140         400kV         Kanpur-Agra         1         S/C         240         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co           141         400kV         Kanpur-Auraiya         1         D/C         73         POWERGRID         POWERGRID         NTPC         Twin Moose         Co	400kV	Kaithal-Hissar	2	D/C	113	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		LILO of Patiala-Hissar	
139         400kV         Kankroli-Jodhpur         1         S/C         188         POWERGRID         POWERGRID         RRVPNL         Twin HTLS         Co           140         400kV         Kanpur-Agra         1         S/C         240         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co           141         400kV         Kanpur-Auraiya         1         D/C         73         POWERGRID         POWERGRID         NTPC         Twin Moose         Co	40011/	W-96-144-1-1-1		6/6	425	DOWEDOND	DOWEDOND	DOM/EDODID	T 1: 14:		Polymer Insulator	
140         400kV         Kanpur-Agra         1         S/C         240         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co           141         400kV         Kanpur-Auraiya         1         D/C         73         POWERGRID         POWERGRID         NTPC         Twin Moose         Co											Conventional	
141 400kV Kanpur-Auraiya 1 D/C 73 POWERGRID POWERGRID NTPC Twin Moose Co											Conventional	
			_								Conventional	
The following the first terms of											Conventional	
	700KV	nanpa radiya	+ -	- D/C	<del>- ''</del>	704451101110	· OWENGIND	11110	I WIII WIOOGC	+	Conventional	*Sorios
143 400kV Kanpur-Ballabgarh 1 S/C 386 POWERGRID POWERGRID Twin Moose	40014	Kannur-Rallahgarh	1	sir	306	POWEDCDID	POWEDCHID	POWEDGDID	Twin Moose		Polymer Insulator	*Series Compensated,Ckt 1-
TOWERONID FOWERONID FOWERONID FOWERONID INITIALIZED	40UKV	Indiput-pallabgaili	1	3/0	300	FOWENDRID	FOWERGRID	FOWERGRID	I WIII IVIOUSE		Polymer insulator	35%, Ckt-2 & 3-40%
										+		*Series
144 400kV Kanpur-Ballabgarh 2 D/C 371 POWERGRID POWERGRID Twin Moose	400kV	Kanpur-Ballabgarh	2	D/C	371	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	Compensated,Ckt 1-
				] -,-							2.,	35%, Ckt-2 & 3-40%
					i							*Series
145 400kV Kanpur-Ballabgarh 3 D/C 371 POWERGRID POWERGRID Twin Moose Poly	400kV	Kanpur-Ballabgarh	3	D/C	371	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	Compensated,Ckt 1-
					<u> </u>							35%, Ckt-2 & 3-40%
		Kanpur-Kanpur(GIS)	1	D/C	21				Quad Moose		Polymer Insulator	
	400kV	Kanpur-Kanpur(GIS)	2	D/C	21			POWERGRID			Polymer Insulator	
	400kV	Kanpur(GIS)-Lucknow(765)	1	D/C	160	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
	400kV	Kanpur(GIS)-Lucknow(765)	2	D/C	160	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
149         400kV         Kanpur(GIS)-Lucknow(765)         2         D/C         160         POWERGRID         POWERGRID         Twin Moose         No		Wichonnur Nou/Mannoh	1 1	D/C	130	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
149         400kV         Kanpur(GIS)-Lucknow(765)         2         D/C         160         POWERGRID         POWERGRID         POWERGRID         Twin Moose           150         400kV         Kishenpur-NewWanpoh         1         D/C         130         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co												
149         400kV         Kanpur(GIS)-Lucknow(765)         2         D/C         160         POWERGRID         POWERGRID         POWERGRID         Twin Moose         No           150         400kV         Kishenpur-NewWanpoh         1         D/C         130         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co           151         400kV         Kishenpur-NewWanpoh         3         D/C         135         POWERGRID         POWERGRID         POWERGRID         Twin Moose         Co	400kV	Kishenpur-NewWanpoh	3	D/C							Conventional Not Available	

153	400kV	Kishenpur-Samba	1 1	D/C	35	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
154	400kV	Kishenpur-Samba	2	D/C	35	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
155	400kV	Kota-Merta	1	D/C	256	POWERGRID	POWERGRID	RRVPNL	Twin Moose		Conventional	
156	400kV	Kotputli-Bhiwadi	1	S/C	132	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	LILO of Bassi-Bhiwadi-
157	400kV	Kurukshetra-Jind	1	D/C	103	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Not Available	2 at Kotputli
158	400kV	Kurukshetra-Jind	2	D/C	103	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Not Available	
159	400kV	Kurukshetra-Sonipat	1	D/C	125	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird (Twin HTLS	LILO of Abdullapur-	Partial (99%)	LILO of Abdullapr-
160	400kV	Kurukshetra-Sonipat	2	D/C	125	POWERGRID	POWERGRID	POWERGRID	for LILOportion)	Sonipat line at	Partial (99%)	1 '
161	400kV	Kurukshetra(PG)-Dhanansu(PS)	1	D/C	165	POWERGRID	POWERGRID	PSTCL	Quad Moose	Kurukshetra-Jalandhar	Polymer Insulator	LILO portion to be
162	400kV	Dhanansu(PS)-Jalandhar(PG)	1	D/C	106	POWERGRID	PSTCL	POWERGRID	Quad Moose	(LILO portion is of	Polymer Insulator	checked
163	400kV	Kurukshetra-Nakodar	1	D/C	234	POWERGRID	POWERGRID	PSTCL	Quad Moose	` '	Polymer Insulator	
164	400kV	Lucknow-Basti	1	D/C	203	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Not Available	
165	400kV	Lucknow-Basti	2	D/C	203	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Not Available	
166	400kV	Lucknow PG-Lucknow UP	1	S/C	63	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Conventional	
167	400kV	Lucknow PG-Unnao	1	D/C	74	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Conventional	
168	400kV	Lucknow PG-Unnao	2	D/C	74	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Conventional	
169	400kV	Lucknow UP-Bareilly PG	1	S/C	279	POWERGRID	UPPTCL	POWERGRID	Twin Moose		Conventional	
170	400kV	765 Lucknow (PG) - Lucknow (PG)	1	D/C	3	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Polymer Insulator	
171	400kV	765 Lucknow (PG) - Lucknow (PG)	2	D/C	3	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Polymer Insulator	
172	400kV	LucknowPG-Sohawal	1	D/C	98	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	LILO of Balia-Lucknow (316 KM) D/C at
173	400kV	LucknowPG-Sohawal	2	D/C	98	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	Sohawal
174	400kV	Lucknow PG-Shahjahanpur	1	D/C	170	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (10%)	
175	400kV	Lucknow PG-Shahjahanpur	2	D/C	170	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Partial (10%)	
176	400kV	Lucknow-Jehta	1	D/C	32	POWERGRID	POWERGRID	UPPTCL	Twin Moose	LILO of 400kV Lucknow	Not Available	
177	400kV	Lucknow-Jehta	2	D/C	32	POWERGRID	POWERGRID	UPPTCL	Twin Moose	Unnao DC at Jehta (UP).	Not Available	
178	400kV	Ludhiana-Jalandhar	1	S/C	85	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
179	400kV	Ludhiana-Malerkotla	1	S/C	36	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
180	400kV	Ludhiana-Patiala	1	D/C	76	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
181	400kV	Ludhiana-Patiala	2	D/C	76	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
182	400kV	Mainpuri-Ballabgarh	1	D/C	236	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
183	400kV	Mainpuri-Ballabgarh	2	D/C	236	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
184	400kV	Malerkotla-Patiala	1	S/C	62	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
185	400kV	Manesar- Sohna Road	1	D/C	17	POWERGRID	POWERGRID	GPTL	Quad Moose	LILO of 400kV Gurgaon	Not Available	
186	400kV	Manesar- Sohna Road	2	D/C	17	POWERGRID	POWERGRID	GPTL	Quad Moose	Manesar D/C at Sohna	Not Available	
187	400kV	Mandola-Maharanibagh	1	D/C (LILO towers are M/C)	29	POWERGRID	POWERGRID	POWERGRID	Twin HTLS	After LILO of 400KV Mandola-Bawana D/C Lines at 400KV	Not Available	
188	400kV	Mandola-Maharanibagh	2	D/C (LILO towers are M/C)	29	POWERGRID	POWERGRID	POWERGRID	Twin HTLS	Maharanibagh(PG)	Not Available	
189	400kV	Maharanibagh-Bawana	1	D/C	29	POWERGRID	POWERGRID	DTL	Twin HTLS		Not Available	
190	400kV	Maharanibagh-Bawana	2	D/C	29	POWERGRID	POWERGRID	DTL	Twin HTLS		Not Available	
191	400kV	Meerut-Bagpat	1	D/C	71	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Meerut-Kaithal DC at Baghpat	Polymer Insulator	
192	400kV	Meerut-Bagpat	2	D/C	71	POWERGRID	POWERGRID	POWERGRID	Twin Moose	LILO of Meerut-Kaithal DC at Baghpat	Polymer Insulator	
193	400kV	Meerut-Mandola	1	D/C	60	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
194	400kV	Meerut-Mandola	2	D/C	60	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
195	400kV	Meerut-Muzzafarnagar	1	S/C	37	POWERGRID	POWERGRID	UPPTCL	Twin Moose		Polymer Insulator	
196	400kV	Moga-Fatehabad	1	D/C	179	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
197	400kV	Moga-Hissar	1	D/C	209	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bypassed at Hissar to form Moga- Bhiwani(PG)	Polymer Insulator	
198	400kV	Moga-Hissar	2	D/C	206	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	LILO of Bhiwadi-Moga both ckts at Hisar
199	400kV	Moga-Hissar	3	D/C	206	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
200	400kV	Moga-Jalandhar	1	D/C	85	POWERGRID	POWERGRID	POWERGRID	Twin ACAR		Polymer Insulator	
201	400kV	Moga-Jalandhar	2	D/C	85	POWERGRID	POWERGRID	POWERGRID	Twin ACAR		Polymer Insulator	
							_	_				

		To a second										
202	400kV	Muradnagar-Hapur	1	s/c	28	POWERGRID	UPPTCL	UPPTCL	Twin Moose	Moradabad-	Not Available	
203	400kV	Moradabad-Hapur	2	S/C	109	POWERGRID	UPPTCL	UPPTCL	Twin Moose	Muradnagar LILOed at	Not Available	
204	400kV	Nallagarh-Koldam	1	D/C	46	POWERGRID	POWERGRID	NTPC	Quad Moose		Conventional	Koldam to Parbati
205	400kV	Nallagarh-Patiala	1	D/C	94	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	
206	400kV	Nallagarh-Patiala	2	D/C	94	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	
207	400kV	Nathpa Jhakri-Gumma	1	D/C	55	POWERGRID	SJVNL	HPPTCL	Triple Snowbird	LILO of DC Jhakri-	Not Available	
208	400kV	Nathpa Jhakri-Gumma	2	D/C	55	POWERGRID	SJVNL	HPPTCL	Triple Snowbird	Panchkula line at	Not Available	
209	400kV	Gumma-Panchkula	1	D/C	112	POWERGRID	HPPTCL	POWERGRID	Triple Snowbird	Gumma	Not Available	
210	400kV	Gumma-Panchkula	2	D/C	112	POWERGRID	HPPTCL	POWERGRID	Triple Snowbird	1	Not Available	
211	400kV	Nathpa Jhakri-RampurHEP	1	D/C	21	POWERGRID	SJVNL	SJVNL	Triple Snowbird	Nathpa Jhakri-	Conventional	LILO of Jhakri-Nalagarh
212	400kV	Nathpa Jhakri-RampurHEP	2	D/C	21	POWERGRID	SJVNL	SJVNL	Triple Snowbird	Nallagarh LILOed at	Conventional	- Lize or shaker Halagain
-	400kV	·							· ·	1150		
213	400kV 400kV	NeemranaPG-Manesar NeemranaPG-Manesar	1	D/C D/C	67	POWERGRID POWERGRID	POWERGRID POWERGRID	POWERGRID POWERGRID	Twin Moose Twin Moose		Polymer Insulator	
214	400KV	NeemranaPG-Manesar	2	D/C	67	POWERGRID	POWERGRID	POWERGRID	I WIN MOOSE	LILO PORTION IF OF	Polymer Insulator	LILO of 400kV
215	400kV	NeemranaPG-Babai	1	D/C	85	POWERGRID	POWERGRID	RRVPNL	Twin Moose	NRSS36(B), LILO of 400kV Neemrana-Sikar 1 at Babai	Not Available	Neemrana-Sikar at Babai by NRSSXXXVI (Essel group): Earlier 29% of Neemrana- Sikar PG
216	400kV	NeemranaPG-Sikar	2	D/C	176	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Not Available	
217	400kV	NewWanpoh-Wagoora	1	D/C	57	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
218	400kV	NewWanpoh-Wagoora	2	D/C	57	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
219	400kV	Orai(PG)-Orai	1	D/C	42	POWERGRID	POWERGRID	UPPTCL	Quad Moose		Not Available	
220	400kV	Orai(PG)-Orai	2	D/C	42	POWERGRID	POWERGRID	UPPTCL	Quad Moose		Not Available	
221	400kV	Panchkula -Abdullapur	1	D/C	63	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	LILO of Jhakri- Abdullapur at Panchkula
222	400kV	Panchkula -Abdullapur	2	D/C	63	POWERGRID	POWERGRID	POWERGRID	Triple Snowbird		Polymer Insulator	LILO of Jhakri-
223	400kV	Patiala-Panchkula	1	D/C	65	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
224	400kV	Patiala-Panchkula	2	D/C	65	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Polymer Insulator	
225	400kV	Patiala-Patran	1	D/C	79	POWERGRID	POWERGRID	PTCL	Triple Snowbird	LILO of 400kV D/C	Polymer Insulator	LILO of 400 kV Kaithal-
226	400kV	Patiala-Patran	2	D/C	79	POWERGRID	POWERGRID	PTCL	Triple Snowbird	Patiala – Kaithal Line at	Polymer Insulator	<b>T</b>
227	400kV	Patran-Kaithal	1	D/C	47	POWERGRID	PTCL	POWERGRID	Triple Snowbird	Patran SS under the	Polymer Insulator	<b>-</b>
228	400kV	Patran-Kaithal	2	D/C	47	POWERGRID	PTCL	POWERGRID	Triple Snowbird	ownership of PTCL.	Polymer Insulator	┥
229	400kV	RampurHEP-Nallagarh	1	D/C	128	POWERGRID	SJVNL	POWERGRID	Triple Snowbird	Nathpa Jhakri-	Conventional	LILO of Jhakri-Nalagarh
230	400kV	RampurHEP-Nallagarh	2	D/C	128	POWERGRID	SJVNL	POWERGRID	Triple Snowbird	Nallagarh LILOed at	Conventional	- Lizzo or shaker Halagaini
231	400kV	RAPS-C-Chittorgarh	1	D/C	155	POWERGRID	NPCIL	RRVPNL	Twin Moose	Name of the second of the seco	Partial (38%)	LILO of 400 kV Rapp C- Kankroli at Chhitorgarh
232	400kV	RAPS-C-Kankroli	1	D/C	199	POWERGRID	NPCIL	POWERGRID	Twin Moose		Partial (51%)	
233	400kV	RAPS-C-Kota	1	s/c	51	POWERGRID	NPCIL	POWERGRID	Twin Moose		Partial (55%)	400kV RAPS-Jaipur line whose work was completed till Kota section is connected with 400kV Raps-Kota#2 (for antitheft purpose) and hence 400kV RapsC-Kota #2 is now two twin moose lines connected in parallel paths
234	400kV	RAPS-C-Kota	2	D/C	55	POWERGRID	NPCIL	POWERGRID	Twin Moose	D/C with 400kV Jaipur- RAPP D line	Not Available	
235	400kV	Rasra-Balia	1	S/C	46	POWERGRID	UPPTCL	POWERGRID	Twin Moose	LILO of 400kV Balia-	Not Available	
236	400kV	Rasra-Mau	1	S/C	38	POWERGRID	UPPTCL	UPPTCL	Twin Moose	Mau-II at Rasara. LILO	Not Available	
237	400kV	Rihand-Allahabad	1	D/C	279	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
238	400kV	Rihand-Allahabad	2	D/C	279	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
239	400kV	Roorkee-Kashipur	1	D/C	151	POWERGRID	POWERGRID	PTCUL	Quad Moose		Partial (72%)	
240	400kV	Roorkee-Kashipur	2	D/C	151	POWERGRID	POWERGRID	PTCUL	Quad Moose		Partial (72%)	
241 242	400kV	Roorkee-Saharanpur	1	D/C	36	POWERGRID	POWERGRID	POWERGRID	Quad Moose		Polymer Insulator	
	400kV	Roorkee-Dehradun	1	D/C	80	POWERGRID	POWERGRID	POWERGRID	Quad Moose	1	Partial (50%)	

243	400kV	Sarnath-Varanasi	1	D/C	70	POWERGRID	UPPTCL	POWERGRID	Quad Moose		Partial (52%)	LILO of Sarnath- Allahabad (144 KM) at 765/400kV Varanasi
												705/HOOKV Varariasi
244	400kV	Sarnath-Varanasi	2	D/C	107	POWERGRID	UPPTCL	POWERGRID	Quad Moose		Partial (52%)	
245	400kV	Shahjahanpur-Bareilly PG	1	D/C	116	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
246	400kV	Shahjahanpur-Bareilly PG	2	D/C	116	POWERGRID	POWERGRID	POWERGRID	Twin Moose		Conventional	
247	400kV	Shahjahanpur-Rosa	1	D/C	8	POWERGRID	POWERGRID	UPPCL	Twin Moose		Not Available	
248	400kV	Shahjahanpur-Rosa	2	D/C	8	POWERGRID	POWERGRID	UPPCL	Twin Moose	1	Not Available	
249	400kV	Shree Cement-Kota	1	D/C	208	POWERGRID	Sh. Cement	POWERGRID	Twin Moose	<u> </u>	Polymer Insulator	
250	400kV	Shree Cement-Merta	2	D/C	103	POWERGRID	Sh. Cement	RRVPNL	Twin Moose		Polymer Insulator	
251	400kV	Sikar-Babai	1	D/C	95	POWERGRID	POWERGRID	RRVPNL	Twin Moose	LILO PORTION IF OF NRSS36(B), LILO of 400kV Neemrana-Sikar 1 at Babai	Not Available	
252	400kV	Sikar-Ratangarh	1	D/C	76	POWERGRID	POWERGRID	RRVPNL	Twin Moose		Conventional	
253	400kV	Sikar-Ratangarh	2	D/C	76	POWERGRID	POWERGRID	RRVPNL	Twin Moose		Conventional	
254	400kV	Singrauli-Allahabad	1	S/C	224	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
255	400kV	Singrauli-Allahabad	2	S/C	202	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
256	400kV	Singrauli-Allahabad	3	S/C	215	POWERGRID	NTPC	POWERGRID	Twin Moose		Not Available	
257	400kV	Singrauli-Anpara	1	S/C	25	POWERGRID	NTPC	UPPTCL	Twin Moose		Partial (91%)	
258	400kV	Singrauli-Fatehpur	1	S/C	331	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	LILO of Singrauli- Kanpur at Fatehpur
259	400kV	Singrauli-LucknowUP	1	S/C	409	POWERGRID	NTPC	UPPTCL	Twin Moose		Conventional	
260	400kV	Singrauli-Rihand	1	S/C	42	POWERGRID	NTPC	NTPC	Twin Moose		Conventional	
261	400kV	Singrauli-Rihand	2	S/C	44	POWERGRID	NTPC	NTPC	Twin Moose		Conventional	
262	400kV	Singrauli-Vindhyachal	1	S/C	3	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
263	400kV	Singrauli-Vindhyachal	2	S/C	5	POWERGRID	NTPC	POWERGRID	Twin Moose		Conventional	
264	400kV	Koteswar(PG)-Koteswar(THDC)	1	D/C	3	POWERGRID	POWERGRID	THDC	Twin Moose		Conventional	
265	400kV	Koteswar(PG)-Koteswar(THDC)	2	D/C	3	POWERGRID	POWERGRID	THDC	Twin Moose		Conventional	
266	400kV	Tehri-Koteshwar(PG)	3	S/C	14	POWERGRID	THDC	POWERGRID	Quad Moose		Not Available	
267	400kV	Unnao-Jehta	1	D/C	70	POWERGRID	UPPTCL	UPPTCL	Twin Moose	LILO of 400kV Lucknow Unnao DC at Jehta (UP). LILO portion is of UP	Not Available	
268	400kV	Unnao-Jehta	2	D/C	70	POWERGRID	UPPTCL	UPPTCL	Twin Moose	LILO of 400kV Lucknow Unnao DC at Jehta (UP). LILO portion is of UP	Not Available	
269	400kV	Uri-II - Uri-I	1	s/c	10	POWERGRID	NHPC	NHPC	Twin Moose		Conventional	LILO of 400kV Uri-I - Wagoora D/C at Amargarh
270	400kV	Uri-II - Wagoora	1	S/C	105	POWERGRID	NHPC	POWERGRID	Twin Moose		Conventional	1
271	400kV	Jauljivi-Bareilly_2	1	D/C	205	POWERGRID	POWERGRID	POWERGRID	Twin Moose	After LILO of 400kV Dhauliganga - Bareilly(UP) Double circuit line(Initially LILOed at Pithoragarh and charged at 220kV level) at Jauljivi(PG) After LILO of 400kV Dhauliganga -	Not Available	
272	400kV	Jauljivi-Bareilly_2	2	D/C	205	POWERGRID	POWERGRID	POWERGRID	Twin Moose	Bareilly(UP) Double circuit line(Initially LILOed at Pithoragarh and charged at 220kV level) at Jauljivi(PG)	Not Available	
B. POWE	RLINK Transmission L	td										
1	400kV	Bareilly PG-Meerut	1	D/C	250	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	LILO of Bareilly PG-
2	400kV	Bareilly PG-Meerut	2	D/C	250	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	Mandola-1 (241 Km) at
3	400kV	Bareilly UP-Bareilly PG	1	D/C	14	POWERLINK	UPPTCL	POWERGRID	Twin Moose		Polymer Insulator	
4	400kV	Bareilly UP-Bareilly PG	2	D/C	14	POWERLINK	UPPTCL	POWERGRID	Twin Moose		Polymer Insulator	
5	400kV	Gorakhpur PG-Lucknow PG	1	D/C	246	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	*Series compensated
6	400kV	Gorakhpur PG-Lucknow PG	2	D/C	246	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	line
7	400kV	Meerut-Mandola	3	D/C	102	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	LILO of Bareilly PG-
8	400kV	Meerut-Mandola	4	D/C	102	POWERLINK	POWERGRID	POWERGRID	Twin Moose		Conventional	Mandola-1&2 (241 Km)
C. PKTSL												

		L.,		- 1-								
1	400kV	Khetri-Sikar	1	D/C	78	PKTSL	PKTSL	POWERGRID	Twin HTLS		Not Available	4
2	400kV	Khetri-Sikar	2	D/C	78	PKTSL	PKTSL	POWERGRID	Twin HTLS		Not Available	
	Transmission India Ltd											_
1	400kV	Mahindergarh (APL)-Bhiwani PG	1	D/C	50	ATIL	APL	POWERGRID	Twin Moose		Conventional	4
2	400kV	Mahindergarh (APL)-Bhiwani PG	2	D/C	50	ATIL	APL	POWERGRID	Twin Moose		Conventional	4
3	400kV	Mahindergarh (APL)-Bhiwani PG	3	D/C	56	ATIL	APL	POWERGRID	Twin Moose	Bypassed at 400kV	Not Available	4
4	400kV	Mahindergarh (APL)-Bhiwani PG	4	D/C	56	ATIL	APL	POWERGRID	Twin Moose	Bhiwani to form 400kV	Not Available	
5	400kV	MahindergarhHVDC-Dhanonda	1	D/C	5	ATIL	APL	HVPNL	Quad Moose	Bypassed at Dhanonda	Conventional	
6	400kV	MahindergarhHVDC-Dhanonda	2	D/C	5	ATIL	APL	HVPNL	Quad Moose	to form	Conventional	
E. APCPL	(Aravali Power Corpor	ration Pvt Ltd.)										
1	400kV	Jhajjar (IGSTPS)-Mundka	1	D/C	66	APCPL	APCPL	DTL	Twin Moose		Polymer	
2	400kV	Jhajjar (IGSTPS)-Mundka	2	D/C	66	APCPL	APCPL	DTL	Twin Moose		Polymer	
F. PHTL(	Powergrid Himachal T	ransmission Limited)										_
1	400kV	Abdullapur-Kala Amb	1	D/C	39	PHTL	POWERGRID	PKATL	Quad Moose		Conventional	
2	400kV	Abdullapur-Kala Amb	2	D/C	39	PHTL	POWERGRID	PKATL	Quad Moose		Conventional	
3	400kV	Kala Amb- Wangtoo (HP)	1	D/C	174	PHTL	PKATL	HPPTCL	Quad Moose	Karcham-Kala Amb	Not Available	1
4	400kV	Karcham Wangtoo - Wangtoo (HP)	1	D/C	1	PHTL	JSW	HPPTCL	Quad Moose	LILOed at Wangtoo (HP)	Not Available	1
5	400kV	Karcham Wangtoo - Wangtoo (HP)	2	D/C	1	PHTL	JSW	HPPTCL	Quad Moose	1	Not Available	1
6	400kV	Baspa-Karcham Wangtoo	1	D/C	22	PHTL	JPVL	JSW	Triple snowbird		Conventional	1
7	400kV	Baspa-Karcham Wangtoo	2	D/C	22	PHTL	JPVL	JSW	Triple snowbird		Conventional	1
8	400kV	Karcham Wangtoo-NJPC	1	D/C	34	PHTL	JSW	SJVNL	Triple snowbird		Conventional	4
9	400kV	Karcham Wangtoo-NJPC Karcham Wangtoo-NJPC	2	D/C	34	PHTL	JSW	SJVNL	Triple snowbird		Conventional	<del>                                     </del>
10	400kV 400kV		1	D/C D/C	21	PHTL	SORANG	HPPTCL	Quad Moose		Not Available	4
		Sorang-Wangtoo										4
11	400kV	Sorang-Kala Amb	1	D/C	160	PHTL	SORANG	PKATL	Quad Moose		Not Available	<u> </u>
	(Parbati-Koldam Tran			D/C	4	DICTO	NTOC	DOMESCOID	Tatala Constitution		270/ Delawar 0 720/	_
1	400kV	Koldam-Ludhiana	1	D/C	151	PKTCL	NTPC	POWERGRID	Triple Snowbird		27% Polymer & 73% porcelain	
2	400kV	Koldam-Ludhiana	2	D/C	151	PKTCL	NTPC	POWERGRID	Triple Snowbird		27% Polymer & 73% porcelain	
3	400kV	Koldam-Banala	1	D/C	67	PKTCL	NTPC	POWERGRID	Quad Moose		100% porcelain	
4	400kV	Nallagarh-Banala	1	D/C	62	PKTCL	POWERGRID	POWERGRID	Quad Moose		100% porcelain	Powergrid owned 46.38km
5	400kV	Parbati-II- ParbatiPooling (Banala)	1	S/C	13	PKTCL	NHPC	POWERGRID	Quad Moose		100% porcelain	Some portion is of
6	400kV	Parbati-III- ParbatiPooling (Banala)	1	S/C	4	PKTCL	NHPC	POWERGRID	Quad Moose		100% porcelain	Powergrid
7	400kV	Parbati II- Sainj	1	S/C	1	PKTCL	NHPC	HPPCL	Quad Moose		100% porcelain	LILO of 400kV Parbati II
8	400kV	Parbati III- Sainj	1	S/C	9	PKTCL	NHPC	HPPCL	Quad Moose		100% porcelain	Parbati III at Saini
	RID:NRSS-29 Transmiss	· · · · · · · · · · · · · · · · · · ·										
1	400kV	Jalandhar-Samba	1	D/C	135	NRSS-29	POWERGRID	POWERGRID	Twin Moose		Polymer	
2	400kV	Jalandhar-Samba	2	D/C	135	NRSS-29	POWERGRID	POWERGRID	Twin Moose		Polymer	
3	400kV	Amargarh-Samba	1	D/C	286	NRSS-29	NRSS-29	POWERGRID	Twin Moose		Polymer	
4	400kV	Amargarh-Samba	2	D/C	286	NRSS-29	NRSS-29	POWERGRID	Twin Moose		Polymer	
5	400kV	Uri-I - Amargarh	1	D/C	62	NRSS-29	NHPC	NRSS-29	Twin Moose	LILO of 400kV D/C Uri-	Polymer	<u> </u>
6	400kV	Uri-I - Amargarh	2	D/C	62	NRSS-29	NHPC	NRSS-29	Twin Moose	I – Wagoora Line at	Polymer	
7	400kV	Amargarh - Wagoora	1	D/C	36	NRSS-29	NRSS-29	POWERGRID	Twin Moose	Amargarh SS under the	Polymer	<u> </u>
8	400kV	Amargarh - Wagoora	2	D/C	36	NRSS-29	NRSS-29	POWERGRID	Twin Moose	ownership of NRSS- XXIX.	Polymer	
	rid Unchahar Transmis			DIC	30	1411/35-23	1411,33-23	TOWEROND	1 WIII WIOO3C		i diyilici	4
1. Foweig	400kV	Fatehpur-Unchahar	1	D/C	54	PUTL	POWERGRID	NBPPL	Twin Moose		Not Available	
2	400kV 400kV	Fatehpur-Unchahar	2	D/C	54	PUTL	POWERGRID	NBPPL	Twin Moose		Not Available  Not Available	4
	(XI(B) (Sekura Energy)	ratenpar-onthanar		<i>υ/</i> C	J4	FUIL	FOWENDRID	NOFFL	I WIII MIOOSE		NOT AVAIIABLE	4
J. NKSSAA 1	400kV	Amritsar-Malerkotla	1	D/C	149	NRSSXXXXI(B)	POWERGRID	POWERGRID	Twin Moose		Dolymor	1
		*** ***	_	· ·		,					Polymer	
2	400kV	Amritsar-Malerkotla	2	D/C	149	NRSSXXXXI(B)	POWERGRID	POWERGRID	Twin Moose		Polymer	<del> </del>
3	400kV	Kurukshetra-Malerkotla	1	D/C	139	NRSSXXXXI(B)	POWERGRID	POWERGRID	Twin Moose		Polymer	4
4	400kV	Kurukshetra-Malerkotla	2	D/C	139	NRSSXXXXI(B)	POWERGRID	POWERGRID	Twin Moose		Polymer	
	on Palwal Transmission											_
1	400kV	Dhanoda-Neemrana	1	D/C	47	GPTL	HVPNL	POWERGRID	Twin HTLS	Bypassed at Dhanonda	Polymer	4
2	400kV	Dhanoda-Neemrana	2	D/C	47	GPTL	HVPNL	POWERGRID	Twin HTLS	to form	Polymer	
3	400kV	Prithala-Kadarpur	1	D/C	29	GPTL	GPTL	GPTL	Twin HTLS		Polymer	4
4	400kV	Prithala-Kadarpur	2	D/C	29	GPTL	GPTL	GPTL	Twin HTLS		Polymer	<u> </u>
5	400kV	Prithala(GPTL)-Aligarh(PG)	1	D/C	49	GPTL	GPTL	POWERGRID	Twin HTLS		Polymer	
6	400kV	Prithala(GPTL)-Aligarh(PG)	2	D/C	49	GPTL	GPTL	POWERGRID	Twin HTLS		Polymer	
7	400kV	Kadarpur-Sohna Road	1	D/C	10	GPTL	GPTL	GPTL	Twin HTLS		Polymer	
8	400kV	Kadarpur-Sohna Road	2	D/C	10	GPTL	GPTL	GPTL	Twin HTLS		Polymer	
L. FBTL												
1	400kV	AREPRL-Fatehgarh Pooling	1	D/C	1	FBTL	FBTL	FBTL	Quad moose		Not Available	
2	400kV	AREPRL-Fatehgarh Pooling	2	D/C	1	FBTL	FBTL	FBTL	Quad moose		Not Available	

										LILO of 400kV		
										Fatehgarh I-Bhadla-1 at		
3	400kV	Fatehgarh II-Fatehgarh Pooling	1	D/C	45	FBTL	POWERGRID	FBTL	Hexa Zebra+ Twin HTLS	Fatehgarh II. LILO Portion	Not Available	
										is of Powergrid		
4	400kV	Fatehgarh II-Fatehgarh Pooling	2	D/C	45	FBTL	POWERGRID	FBTL	Hexa Zebra+ Twin HTLS		Not Available	
M. PBTSL		-										
				D/C (some					1			
1	400kV	Bikaner_2 (PBTSL)-Khetri (PKTSL)	1	towers	275	PBTSL	PBTSL	PKTSL	Twin HTLS		Not Available	
				M/C)								
				D/C (some								
2	400kV	Bikaner_2 (PBTSL)-Khetri (PKTSL)	2	towers	275	PBTSL	PBTSL	PKTSL	Twin HTLS		Not Available	
				M/C)								
				D/C (some								
3	400kV	Bikaner_2 (PBTSL)-Khetri (PKTSL)	3	towers	275	PBTSL	PBTSL	PKTSL	Twin HTLS		Not Available	
	l	Billanci_E (1 515E) tilleti (1 tilsE)		M/C)	2,3	15152	'5'52	111102	1		1400 / Wallable	
			1	D/C (some					1			
4	400kV	Bikaner_2 (PBTSL)-Khetri (PKTSL)	4	towers	275	PBTSL	PBTSL	PKTSL	Twin HTLS		Not Available	
"	4006	bikaner_2 (FB13E)-Kneth (FK13E)	+		2/3	FBISE	FBISE	FRISE	I WIII III S		NOT Available	
5	400kV	Khetri (PKTSL)-Bhiwadi(PG)	1	M/C) D/C	126	PBTSL	PKTSL	POWERGRID	Twin HTLS		Not Available	1
6	400kV	Khetri (PKTSL)-Bhiwadi(PG)	2	D/C	126	PBTSL	PKTSL	POWERGRID	Twin HTLS		Not Available	
N. PRTL		Transport of the second										
1	400kV	Jaisalmer(RS)-Fatehgarh_III(PG)	1	D/C	50	PRTL	RAJASTHAN	PRTL	Twin HTLS		Not Available	
2	400kV	Jaisalmer(RS)-Fatehgarh_III(PG)	2	D/C	50	PRTL	RAJASTHAN	PRTL	Twin HTLS		Not Available	
3	400kV	Fatehgarh_III(PG)- Fatehgarh_II(PG)	1	D/C	44	PRTL	PRTL	POWERGRID	Twin HTLS		Not Available	
4	400kV	Fatehgarh_III(PG)- Fatehgarh_II(PG)	2	D/C	44	PRTL	PRTL	POWERGRID	Twin HTLS		Not Available	
O. NRSS-3	36		-	-		_	-	_	-			-
1	400kV	Babai(RS)-Bhiwani(PG)	1	D/C	111	NRSS-36	NRSS-36	POWERGRID	Twin Moose		Not Available	
2	400kV	Babai(RS)-Bhiwani(PG)	2	D/C	111	NRSS-36	NRSS-36	POWERGRID	Twin Moose		Not Available	
RF Con	nected at ISTS D	edicated Lines		•			•		•			
A. RENEV		In (20) 20 (2 )		I a:-			I		T =			
1	400kV	Bikaner(PG) - Bikaner (Renew)	1	s/c	5	RENEW	POWERGRID	RENEW	Twin Moose		Not Available	
B. Avaada												
1	400kV	Bikaner(PG)-Avaada	1	S/C	14	AEPL	POWERGRID	AEPL	Twin Moose		Not Available	
C. ARPOP	L											
C. ARPOP	400kV	Bikaner(PG)-Ayana	1	S/C	12	ARPOPL	PGCIL	Ayana	ACSR Twin Moose+AL		Not Available	
		Bikaner(PG)-Ayana	1	S/C	12	ARPOPL	PGCIL	Ayana	ACSR Twin Moose+AL 59		Not Available	
		Bikaner(PG)-Ayana	1	S/C	12	ARPOPL	PGCIL	Ayana			Not Available	
1		Bikaner(PG)-Ayana  Bikaner(PG)-Azure 43 PSS	1	s/c	12	ARPOPL Azure	PGCIL	Ayana Azure 43 PSS			Not Available  Not Available	
D. Azure	400kV 400kV	Bikaner(PG)-Azure 43 PSS	1	s/c		Azure	POWERGRID	Azure 43 PSS	59 Twin Moose		Not Available	
1 D. Azure	400kV				9				59			
D. Azure  1 2 E. RSRPL	400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS	1	S/C S/C	9	Azure Azure	POWERGRID Azure 43 PSS	Azure 43 PSS Azure 43 RSS	59 Twin Moose Twin Moose		Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1	400kV 400kV	Bikaner(PG)-Azure 43 PSS	1 1	s/c	9	Azure	POWERGRID	Azure 43 PSS	59 Twin Moose		Not Available	
D. Azure  1 2 E. RSRPL	400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi	1 1	S/C   S/C	9 3	Azure Azure RSRPL	POWERGRID Azure 43 PSS RENEW	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose		Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC	400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat	1 1 1	S/C   S/C   S/C   S/C   D/C   D/C	9 3 13	Azure Azure RSRPL NTPC	POWERGRID Azure 43 PSS RENEW POWERGRID	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose Quad Moose		Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2	400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi	1 1	S/C   S/C	9 3	Azure Azure RSRPL	POWERGRID Azure 43 PSS RENEW	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose		Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE	400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat	1 1 1	S/C   S/C   S/C   S/C   D/C   D/C	9 3 13	Azure Azure RSRPL NTPC	POWERGRID Azure 43 PSS RENEW POWERGRID	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose Quad Moose		Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2	400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat	1 1 1	S/C   S/C   S/C   S/C   D/C   D/C	9 3 13	Azure Azure RSRPL NTPC	POWERGRID Azure 43 PSS RENEW POWERGRID	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose Quad Moose		Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE	400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat	1 1 1	S/C   S/C   S/C   S/C   D/C   D/C	9 3 13	Azure Azure RSRPL NTPC	POWERGRID Azure 43 PSS RENEW POWERGRID	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose Quad Moose		Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE	400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat	1 1 1	S/C   S/C   S/C   S/C   D/C   D/C	9 3 13	Azure Azure RSRPL NTPC	POWERGRID Azure 43 PSS RENEW POWERGRID	Azure 43 PSS Azure 43 RSS RSRPL	Twin Moose Twin Moose Twin Moose Quad Moose	Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL	400kV 400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2		S/C   S/C   S/C   D/C   D/C	9 3 13 29 2	Azure Azure RSRPL NTPC NTPC	POWERGRID Azure 43 PSS  RENEW  POWERGRID  NTPC	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC	Twin Moose Twin Moose Twin Moose Quad Moose	· ·	Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 1 2 STATE 1 A. DTL	400kV 400kV 400kV 400kV 400kV 400kV LINES	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad	1 1 1 1 1 1 1 1 1	S/C   S/C   S/C   S/C   D/C   D/C   D/C   D/C   D/C   M/C	9 3 13 29 2	Azure Azure Azure RSRPL NTPC NTPC DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID  NTPC  DTL	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC POWERGRID	Twin Moose Twin Moose Twin Moose Quad Moose	tower	Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL	400kV 400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2		S/C   S/C   S/C   D/C   D/C	9 3 13 29 2	Azure Azure RSRPL NTPC NTPC	POWERGRID Azure 43 PSS  RENEW  POWERGRID  NTPC	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC	Twin Moose Twin Moose Twin Moose Quad Moose	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 2	400kV 400kV 400kV 400kV 400kV 400kV 400kV 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad	1 1 1 1 1 2	S/C   S/C   S/C   S/C   D/C   D/C   D/C   M/C   M/C   M/C	9 3 13 29 2 2	Azure Azure Azure RSRPL NTPC NTPC DTL DTL	POWERGRID AZUTE 43 PSS  RENEW  POWERGRID  NTPC  DTL  DTL	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC POWERGRID POWERGRID	Twin Moose Twin Moose Twin Moose Quad Moose Quad Moose	tower	Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 1 2	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad Bamnauli-Tughlakabad Bamnauli-Jughlakabad	1 1 1 1 1 1 1 1 2 2 1 1 1	S/C   S/C   S/C   S/C   D/C   D/C   D/C   D/C   D/C   D/C   D/C   M/C   D/C   D/C	9 3 13 29 2 2	Azure Azure Azure RSRPL NTPC NTPC DTL DTL DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID  NTPC  DTL  DTL  DTL	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC POWERGRID POWERGRID POWERGRID	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 2 3 4	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad Bamnauli-Tughlakabad Bamnoli-Jhatikara Bamnoli-Jhatikara	1 1 1 1 1 1 1 1 2 2 1 1 2 2	S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68	Azure Azure Azure RSRPL NTPC NTPC DTL DTL DTL DTL DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID  NTPC  DTL  DTL  DTL  DTL  DTL  DTL	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC POWERGRID POWERGRID POWERGRID POWERGRID POWERGRID	Twin Moose Twin Moose Twin Moose  Twin Moose  Quad Moose Quad Moose  Quad Moose Quad Moose Quad Moose	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 1 2 3 4 5	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 PSS Azure 43 PSS  Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Baman-Mundka	1 1 1 1 1 1 1 2 2 1 1 1 1 1 1 1 1 1 1 1	S/C   S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 12 12 11 18	Azure Azure Azure RSRPL NTPC NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  POWERGRID  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 1 2 3 4 5 6	400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Bawana-Mundka	1 1 1 1 1 1 1 2 2 1 1 1 2 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 2 68 68 68 12 12 12 18	Azure Azure Azure RSRPL NTPC NTPC DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  POWERGRID  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 1 5 NTPC 1 2 STATE 1 2 3 4 5 6 7	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Bawana-Mundka Jhatikara-Mundka	1 1 1 1 1 1 1 1 2 2 1 1 2 2 1 1 1 1 1 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 2 68 68 68 12 12 18 18 18	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL DTL DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE A. DTL 1 2 3 4 5 6	400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Bawana-Mundka	1 1 1 1 1 1 1 2 2 1 1 1 2 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 2 68 68 68 12 12 12 18	Azure Azure Azure RSRPL NTPC NTPC DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  POWERGRID  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator Polymer Insulator	
1 D. Azure 1 2 E. RSPL 1 F. NTPC 1 2 STATE 1 2 3 4 5 6 7 8 B.	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Bawana-Mundka Jhatikara-Mundka	1 1 1 1 1 1 1 1 2 2 1 1 2 2 1 1 1 1 1 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 2 68 68 68 12 12 18 18 18	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL DTL DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE 1 2 3 4 5 6 7 8 B. HVPNL	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Jhatikara-Mundka Jhatikara-Mundka	1 1 1 1 1 1 1 2 2 1 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 68 12 12 12 18 18 17	Azure Azure Azure RSRPL NTPC NTPC DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL DTL DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSPL 1 F. NTPC 1 2 STATE 1 2 3 4 5 6 7 8 B.	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Bawana-Mundka Jhatikara-Mundka	1 1 1 1 1 1 1 1 2 2 1 1 2 2 1 1 1 1 1 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 68 12 12 18 18 17 17	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL DTL DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL  DTL  HVPNL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE 1 2 3 4 5 6 7 8 B. HVPNL	400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Jhatikara-Mundka Jhatikara-Mundka	1 1 1 1 1 1 1 2 2 1 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 68 12 12 12 18 18 17	Azure Azure Azure RSRPL NTPC NTPC DTL	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL DTL DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL  DTL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 1 2 STATE 1 2 3 4 5 6 7 8 B. HUPNL	400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnauli-Jhatikara Bamoli-Jhatikara Bawana-Mundka Jhatikara-Mundka Jhatikara-Mundka Jhatikara-Mundka  LCLP Jhajjar - Dhanonda	1 1 1 1 1 1 1 1 2 2 1 1 1 2 2 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 68 12 12 18 18 17 17	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	Azure 43 PSS Azure 43 RSS  RSRPL  NTPC  NTPC  POWERGRID  POWERGRID  POWERGRID  DTL  DTL  DTL  DTL  HVPNL	Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad Moose Quad bersimis	tower Tower is quad circuit	Not Available Not Available Not Available Not Available Not Available Not Available Polymer Insulator	
1 D. Azure 1 2 E. RSRPL 1 1 F. NTPC 1 2 STATE   A. DTL 1 2 3 4 5 6 7 8 B. HVPNL 1 2	400kV 400kV 400kV 400kV 400kV 400kV LINES 400kV	Bikaner(PG)-Azure 43 PSS Azure 43 (RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad Bamnauli-Tughlakabad Bamnoli-Jhatikara Bamnoli-Jhatikara Bawana-Mundka Jhatikara-Mundka Jhatikara-Mundka Jhatikara-Mundka Jhatikara-Mundka CLP Jhajjar - Dhanonda CLP Jhajjar - Dhanonda	1 1 1 1 1 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 68 68 68 12 12 12 13 17 17	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC NTPC POWERGRID POWERGRID POWERGRID DTL DTL DTL DTL DTL HVPNL HVPNL	Twin Moose Twin Moose Twin Moose Twin Moose  Quad Moose Quad Moose Quad Moose Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis Quad bersimis Twin Moose Twin Moose	tower Tower is quad circuit	Not Available Polymer Insulator Conventional Conventional Already had Anti fog	
1 D. Azure 1 2 E. RSRPL 1 F. NTPC 1 2 STATE 1 2 3 4 5 6 7 8 B. HVPNL 1 1 2 3 3	400kV	Bikaner(PG)-Azure 43 PSS Azure43(RSS)-Azure 43 PSS Bikaner(RENEW) - Renew Surya Ravi  Bhadla II - Kolayat Kolayat - Kolayat_2  Bamnauli-Tughlakabad  Bamnauli-Tughlakabad  Bamnoli-Jhatikara Bamnoli-Jhatikara Bamna-Mundka Jhatikara-Mundka Jhatikara-Mundka Jhatikara-Mundka CLP Jhajjar - Dhanonda CLP Jhajjar - Dhanonda CLP Jhajjar - Kabulpur	1 1 1 1 1 1 1 2 2 1 1 2 2 1 1 2 2 1 1 1 2 2 1	S/C   S/C   S/C   S/C   S/C   S/C   S/C   D/C   D/C	9 3 13 29 2 2 2 12 12 18 18 17 17 17 20 20 35	Azure Azure Azure  RSRPL  NTPC  NTPC  DTL  DTL  DTL  DTL  DTL  DTL  DTL  DT	POWERGRID AZURE 43 PSS  RENEW  POWERGRID NTPC  DTL DTL DTL DTL DTL DTL DTL DTL CTL DTL CTL POWERGRID POWERGRID POWERGRID CLP Jhajjar CLP Jhajjar	Azure 43 PSS Azure 43 RSS RSRPL NTPC NTPC NTPC POWERGRID POWERGRID POWERGRID DTL DTL DTL DTL HVPNL HVPNL HVPNL	Twin Moose Twin Moose Twin Moose Twin Moose Quad Moose Quad Moose Quad bersimis Quad Moose Twin Moose Quad Moose	tower Tower is quad circuit	Not Available Polymer Insulator Conventional	

6	400kV	Deepalpur-Kabulpur	2 1	D/C	67	JKTPL	KT Jhajjar	HVPNL	Quad Moose	1	towers	
7	400kV	Dhanoda-Daultabad	1	D/C	73	HVPNL	HVPNL	HVPNL	Quad Moose		Already had Polymer	
8	400kV	Dhanoda-Daultabad	2	D/C	73	HVPNL	HVPNL	HVPNL	Quad Moose		Insulator	
9	400kV	Gurgaon-Daultabad	1	D/C	21	HVPNL	POWERGRID	HVPNL	Quad Moose			Six towers multi-circuit
10	400kV	Gurgaon-Daultabad	2	D/C	21	HVPNL	POWERGRID	HVPNL	Quad Moose			with Bamnauli-
11	400kV	Jhajjar-Daulatabad	1	D/C	64	HVPNL	APCPL	HVPNL	Twin Moose		Polymer Insulator	Partial (84%),
12	400kV	Jhajjar-Daulatabad	2	D/C	64	HVPNL	APCPL	HVPNL	Twin Moose		Polymer Insulator	Remaining pending
13	400kV	Khedar-Fatehabad	1	D/C	40	HVPNL	HPGCL	POWERGRID	Twin Moose		Conventional	Presently there is no planning of replacment of Convention disc Insulator with Polymer Insulators
14	400kV	Jind-Kirori	1	D/C	51	HVPNL	POWERGRID	HVPNL	Twin Moose		Polymer Insulator	
15	400kV	Jind-Kirori	2	D/C	51	HVPNL	POWERGRID	HVPNL	Twin Moose		Polymer Insulator	
16	400kV	Khedar-Kirori	1	D/C	6.2	HVPNL	HPGCL	HVPNL	Twin Moose		Conventional	Presently there is no
17	400kV	Khedar-Kirori	2	D/C	6	HVPNL	HPGCL	HVPNL	Twin Moose			planning of replacment
18	400kV	Khedar-Nuhiawali	1	D/C	114	HVPNL	HPGCL	HVPNL	Twin Moose		Conventional	Existing disc insulator
19	400kV	Nuhiawali-Fatehabad	1	D/C	78	HVPNL	HVPNL	POWERGRID	Twin Moose		Conventional	are of Porcelain
C. PDD (Ja	ammu & Kashmir)											
1	400kV	Baglihar(stage 1)-Kishenpur	1	D/C	68	JK PDD	JKSPDCL	POWERGRID	Twin Moose		Conventional	
2	400kV	Baglihar(stage 1)-Kishenpur	2	D/C	68	JK PDD	JKSPDCL	POWERGRID	Twin Moose		Not Available	
D. PSTCL						· · · · · · · · · · · · · · · · · · ·						
1	400kV	Behman Jassa- HMEL	1	D/C	17	PSTCL	PSTCL	PSTCL	Twin Moose		Not Available	
2	400kV	Behman Jassa- HMEL	2	D/C	17	PSTCL	PSTCL	PSTCL	Twin Moose		Not Available	
3	400kV	Behman Jassa- Moga	1	S/C	113	PSTCL	PSTCL	PSTCL	Twin Moose	After LILO of 400 KV TSPL to 400 KV Moga at 400 KV Behman Jassa Singh	Not Available	
4	400kV	Makhu-Amritsar	1	D/C	64	PSTCL	PSTCL	PSTCL	Twin Moose		Partial (10%)	
5	400kV	Makhu-Amritsar	2	D/C	64	PSTCL	PSTCL	PSTCL	Twin Moose		Partial (10%)	
6	400kV	Muktsar-Makhu	1	D/C	96	PSTCL	PSTCL	PSTCL	Twin Moose		Conventional	
7	400kV	Muktsar-Makhu	2	D/C	96	PSTCL	PSTCL	PSTCL	Twin Moose		Polymer	
8	400kV	Nakodar-Makhu	1	D/C	52	PSTCL	PSTCL	PSTCL	Twin Moose		Conventional	
9	400kV	Nakodar-Makhu	2	D/C	52	PSTCL	PSTCL	PSTCL	Twin Moose		Conventional	
10	400kV	Nakodar-Moga	1	s/c	78	PSTCL	PSPCL	POWERGRID	Twin Moose		Not Available	LILO of 400kV Talwandi sabo-Nakodar at Moga
11	400kV	Rajpura-Dhuri	1	D/C	86	PSTCL	PSTCL	PSTCL	Twin Moose		Conventional	Lilo of Rajpura th-Dhuri
12	400kV	Rajpura TPS- Rajpura	1	D/C	9	PSTCL	PSPCL	PSTCL	Twin Moose		Conventional	1 at 400kV Rajpura
13	400kV	Rajpura-Dhuri	2	D/C	86	PSTCL	PSTCL	PSTCL	Twin Moose		Conventional	Lilo of Rajpura th-Dhuri
14	400kV	Rajpura TPS- Rajpura	2	D/C	9	PSTCL	PSPCL	PSTCL	Twin Moose		Not Available	2 at 400kV Rajpura
15	400kV	Rajpura TPS-Nakodar	1	D/C	139	PSTCL	PSPCL	PSTCL	Twin Moose		Conventional	
16	400kV	Rajpura TPS-Nakodar	2	D/C	139	PSTCL	PSPCL	PSTCL	Twin Moose		Conventional	
17	400kV	Talwandi Saboo- Dhuri	1	D/C	175	PSTCL	PSPCL	PSTCL	Twin Moose		Partial (22%)	
18	400kV	Talwandi Saboo- Dhuri	2	D/C	175	PSTCL	PSPCL	PSTCL	Twin Moose		Partial (22%)	
19	400kV	Talwandi Saboo- Behman Jassa	1	D/C	20	PSTCL	PSPCL	PSTCL	Twin Moose	After LILO of 400 KV TSPL to 400 KV Moga at 400 KV Behman Jassa Singh	Polymer	
20	400kV	Talwandi Saboo- Nakodar	1	D/C	180	PSTCL	PSPCL	PSTCL	Twin Moose		Conventional	
21	400kV	Talwandi Saboo- Muktsar	1	D/C	100	PSTCL	PSPCL	PSTCL	Twin Moose		Polymer	
22	400kV	Talwandi Saboo- Muktsar	2	D/C	100	PSTCL	PSPCL	PSTCL	Twin Moose		Polymer	
E. PTCUL	*****	Let a training a training										
1	400kV	Alaknanda(GVK)-Srinagar(PTCUL)	1	D/C	14	PTCUL	GVKPIL	PTCUL	Twin Moose		Conventional	
2	400kV	Alaknanda(GVK)-Srinagar(PTCUL)	2	D/C	14	PTCUL	GVKPIL	PTCUL	Twin Moose		Conventional	
3	400kV	Muradabad-Kashipur	1	s/c	108	PTCUL	UPPTCL	PTCUL	Twin Moose	-	Conventional	LTI O - C 400114
4	400kV	Rishikesh-Nehtaur	1	D/C	124	PTCUL	PTCUL	UPPTCL	Twin Moose		Not Available	LILO of 400kV
5 6	400kV 400kV	Nehtaur-Kashipur Roorkee-Rishikesh	1	D/C S/C	80 50	PTCUL PTCUL	UPPTCL POWERGRID	PTCUL PTCUL	Twin Moose Twin Moose	LILO portion is of POWERGRID	Not Available Not Available	Rishikesh-Kashipur
7	400kV	Roorkee-Muzaffarnagar	1	S/C	71	PTCUL	POWERGRID	UPPTCL	Twin Moose		Not Available	
F. RRVPN				-, -								•
1	400kV	Ajmer-Bhilwara	1	D/C	160	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
2	400kV	Ajmer-Bhilwara	2	D/C	160	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
3	400kV	Akal-Barmer	1	s/c	124	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Conventional	
$\overline{}$		•					•			•		•

	400kV	Akal-Jodhpur	4	S/C	225	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Conventional	
5	400kV 400kV	Akal-Jodhpur Akal-Ramgarh	1	D/C	225 99	RRVPNL	RRVPNL	RRVPNL RRVPNL	Twin Moose Twin Moose	-	Conventional Not Available	
6	400kV	Akal-Ramgarh	2	D/C	99	RRVPNL	RRVPNL	RRVPNL	Twin Moose	Dunascod at Auto 4	Not Available	
7	400kV	Anta-Chhabra	1	s/c	90	RRVPNL	RRVPNL	RVUNL	Quad Moose	Bypassed at Anta to form Chhabra- Kota(PG)	Not Available	
8	400kV	Anta-Chhabra SC	1	D/C	89	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
9	400kV	Anta-Chhabra SC	2	D/C	89	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
10	400kV	Anta-Kalisindh	1	D/C	80	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
11	400kV	Anta-Kalisindh	2	D/C	80	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
12	400kV	Anta-Kawai	1	D/C	50	RRVPNL	RRVPNL	Kawai(Adani)	Quad Moose		Not Available	
13	400kV	Anta-Kawai	2	D/C	50	RRVPNL	RRVPNL	Kawai(Adani)	Quad Moose		Not Available	
14	400kV	Anta-Kota (PG)	1	s/c	91	RRVPNL	RRVPNL	POWERGRID	Twin Moose	Bypassed at Anta to form Chhabra- Kota(PG)	Not Available	
15	400kV	Barmer-Bhinmal	1	D/C	144	RRVPNL	RRVPNL	POWERGRID	Twin Moose		Not Available	
16	400kV	Barmer-Bhinmal	2	D/C	144	RRVPNL	RRVPNL	POWERGRID	Twin Moose		Not Available	
17	400kV	Barmer-Jaisalmer-II (Bhaesada)	1	D/C	117	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
18	400kV	Barmer-Jaisalmer-II (Bhaesada)	2	D/C	117	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
19	400kV	Barmer-Rajwest	1	D/C	15	RRVPNL	RRVPNL	RAJWEST	Twin Moose		Conventional	
20	400kV	Bhadla-Jodhpur	1	D/C	106	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
21	400kV	Bhilwara-Chhabra	1	S/C	303	RRVPNL	RRVPNL	RVUNL	Twin Moose		Conventional	
22	400kV	Bhilwara-Chittorgarh(RRVPNL)	1	D/C	49	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
23	400kV	Bhilwara-Chittorgarh(RRVPNL)	2	D/C	49	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
24	400kV	Bikaner-Bhadla	1	D/C	189	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
25	400kV	Bikaner-Bhadla	2	D/C	189	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
26	400kV	Bikaner-Merta	1	S/C	172	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
27	400kV	Bikaner-Sikar(PG)	1	D/C	171	RRVPNL	RRVPNL	POWERGRID	Twin Moose		Not Available	
28	400kV	Bikaner-Sikar(PG)	2	D/C	171	RRVPNL	RRVPNL	POWERGRID	Twin Moose		Not Available	
29	400kV	Chhabra - Kawai SCTPS	1	s/c	45	RRVPNL	RVUNL	APRL	Twin Moose		Conventional	
30	400kV	Chhabra-Chhabra SC	1	D/C	2	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
31	400kV	Chhabra-Chhabra SC	2	D/C	2	RRVPNL	RRVPNL	RVUNL	Quad Moose		Not Available	
32	400kV	Heerapura-Hindaun	1	S/C	192	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Conventional	
33	400kV	Hindaun-Chhabra	1	S/C	305	RRVPNL	RRVPNL	RVUNL	Twin Moose		Conventional	
34	400kV	Kakani (Jodhpur New)-Jodhpur	2	S/C	102	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
35	400kV	Kankani (Jodhpur New)-Akal	1	D/C	223	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
36	400kV	Kankani(Jodhpur New)-Jaisalmer-II(Bhainsra)	1	D/C	177	RRVPNL	RRVPNL	RRVPNL	Quad Moose	LILO of 400kV Kankani(Jodhpur New)- Akal ckt-2	Not Available	
37	400kV	Jaisalmer-II(Bhainsra)-Akal	1	D/C	61	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
38	400kV	Kankani (Jodhpur New)-Jodhpur	1	S/C	67	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
39	400kV	Kankani (Jodhpur New)-Merta	1	s/c	140	RRVPNL	RRVPNL	RRVPNL	Twin Moose	LILO of 400kV Jodhpur- Merta-1 at Kakani	Not Available	
40	400kV	Merta-Bhadla	1	D/C	175	RRVPNL	RRVPNL	RRVPNL	Twin Moose	LILO of 400kV Jodhpur- Merta-2 at Bhadla	Not Available	
41	400kV	Merta-Heerapura	1	S/C	175	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Conventional	
42	400kV	Merta-Ratangarh	1	S/C	173	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Conventional	
43	400kV	Phagi-Ajmer(RRVPNL)	1	D/C	109	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
44	400kV	Phagi-Ajmer(RRVPNL)	2	D/C	109	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
45	400kV	Phagi-Heerapura	1	D/C	52	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
46	400kV	Phagi-Heerapura	2	D/C	52	RRVPNL	RRVPNL	RRVPNL	Quad Moose		Not Available	
47	400kV	Rajwest - Kankani (Jodhpur New)	1	s/c	209	RRVPNL	RRVPNL	RRVPNL	Twin Moose	LILO of 400kV Jodhpur-Rajwest-I at Kakani	Not Available	
48	400kV	Rajwest-Jodhpur	1	D/C	209	RRVPNL	RWPL	RRVPNL	Twin Moose		Conventional	
49	400kV	Ramgarh-Bhadla	1	D/C	160	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
50	400kV	Ramgarh-Bhadla	2	D/C	160	RRVPNL	RRVPNL	RRVPNL	Twin Moose		Not Available	
51	400kV	Suratgarh-Bikaner	1	S/C	146	RRVPNL	RVUNL	RRVPNL	Twin Moose		Conventional	
52	400kV	Suratgarh-Ratangarh	1	S/C	144	RRVPNL	RVUNL	RRVPNL	Twin Moose		Conventional	
53	400kV	Suratgarh-Ratangarh	2	S/C	144	RRVPNL	RVUNL	RRVPNL	Twin Moose		Conventional	
54	400kV	Suratgarh-Suratgarh SC	1	S/C	2	RRVPNL	RVUNL	RVUNL	Quad Moose		Not Available	
55	400kV	Suratgarh SC-Bikaner	1	D/C	140	RRVPNL	RVUNL	RRVPNL	Twin Moose		Not Available	
56	400kV	Suratgarh SC-Bikaner	2	D/C	140	RRVPNL	RVUNL	RRVPNL	Twin Moose		Not Available	
G. UPPTC		•	•				1					•
				-	•		•				•	

	4001-14	Anna (Fatabland) Anna Carith		D/C	70	LIDDTCI	LIBBTOL	LIBBTOL	Turin Manage	1	Net Assileble	<u> </u>
1	400kV 400kV	Agra (Fatehbad)-Agra South	1	D/C	70	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	1110 - 5 400 114
2	400kV	Agra (UP)-Agra(Fatehbad)	1	S/C	104	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	LILO of 400 kV
												Agra(UP)- Muradnagar(N)
												at Fatehabad(UP)
3	400kV	Agra UP-Unnao	1	S/C	279	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Partial (25%)	
4	400kV	Agra(Fatehbad)-Mathura	1	S/C	142	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
5	400kV	Agra(Fatehbad)-Mathura	2	D/C	151	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	LILO of 400 kV
												Fatehabad(UP)-
												Muradnagar at Mathura
6	400kV	Alakhnanda-Vishnuprayag	1	D/C	109	UPPTCL	GVKPIL	JPVL	Twin Moose		Not Available	
7	400kV	Aligarh-Mainpuri	1	D/C	93	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
-	400kV					UPPTCL	UPPTCL					
8		Aligarh-Mainpuri	2	D/C	93			UPPTCL	Quad Moose		Not Available	
9	400kV	Aligarh-Muradnagar	1	S/C	177	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	*Series Compensated
												line (40%). It would be
												shifted
10	400kV	Aligarh-Sikandrabad	1	D/C	95	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
11	400kV	Aligarh-Harduaganj	1	S/C	40	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
12	400kV	AnparaB-AnparaC	1	D/C	0.05	UPPTCL	UPRVUNL	LANCO	Quad Moose		Conventional	
13	400kV	AnparaB-AnparaC	2	D/C	0.05	UPPTCL	UPRVUNL	LANCO	Quad Moose	<del>                                     </del>	Conventional	
14	400kV	AnparaB-AnparaD	1	D/C	5	UPPTCL	UPRVUNL	UPPTCL	Twin Moose	<del> </del>	Not Available	
										<del>                                     </del>		
15	400kV	AnparaB-AnparaD	2	D/C	5	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Not Available	
16	400kV	AnparaB-Mau	1	S/C	262	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Partial (13%)	
17	400kV	AnparaB-Obra B	1	s/c	40	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Partial	
18	400kV	AnparaB-Sarnath	1	D/C	158	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Partial	
19	400kV	AnparaB-Sarnath	2	D/C	158	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Conventional	
20	400kV	Ataur-Hapur	1	D/C	52	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
21	400kV	Ataur-Hapur	2	D/C	52	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
22	400kV	Ataur-Indirapuram	1	D/C	15	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
23	400kV	Ataur(UP)-Noida Sec 123(UP)	1	D/C	19	UPPTCL	UPPTCL	UPPTCL	Quad Moose (LILO	LILO of 400 KV ATAUR-	Not Available	
25	40000	Ataul (OF)-Nolda Sec 125(OF)	1	D/C	19	OFFICE	OFFICE	OFFICE				
$\vdash$		<u> </u>	-	- 1-					portion Twin HTLS)	INDIRAPURAM CKT-II at		
24	400kV	Indirapuram(UP)-Noida Sec 123(UP)	1	D/C	17	UPPTCL	UPPTCL	UPPTCL	Quad Moose (LILO	400 KV NOIDA SECTOR	Not Available	
									portion Twin HTLS)	123		
25	400kV	Azamgarh-Mau	1	S/C	48	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Partial (79%)	
26	400kV	Azamgarh-Tanda	1	D/C	153	UPPTCL	UPPTCL	NTPC	Twin Moose		Not Available	
27	400kV	Badaun-Sambhal	1	D/C	77	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
28	400kV	Badaun-Sambhal	2	D/C	77	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
29	400kV	Banda-Orai	1	D/C	108	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
30	400kV	Banda-Orai	2	D/C	108	UPPTCL	UPPTCL	UPPTCL	Quad Moose	<u> </u>	Not Available	
31	400kV	Banda-Rewa road	1	D/C	177	UPPTCL	UPPTCL	UPPTCL	Quad Moose	+	Not Available	
32	400kV	Banda-Rewa road	2	D/C	177	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
							I		İ		LILO of 400kV Bara-	
33	400kV	Bara-Meja	1	D/C	32	UPPTCL	UPPTCL	MUNPL	Quad Moose		Rewa road D/C at Meja	
34	400kV	Bara-Meja	2	D/C	32	UPPTCL	UPPTCL	MUNPL	Quad Moose			
												*Series Compensated
35	400kV	Bareilly UP-Unnao	1	D/C	271	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Partial (15%)	line (45%)
~		,	^		-''-	2	1				1 4. 44. (1570)	(1070)
$\vdash$		<del> </del>										*Series Compensated
,	400137	Parailly LIP Lippas	,	D/C	274	UPPTCL	UPPTCL	UPPTCL	Turin MA		Dortini (150/)	
36	400kV	Bareilly UP-Unnao	2	D/C	271	UPPICE	UPPICE	UPPICE	Twin Moose		Partial (15%)	line (45%)
$\vdash$			-							+	B I (====)	
37	400kV	Gorakhpur UP-Azamgarh	1	S/C	90	UPPTCL	UPPTCL	UPPTCL	Twin Moose	<b></b>	Partial (76%)	
38	400kV	Gr. Noida(765)-Sector 148	1	D/C	47	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
39	400kV	Gr. Noida(765)-Sector 148	2	D/C	47	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
40	400kV	Gr. Noida-Gr. Noida (765)	1	D/C	45	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
41	400kV	Gr. Noida-Gr. Noida (765)	2	D/C	45	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
42	400kV	Gr.Noida-Sikandrabad	1	D/C	17	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
43	400kV	Gr.Noida-Sikandrabad Gr.Noida-Sikandrabad	2	D/C	17	UPPTCL	UPPTCL	UPPTCL	Quad Moose	<b>†</b>	Not Available	
43	400kV		1				UPPTCL	UPPTCL		+	Not Available Not Available	
		Hapur-Dasna		D/C	14	UPPTCL			Quad Moose	<del> </del>		
45	400kV	Hapur-Dasna	2	D/C	14	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
46	400kV	Hapur-Moradabad	1	S/C	109	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
47	400kV	Hapur-Muradnagar	1	s/c	28	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
48	400kV	Harudaganj-Sikandarabad	1	S/C	115	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	

		ı	1							1		1710 - 6 4001 \( \text{10} \)
49	400kV	Mainpuri(UP)-Mainpuri(PG)	1	D/C	25	UPPTCL	UPPTCL	POWERGRID	Twin Moose		Not Available	LILO of 400kV Orai- Mainpuri(PG) at Mainpuri(UP)
50	400kV	Mainpuri(UP)-Mainpuri(PG)	2	D/C	26	UPPTCL	UPPTCL	POWERGRID	Twin Moose		Not Available	
51	400kV	Meja-Musauli	1	D/C	65	UPPTCL	MUNPL	UPPTCL	Quad Moose		Not Available	
52	400kV	Meja-Rewa road	1	D/C	45	UPPTCL	MUNPL	UPPTCL	Quad Moose		Not Available	
53	400kV	Muradnagar New- Mathura	1	D/C	246	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	LILO of 400 kV
				-, -	2.10	22						Fatehabad(UP)- Muradnagar at Mathura
54	400kV	Muradnagar-Ataur	2	D/C	18	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
55	400kV	Musauli-Rewa road	1	D/C	34	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
56	400kV	Muzaffarnagar-Alakhnanda	1	D/C	189	UPPTCL	UPPTCL	GVKPIL	Twin Moose		Not Available	
57	400kV	Muzaffarnagar-Ataur	1	D/C	121	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
58	400kV	Muzaffarnagar-Vishnuprayag	1	D/C	280	UPPTCL	UPPTCL	JPVL	Twin Moose		Conventional	
59	400kV	Noida Sec 148 - Noida Sec 123	1	D/C	20	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
60	400kV	Noida Sec 148 - Noida Sec 123	2	D/C	20	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
61	400kV	Noida Sec 148-Noida Sec 123	1	D/C	20	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
62	400kV	Noida Sec 148-Noida Sec 123	2	D/C	20	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
63	400kV	Obra-Rewa road	1	S/C	179	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
64	400kV	Obra-Sultanpur	1	S/C	230	UPPTCL	UPRVUNL	UPPTCL	Twin Moose		Conventional	
65	400kV	Obra B - Obra C	1	S/C	1	UPPTCL	UPRVUNL	UPRVUNL	Twin Moose		Not Available	
66	400kV	Orai-Mainpuri(UP)	1	D/C	176	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
67	400kV	Orai-Mainpuri(UP)	2	D/C	176	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
68	400kV	Orai-Paricha	1	D/C	111	UPPTCL	UPPTCL	UPRVUNL	Twin Moose		Not Available	
69	400kV	Orai-Paricha	2	D/C	111	UPPTCL	UPPTCL	UPRVUNL	Twin Moose		Not Available	
70	400kV	Panki-Aligarh	1	S/C	285	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Partial (24%)	
71	400kV	Rewa road -Panki	1	S/C	210	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	LILO of Bara-Panki at 400kV Rewa Road
72	400kV	Rosa-Badaun	1	D/C	85	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
73	400kV	Rosa-Badaun	2	D/C	85	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
74	400kV	Sarnath-Azamgarh	1	S/C	97	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
75	400kV	Lucknow_1(PG)-Mohanlalganj (PGYTL)	1	S/C	58	UPPTCL	POWERGRID	UPPTCL	Twin Moose	LILO of 400kV	Conventional	
76	400kV	Sultanpur(UP)-Mohanlalganj (PGYTL)	1	S/C	133	UPPTCL	UPPTCL	UPPTCL	Twin Moose	LUCKNOW(PG)-	Conventional	
77	400kV	Sultanpur-Tanda	1	D/C	103	UPPTCL	UPPTCL	NTPC	Twin Moose		Not Available	
78	400kV	Tanda-Basti	1	D/C	44	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
79	400kV	Tanda-Basti	2	D/C	44	UPPTCL	UPPTCL	UPPTCL	Quad Moose		Not Available	
80	400kV	Mohanlalganj (PGYTL)-Unnao(UP)	1	S/C	104	UPPTCL	UPPTCL	UPPTCL	Twin Moose	LILO of 400 KV	Partial (13%)	Status after LILO?
81	400kV	Lucknow(UP)-Mohanlalganj (PGYTL)	1	S/C	89	UPPTCL	UPPTCL	UPPTCL	Twin Moose	SAROJANI	Partial (13%)	
82	400kV	Unnao-Panki	1	S/C	49	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Partial (41%)	
83	400kV	Varanasi-Jaunpur	1	D/C	73	UPPTCL	POWERGRID	UPPTCL	Twin Moose	ļ	Not Available	
84	400kV	Varanasi-Jaunpur	2	D/C	73	UPPTCL	POWERGRID	UPPTCL	Twin Moose	l	Not Available	
85	400kV	Jaunpur (UP)-Obra_B(UP)	1	D/C	177	UPPTCL	UPPTCL	UPPTCL	Twin Moose	After LILO of 400 KV	Not Available	
86	400kV	Obra_C_TPS(UP)-Jaunpur (UP)	1	D/C	176	UPPTCL	UPPTCL	UPPTCL	Twin Moose	OBRA B- OBRA-C CKT-	Not Available	
87	400kV	Sambhal-Rampur	1	D/C	74	UPPTCL	UPPTCL	UPPTCL	Twin Moose	ļ	Not Available	
88	400kV	Sambhal-Rampur	2	D/C	74	UPPTCL	UPPTCL	UPPTCL	Twin Moose	ļ	Not Available	
89	400kV	Simbholi-Meerut_PMSTL	1	D/C	29	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
90	400kV	Simbholi-Meerut_PMSTL	2	D/C	29	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
91	400kV	Simbholi_PMSTL (UP)-Muradnagar_2(UP)	1	D/C	71	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
92	400kV	Simbholi_PMSTL (UP)-Muradnagar_2(UP)	2	D/C	71	UPPTCL	UPPTCL	UPPTCL	Twin Moose		Not Available	
93	400kV	Panki-Panki_TPS	1	S/C	1	UPPTCL	UPPTCL	UPPTCL	Twin Moose	-	Not Available	
H. PJFTL		T		- 1-						I		_
1	400kV	Firozabad-Jawaharpur	1	D/C	40	PJFTL	PJFTL	UPRVUNL	Quad Moose	Anti-theft charging	Not Available	
2	400kV	Firozabad-Jawaharpur	2	D/C	40	PJFTL	PJFTL	UPRVUNL	Quad Moose	from Firozabad(PJFTL)	Not Available	
3	400kV	Agra South-Firozabad PJFTL	1	D/C	79	PJFTL	UPPTCL	PJFTL	Twin Moose	LILO of 400kV Agra South-Agra Fatehabad ckt-2 at Firozabad PJFTL	Not Available	
4	400kV	Agra(Fatehabad)-Firozabad PJFT	1	D/C	79	PJFTL	UPPTCL	PJFTL	Twin Moose	13116	Not Available	
4	+ourv	Lagrati aterianan)-i irozanan ETET	1 1	<i>b</i> /C	13	FJEIL	UFFICE	FJÜL	I WIII IVIOUSE	1	NOT AVAILABLE	

I. GTL				I						1		
1	400kV	Kanpur(PG)-Ghatampur_TPS(UP)	1	D/C	49	GTL	POWERGRID	UPPTCL	Twin Moose	Antitheft charging from	Not Available	
2	400kV	Kanpur(PG)-Ghatampur_TPS(UP)	2	D/C	49	GTL	POWERGRID	UPPTCL	Twin Moose	Kanpur(PG) Upto DEAD	Not Available	
J. HPPTC		1 - k - ( - )		, ,		-				1		
1	400kV	Lahal-Chamba	1	D/C	35	HPPTCL	HPPTCL	POWERGRID	Twin Moose		Not Available	
2	400kV	Lahal-Chamba	2	D/C	35	HPPTCL	HPPTCL	POWERGRID	Twin Moose		Not Available	
K. NTPC.	jv	•	•		•	•	•		•	•		
1	400kV	Dadri-Loni (Harsh Vihar)	1	D/C	54	NTPC	NTPC	DTL	Twin Moose		Polymer	
2	400kV	Dadri-Loni (Harsh Vihar)	2	D/C	54	NTPC	NTPC	DTL	Twin Moose		Polymer	
L. MTSCL		•										
1	400kV	Ajmer-Deedwana	1	S/C	110	MTSCL	RRVPNL	MTSCL	Twin Moose		Not Available	
2	400kV	Bikaner-Deedwana	1	S/C	129	MTSCL	RRVPNL	MTSCL	Twin Moose		Conventional	
M. Arava	li Transmission Service	e Company Ltd (ATSCL)										-
1	400kV	Alwar-Hindaun	1	s/c	96	ATSCL	ATSL	RRVPNL	Twin Moose		Not Available	Partly owned by Aravali Transmission Services ILtd.
N. BBMB	3											
1	400kV	Dehar-Rajpura	1	S/C	129	ввмв	ввмв	PSTCL	Twin Morkulla+ LILO portion is of twin moose	Dehar-Bhiwani LILOed at Rajpura	Antifog	LILO of Dehar-Bhiwani at Rajpura
2	400kV	Bhiwani(BBMB)-Rajpura	1	S/C	213	ВВМВ	ВВМВ	PSTCL		Dehar-Bhiwani LILOed at Rajpura	Antifog	
3	400kV	Dehar-Panchkula	1	S/C	125	ввмв	ВВМВ	POWERGRID	Twin Morkulla+ LILO portion is of twin moose	POWERGRID owned LILO portion of 9.034Km	Antifog	LILO of Dehar-Panipat at Panchkula
4	400kV	Panchkula-Panipat	1	S/C	155	BBMB	POWERGRID	BBMB			Antifog	
OTHER	DEDICATED LIN	ES		-			-	-				•
A. THDC			1	I		I			T T	1		
1	400kV	Aligarh-Khurja	1	D/C	35	THDC	POWERGRID	THDC	Twin Moose		Not Available	
2	400kV	Aligarh-Khurja	2	D/C	35	THDC	POWERGRID	THDC	Twin Moose		Not Available	
		ion Line charged at 220kV									. roc / trainable	
STATE	LINES								•	•		
A. RRVPI												
1	400kV charged at 220kV	Dholpur-Hindaun	1	s/c	100	RRVPNL	RRVUNL	RRVPNL	Twin Moose		Conventional	
2	400kV charged at 220kV	Kota-KTPS	1	D/C	7	RRVPNL	POWERGRID	RRVUNL	Twin Moose		Conventional	
3	400kV charged at 220kV	Kota-KTPS	2	D/C	7	RRVPNL	POWERGRID	RRVUNL	Twin Moose		Conventional	

### National Load Despatch Centre Import Capability of Punjab for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	10900	500	10400	5497	4903		https://www.punjab sldc.org/ATC_TTC.as px
Limiting Constr	aints	N-1 contigency of 400 Loading close to N-1 c 220 kV underlying net	ontingency limits of 40	00/220kV Malerkotla a				

# National Load Despatch Centre Import Capability of Uttar Pradesh for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	17700	600	17100	10165	6935		https://www.upsldc.or g/documents/20182/0/ ttc_atc_24-11- 16/4c79978e-35f2-4aef- 8c0f-7f30d878dbde
<b>Limiting Con</b>	straints	N-1 contingency o	f 400/220kV Panki,	Allahabad(PG), Ag	gra(PG), Lucknow (	PG) ICTs		

# National Load Despatch Centre Import Capability of Haryana for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	10700	300	10400	5418	4982		https://hvpn.org. in/#/atcttc
<b>Limiting Con</b>	straints	N-1 contingency o	f 400/220kV ICT at	Deepalpur, Hisar,	Kabulpur and Panipat(	ВВМВ)		

### National Load Despatch Centre Import Capability of Rajasthan for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	7600	600	7000	5755	1245		https://sldc.rajast han.gov.in/rrvpnl /scheduling/dow nloads
<b>Limiting Con</b>	straints	N-1 contingency o	f 400/220kV Heera	pura, Jodhpur, Bik	aner, Ajmer, Merta, H	indaun and Ratang	garh ICTs	

# National Load Despatch Centre Import Capability of Delhi for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments				
1 January 2026 to 31 January 2026	00-24	7600	300	7300	4810	2490		https://www.del hisldc.org/resour ces/atcttcreport. pdf				
<b>Limiting Con</b>	straints	N-1 contingency o	I-1 contingency of 400/220kV HarshVihar and Bawana (bus-split) ICTs.									

#### National Load Despatch Centre Import Capability of Uttarakhand for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	1990	100	1890	1402	488		https://uksldc.in/ttc- atc
<b>Limiting Constr</b>	aints	N-1 contingency of 40	00/220kV Kashipur ICTs	s. High loading of 220k	V Roorkee-Roorkee an	d 220kV CBGanj-Pantr	nagar lines	

### National Load Despatch Centre Import Capability of HP for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments		
1 January 2026 to 31 January 2026	00-24	2386	100	2286	1181	1105		https://hpsldc.com/ mrm_category/ttc- atc-report/		
<b>Limiting Constr</b>	ainte	Overloading of 2*100MVA Giri transformers High loading of 220kV Nallagarh-Upernangal D/C								

### National Load Despatch Centre Import Capability of J&K for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to	00-09 & 14-24	3500	100	3400	1977	1423		
31 January 2026	09-14	2800	100	2700	1977	723		
Limiting Constr		N-1 contigency of 400 220 kV underlying net Low voltages in J&K c		agoora				

### National Load Despatch Centre Import Capability of Chandigarh for January 2026

Date	Time Period in IST (hrs)	Total Transfer Capability (TTC) (MW)	Reliability Margin (MW)	Available Transfer Capability (ATC) (MW)	Approved General Network Access (MW)	Margin Available for Temporary General Network Access(MW)	Changes in TTC w.r.t. Last Revision	Comments
1 January 2026 to 31 January 2026	00-24	480	20	460	342	118		
<b>Limiting Constr</b>		N-1 contigency of 220	kV Nallagarh-Kishenga	irh				



#### ग्रिंड कंट्रोलर ऑफ इंडिया लिमिटेड भारत सरकार का उद्यम GRID CONTROLLER OF INDIA LIMITED





(A Government of India Enterprise)

[formerly Power System Operation Corporation Limited (POSOCO)]

उत्तर क्षेत्रीय भार प्रेषण केन्द्र / Northern Regional Load Despatch Centre

कार्यालय : 18-ए, शहीद जीत सिंह सनसनवाल मार्ग, कटवारिया सराय, नई दिल्ली-110016 Office : 18-A, Shaheed Jeet Singh Sansanwal Marg, Katwaria Sarai, New Delhi-110016

CIN: U40105DL2009GOI188682, Website: www.nrldc.in, E-mail: nrldc@grid-india.in, Tel.: 011 26519406, 26523869, Fax: 01) 26852747

संदर्भ सं: 3.क्षे.भा.प्रे.कें/अनुपालन निगरानी/2025 सेवा में.

30<sup>th</sup> सितम्बर 2025

वितरण सूची के अनुसार

विषय: IEGC विनियम की धारा 56 के अनुसार वार्षिक स्व-मूल्यांकन (Self-Audit) रिपोर्ट प्रस्तुत करने हेतु

महोदय / महोदया,

भारतीय विद्युत ग्रिंड संहिता (IEGC) विनियम की धारा 56 के अनुसार, सभी संबंधित पक्षों — जैसे कि उपयोगकर्ता (Users), केंद्रीय पारेषण उपयोगकर्ता (CTU), राज्य पारेषण उपयोगकर्ता (STUs), एनएलडीसी, आरएलडीसी, आरपीसी, एसएलडीसी, पावर एक्सचेंज, क्यूसीए एवं एसएनए— को प्रत्येक वर्ष एक स्व-मूल्यांकन (Self-Audit) करना आवश्यक है, ताकि इन विनियमों के अनुपालन की समीक्षा की जा सके।

As per Clause 56 of the Indian Electricity Grid Code (IEGC) Regulations, all stakeholders involved in grid operations and market functions—including Users, CTU, STUs, NLDC, RLDCs, RPCs, SLDCs, Power Exchanges, QCAs, and SNAs—are required to conduct an annual self-audit to assess their compliance with the applicable provisions of the regulations.

ध्यान दिलाया जाता है कि वर्ष 2024-25 के लिए सेल्फ-ऑडिट रिपोर्ट 31 जुलाई 2025 तक अनिवार्य रूप से प्रस्तुत की जानी थी, जैसा कि भारतीय विद्युत ग्रिड संहिता (IEGC) विनियम की धारा 56(2)(a) में वर्णित है।

In accordance with IEGC Clause 56(2)(a), the self-audit report for the year 2024-25 was required to be submitted by 31st July 2025.

कृपया रिपोर्ट में निम्नलिखित बिंदुओं को अवश्य शामिल करें:

- किसी भी गैर-अनुपालन (Non-Compliance) की स्थिति में उसके कारण और प्रक्रिया की स्पष्ट जानकारी;
- 2. ऐसे गैर-अनुपालन से ह्ई क्षति या प्रभाव की सीमा;
- 3. सुधारात्मक कदम तथा समाधान हेतु प्रस्तावित समय-सीमा;
- 4. भविष्य में ऐसी प्नरावृत्ति को रोकने के लिए उठाए गए कदम।



The self-audit report should inter alia include the following details:

- Sufficient information on any instances of non-compliance, explaining how and why they occurred.
- 2. Extent of impact or damage caused by such non-compliance.
- 3. Corrective steps planned along with a timeline for rectification.
- 4. Measures taken to prevent recurrence in the future.

#### रिपोर्ट प्रस्तृत करने के निर्देश:

- उपयोगकर्ता, क्यूसीए, एसएनए संबंधित आरएलडीसी या एसएलडीसी को रिपोर्ट भेजें।
- पावर एक्सचेंज रिपोर्ट एनएलडीसी को भेजें।
- एनएलडीसी, आरएलडीसी, सीटीयू, आरपीसी रिपोर्ट सीईआरसी को भेजें।
- एसटीयु और एसएलडीसी रिपोर्ट संबंधित एसईआरसी को भेजें।

#### Submission Guidelines:

- Users, QCAs, SNAs are to submit their self-audit reports to the respective RLDC or SLDC, depending on their jurisdiction.
- · Power Exchanges shall submit their reports to the NLDC.
- · NLDC, RLDCs, CTU, and RPCs shall submit their reports to the CERC.
- STUs and SLDCs shall submit their reports to the respective SERC.

सभी घटकों से यह भी अपेक्षा की जाती है कि धारा 56(2)(f) के अनुसार, चिन्हित कमियों को एक निश्चित और उचित समय-सीमा के भीतर ठीक किया जाए।

All constituents are also reminded that as per Clause 56(2)(f), any deficiencies identified during the self-audit must be rectified in a time-bound and reasonable manner.

यह उल्लेख करना उचित है कि ओसीसी बैठकों, टीसीसी-एनआरपीसी बैठक तथा अन्य बैठकों में कई बार चर्चा होने के बावजूद, उत्तर क्षेत्र के विभिन्न घटकों से स्व-मूल्यांकन रिपोर्ट (Self-Audit Report) अब तक प्राप्त नहीं हुई है। सभी घटकों से पुनः अनुरोध किया जाता है कि वे शीघ्रता से अपनी-अपनी Self-Audit रिपोर्ट प्रस्तुत करें, क्योंकि इसकी नियत तिथि 31 जुलाई 2025 पहले ही समाप्त हो चुकी है।

It is pertinent to mention that despite multiple discussions in the OCC meetings, TCC-NRPC meeting and other meetings the Self-Audit reports from various constituents of the Northern Region are still awaited. All constituents are once again urged to expedite the submission of their respective Self-Audit reports at the earliest, as the deadline of 31st July 2025 has already passed.

Doz

संबंधित जानकारी एवं स्व-मूल्यांकन रिपोर्ट प्रस्तुत करने हेतु कृपया निम्न ईमेल आईडी का उपयोग करें:

nrldc-compliance@grid-india.in

nrldcso2@grid-india.in

For submission of information and self-audit reports, the following email IDs may be used:

nrldc-compliance@grid-india.in nrldcso2@grid-india.in

आपके शीघ्र सहयोग की अपेक्षा है।

Your prompt cooperation in this matter is earnestly requested.

धन्यवाद।

सोमारा लॉकरों मुख्य महाप्रबंधक उ.क्षे.भा.प्रे.कें., नई दिल्ली

# प्रतिलिपि सूचनार्थः

- 1. कार्यकारी निदेशक, राष्ट्रीय भार प्रेषण केंद्र, नई दिल्ली
- 2. सदस्य सचिव, उत्तर क्षेत्रीय विद्युत समिति, नई दिल्ली
- 3. निदेशक (प्रणाली संचालन), ग्रिड-इंडिया, नई दिल्ली



#### **Distribution List:**

- 1. Head (State Load Dispatch Centre), Delhi Transco Limited, SLDC Building (Behind Zakir Husain College), Tagore Hostel Lane, Minto Road, New Delhi 110002
- 2. Head (State Load Dispatch Centre), Haryana Vidyut Prasaran Nigam Limited, Shakti Bhawan, Sector-6, Panchkula 134109
- 3. Chief Engineer, Haryana Power Purchase Centre, Room No. 308, Shakti Bhawan, Sector-6, Panchkula 134109, Haryana
- 4. Chief Engineer, State Load Dispatch Centre (Nodal agency for Himachal Pradesh), Himachal Pradesh State Load Despatch Centre, Totu, Shimla 171011, Himachal Pradesh
- 5. Head (State Load Dispatch Centre), Punjab State Load Dispatch Centre, Punjab State Transmission Corporation Limited, 220 kV Sub Station Ablowal, Patiala, Punjab 147001
- 6. Chairman and Managing Director, Punjab State Power Corporation Limited, The Mall, Patiala, Punjab 147001
- 7. Head (State Load Dispatch Centre), Rajasthan Rajya Vidyut Prasaran Nigam Limited, Heerapura, Jaipur, Rajasthan 302024
- 8. Chairman, Rajasthan Urja Vikas Nigam Limited, Vidyut Bhawan, Janpath, Jyoti Nagar, Jaipur 302005, Rajasthan
- 9. Chief Engineer, Electricity Department, Union Territory of Chandigarh, Sector 9-D, Chandigarh 160019
- 10. Managing Director, Jammu and Kashmir Power Corporation Limited, State Load Dispatch Centre Building, First Floor, Gladni Grid Station, Nanval Bala, Jammu 180004
- 11. Chairman, Uttar Pradesh Power Corporation Limited, Shakti Bhawan, 14-Ashok Marg, Lucknow 226001
- 12. Managing Director, Uttarakhand Power Corporation Limited, Kanwli Road, Urja Bhawan, Dehradun 248001, Uttarakhand
- 13. Chief Electrical Engineer, North Central Railway, General Manager Office, Subedarganj, Uttar Madhya Railway, Allahabad, Uttar Pradesh 211011
- 14. Head of Project, Singrauli Super Thermal Power Station, NTPC, Post Office Shakti Nagar, District Sonebhadra, Uttar Pradesh 231222
- 15. Head of Project, Singrauli Solar Photovoltaic Power Project, NTPC, Post Office Shakti Nagar, District Sonebhadra, Uttar Pradesh 231222
- 16. Head of Project, Singrauli Small Hydro Power Project, NTPC, Post Office Shakti Nagar, District Sonebhadra, Uttar Pradesh 231222
- 17. Head of Project, Rihand Super Thermal Power Station-I, NTPC, Post Office Rihand Nagar, District Sonebhadra, Uttar Pradesh 231223
- 18. General Manager, Rihand Super Thermal Power Station-II, NTPC, Post Office Rihand Nagar, District Sonebhadra, Uttar Pradesh 231223

- 19. Head of Project, Rihand Super Thermal Power Station-III, NTPC, Post Office Rihand Nagar, District Sonebhadra, Uttar Pradesh 231223
- 20. Head of Project, Dadri, National Capital Power Project, NTPC-Dadri, Vidyut Nagar, District Gautam Budh Nagar, Uttar Pradesh 201008
- 21. Head of Project, Dadri Stage II, National Capital Power Project, NTPC-Dadri, Vidyut Nagar, District Gautam Budh Nagar, Uttar Pradesh 201008
- 22. Head of Project, Dadri Gas Power Project, NTPC-Dadri, Vidyut Nagar, District Gautam Budh Nagar, Uttar Pradesh 201008
- 23. Head of Project, Dadri Solar Photovoltaic Power Project, NTPC-Dadri, Vidyut Nagar, District Gautam Budh Nagar, Uttar Pradesh 201008
- 24. Head of Project, Firoz Gandhi Unchahar Thermal Power Project-I, NTPC, Post Office Unchahar, District Raebareilly, Uttar Pradesh 229406
- 25. Head of Project, Firoz Gandhi Unchahar Thermal Power Project-II, NTPC, Post Office Unchahar, District Raebareilly, Uttar Pradesh 229406
- 26. Head of Project, Firoz Gandhi Unchahar Thermal Power Project-III, NTPC, Post Office Unchahar, District Raebareilly, Uttar Pradesh 229406
- 27. Head of Project, Firoz Gandhi Unchahar Thermal Power Project-IV, NTPC, Post Office Unchahar, District Raebareilly, Uttar Pradesh 229406
- 28. Head of Project, Firoz Gandhi Unchahar Solar Photovoltaic Power Project, NTPC, Post Office Unchahar, District Raebareilly, Uttar Pradesh 229406
- 29. Head of Project, Auraiya Gas Power Project (Gas Fired, Re-gasified Liquefied Natural Gas Fired, Liquid Fired), NTPC, Post Office Dibiyapur, District Auraiya, Uttar Pradesh 206244
- 30. Head of Project, Auraiya Solar Power Plant, NTPC Limited, Post Office Dibiyapur, District Auraiya, Uttar Pradesh 206244
- 31. Head of Project, Anta Gas Power Project (Gas Fired, Re-gasified Liquefied Natural Gas Fired, Liquid Fired), NTPC, Post Office Anta, District Baran, Rajasthan 325209
- 32. Head of Project, Koldam Hydroelectric Power Project, NTPC, Post Barmana, District Bilaspur, Himachal Pradesh 174013
- 33. Head of Project, NTPC Limited, Tanda Stage-II, Post Office Vidyut Nagar, District Ambedkar Nagar, Uttar Pradesh 224238
- 34. General Manager, Nidan Solar Power Plant, NTPC Limited, Fatehgarh Solar Project, Village Nidan, Tehsil Pokharan, District Jaisalmer 345021, Rajasthan
- 35. Deputy General Manager, Devikot Solar Power Plant, NTPC Green Energy Limited, Plot No. 929, Barmer-Jaisalmer Highway, Devikot, Fatehgarh, District Jaisalmer, Rajasthan 345027
- 36. General Manager (Head of Project), Nokhra Solar Plant, NTPC Green Energy Limited, D-903, Tirupati Apartment, Near Kothari Hospital, Gajner Road, District Bikaner, Rajasthan 334001
- 37. General Manager, Kolayat Solar Plant, NTPC Green Energy Limited, Nokhra Solar Plant, NTPC Limited, Pethado Ki Dhani, Tehsil Kolayat, District Bikaner, Rajasthan 334303

- 38. Station Director, Narora Atomic Power Station, Nuclear Power Corporation of India Limited, Narora, District Bulandshahar, Uttar Pradesh 203389
- 39. Station Director, Rajasthan Atomic Power Station-B, Nuclear Power Corporation of India Limited, Rawatbhata, Post Office Anu Shakti Vihar, District Kota, Rajasthan 323303
- 40. Station Director, Rajasthan Atomic Power Station-C (Units 5 and 6), Nuclear Power Corporation of India Limited, Rawatbhata, Post Office Anushakti Vihar, District Kota, Rajasthan 323303
- 41. Station Director, Rajasthan Atomic Power Project Units 7 and 8, Nuclear Power Corporation of India Limited, Rawatbhata, Post Office Anushakti Vihar, District Kota, Rajasthan 323303
- 42. Head of Power Station, Bairasiul Hydroelectric Project, National Hydroelectric Power Corporation Limited, Surangini, District Chamba, Himachal Pradesh 176317
- 43. Head of Power Station, Salal Hydroelectric Project, National Hydroelectric Power Corporation Limited, Jyotipuram, District Udhampur, Jammu and Kashmir 182312
- 44. Head of Power Station, Tanakpur Hydroelectric Project, National Hydroelectric Power Corporation Limited, Banbassa, District Champawat, Uttarakhand 262310
- 45. Head of Power Station, Chamera-I Hydroelectric Project, National Hydroelectric Power Corporation Limited, Khairi, District Chamba, Himachal Pradesh 176310
- 46. Head of Power Station, Uri Hydroelectric Project, National Hydroelectric Power Corporation Limited, Mohra, District Baramulla, Jammu and Kashmir 193122
- 47. Head of Power Station, Chamera-II Hydroelectric Project, National Hydroelectric Power Corporation Limited, Karian, District Chamba, Himachal Pradesh 176310
- 48. Head of Power Station, Chamera-III Hydroelectric Project, National Hydroelectric Power Corporation Limited, Dharwala, District Chamba, Himachal Pradesh 176311
- 49. Head of Power Station, Dhauliganga Hydroelectric Project, National Hydroelectric Power Corporation Limited, Tapovan, Dharchula, District Pithoragarh, Uttarakhand 262545
- 50. Head of Power Station, Dulhasti Hydroelectric Project, National Hydroelectric Power Corporation Limited, Chenab Nagar, District Kishtwar, Jammu and Kashmir 182206
- 51. Head of Power Station, Uri-II Hydroelectric Project, National Hydroelectric Power Corporation Limited, Nowpura, District Baramulla, Jammu and Kashmir 193123
- 52. Head of Power Station, Parbati Hydroelectric Project Stage-III, National Hydroelectric Power Corporation Limited, Behali, Post Office Larji, District Kullu, Himachal Pradesh 175122
- 53. Head of Power Station, Sewa-II Power Station, National Hydroelectric Power Corporation Limited, Mashke, Post Bag No. 2, Post Office Khari, District Kathua, Jammu and Kashmir 176325
- 54. Head of Power Station, Kishanganga Hydroelectric Project, National Hydroelectric Power Corporation Limited, Office-cum-Residential Colony, Kralpora, District Bandipora, Jammu and Kashmir 193502

- 55. Head of Power Station, Parbati-II Hydroelectric Project, National Hydroelectric Power Corporation Limited, Electrical and Mechanical Complex, Sainj, District Kullu, Himachal Pradesh 175134
- 56. Head of Project, Nathpa Jhakri Hydroelectric Power Project, Satluj Jal Vidyut Nigam Limited, Post Office Jhakri, District Shimla, Himachal Pradesh 172201
- 57. Head of Project, Rampur Hydroelectric Power Project, Satluj Jal Vidyut Nigam Limited, Bayal, Post Office Koyal, Nirmand, District Kullu, Himachal Pradesh 172203
- 58. Head of Power Station, Tehri Hydroelectric Power Project, Tehri Hydro Development Corporation Limited, Bhagirath Puram, Tehri, Uttarakhand 249001
- 59. Head of Power Station, Koteshwar Hydroelectric Power Project, Tehri Hydro Development Corporation Limited, Koteshwerpuram, Post Office Pokhari, District Tehri Garhwal, Uttarakhand 249146
- 60. Project In-charge, Allain Duhangan Hydroelectric Power Limited, Village Prini, Post Office Jagat Sukh, Tehsil Manali, District Kullu, Himachal Pradesh 175143
- 61. Chief Executive Officer, Indira Gandhi Super Thermal Power Project, Aravali Power Company Private Limited, Post Office Jharli, Tehsil Matanhail, District Jhajjar, Haryana 124125
- 62. Project Head, Karcham Wangtoo Hydroelectric Power Project, JSW Hydro Energy Limited, Sholtu Colony, Post Office Tapti, District Kinnaur, Himachal Pradesh 172104
- 63. Company Secretary, Shree Cement Thermal Power Project, Bangurnagar, Beawar, District Ajmer, Rajasthan 305901
- 64. Company Secretary, Greenko Budhil Hydroelectric Power Station Limited, Greenko Hub, Number 13, Hitech City, Madhapur, Hyderabad, Telangana 500081
- 65. Project Head, Himachal Sorang Power Limited, D-7, Lane-I, Sector-I, New Shimla, District Shimla, Himachal Pradesh 171009
- 66. Head of Project, Sainj Hydroelectric Power Project, Himachal Pradesh Power Corporation Limited, Sarabai, District Kullu, Himachal Pradesh 175125
- 67. Head of Operation and Maintenance, Singoli-Bhatwari Hydroelectric Power Project, Renew Jal Urja Limited, Village Bedubagar, Post Office Augustmuni, District Rudraprayag, Uttarakhand 246421
- 68. Director (Power Regulation), Bhakra Power House, Bhakra Beas Management Board, State Load Dispatch Centre Complex, 66 kV Substation, Industrial Area Phase-I, Madhya Marg, Chandigarh 160002
- 69. Director (Power Regulation), Dehar Hydroelectric Power Project, Bhakra Beas Management Board, State Load Dispatch Centre Complex, 66 kV Substation, Industrial Area Phase-I, Madhya Marg, Chandigarh 160002
- 70. Director (Power Regulation), Pong Power House Circle, Bhakra Beas Management Board, State Load Dispatch Centre Complex, 66 kV Substation, Industrial Area Phase-I, Madhya Marg, Chandigarh 160002

- 71. Executive Director, Power Grid Corporation of India Limited, Northern Region Transmission System-I, B-9, Qutab Institutional Area, New Delhi 110016
- 72. Director, Operations, Powerlinks Transmission Limited, 10th Floor, DLF Tower-A, District Centre, Jasola, New Delhi 110044
- 73. Chief Financial Officer, Powergrid Himachal Transmission Limited, B-9, Qutab Institutional Area, New Delhi 110016
- 74. Director, Business Development, Adani Transmission India Limited, Shantigram, Near Vaishno Devi Circle, S.G. Highway, Khodiyar, Ahmedabad, Gujarat 382421
- 75. Managing Director, Parbati Koldam Transmission Company Limited, 5th Floor 1A, JMD Galleria, Sector-48, Sohna Road, Gurugram, Haryana 122018
- 76. Chief Executive Officer, Aravali Power Company Private Limited (Transmission Licensee), Post Office Jharli, District Jhajjar, Haryana 124141
- 77. Vice President (Regulatory and Contracts), Northern Region System Strengthening XXIX Transmission Limited, Unit No. 101, First Floor, Windsor, Village Kole Kalyan, Off CST Road, Vidyanagari Marg, Santacruz (East), Mumbai, Maharashtra 400098
- 78. Vice President (Regulatory and Contracts), Rajasthan Atomic Power Project Transmission Company Limited, Unit No. 101, First Floor, Windsor, Village Kole Kalyan, Off CST Road, Vidyanagari Marg, Santacruz (East), Mumbai, Maharashtra 400098
- 79. Vice President (Regulatory and Contracts), Patran Transmission Company Limited, Unit No. 101, First Floor, Windsor, Village Kole Kalyan, Off CST Road, Vidyanagari Marg, Santacruz (East), Mumbai, Maharashtra 400098
- 80. Vice President (Regulatory and Contracts), Gurugram Palwal Transmission Limited, Unit No. 101, First Floor, Windsor, Village Kole Kalyan, Off CST Road, Vidyanagari Marg, Santacruz (East), Mumbai, Maharashtra 400098
- 81. Associate Director Commercial and Regulatory, Northern Region System Strengthening XXXI (B) Transmission Limited, 504 and 505, 5th Floor, Windsor, Off CST Road, Kalina, Santacruz (East), Mumbai, Maharashtra 400098
- 82. Assistant General Manager, Northern Region System Strengthening XXXVI Transmission Limited, Tata Power Company Limited, Shatabdi Bhawan, B-12 and 13, Sector-4, Noida, Uttar Pradesh 201301
- 83. Chief Executive Officer, Powergrid Unchahar Transmission Limited, 765/400/220 kV Substation, Village Chauferava, Post and District Fatehpur, Uttar Pradesh 212601
- 84. Chief Executive Officer, Powergrid Kala Amb Transmission Limited, 400/220 kV Gas Insulated Substation, Village Meerpur Kotla, Post Office Trilokpur, Tehsil Nahan, District Sirmour, Himachal Pradesh 173030
- 85. Director, Fatehgarh Bhadla Transmission Limited, 3rd Floor, South Wing, Adani Corporate House, Shantigram, S.G. Highway, Khodiyar, Ahmedabad, Gujarat 382421
- 86. Director, Bikaner-Khetri Transmission Limited, 3rd Floor, South Wing, Adani Corporate House, Shantigram, S.G. Highway, Khodiyar, Ahmedabad, Gujarat 382421

- 87. Project In-Charge, Powergrid Ajmer Phagi Transmission Limited, Powergrid, B-9, Qutab Institutional Area, New Delhi 110016
- 88. Chief Engineer (Communication and Relay), Power Transmission Corporation of Uttarakhand Limited, Vidyut Bhawan, Near ISBT Crossing, Saharanpur Road, Majra, Dehradun, Uttarakhand 248002
- 89. Project In-Charge, Powergrid Fatehgarh Transmission Limited, Village Sanwata, Devikot Sankra Road, 8 Kilometer Milestone, District Jaisalmer, Rajasthan 345027
- 90. Project In-Charge, Powergrid Khetri Transmission System Limited, Village Jasrapur, Tehsil Khetri, District Jhunjhunu, Rajasthan 333514
- 91. Chief Executive Officer, Powergrid Varanasi Transmission System Limited, C-27/210, Kailgad House, Jagatganj, District Varanasi, Uttar Pradesh 221002
- 92. Project In-Charge, Powergrid Bikaner Transmission System Limited, 765/400 kV Substation, Village Jalalsar, Post Jamsar, District Bikaner, Rajasthan 334601
- 93. Chief Engineer (Communication and Relay), Power Transmission Corporation of Uttarakhand Limited, Vidyut Bhawan, Near ISBT Crossing, Saharanpur Road, Majra, Dehradun, Uttarakhand 248002

Y(d)(PG)

N (PG)

120

80

210

Y(d)(PG)

N (PG)

#### **Grid Event summary for November 2025** Category of Grid Loss of generation / loss of load Outage **Compliance of Protection Protocol/Standard** during the Grid Disturbance Incident/ Disturbance (As reported) Affected Area Owner/ Agency (Tripped/Manually opened) Flash Report DR/EL **Detail Tripping Repor** (GI-I to GD-V) Loss(MW) ubmission (Y/N) Submission (Y/N) (Y/N) 1)220 KV RAPS\_B(NP)- Kota Sakatpura(RS) (RS) Ckt 2)220kV Kota Sakatpura-KTPS ckt-3 i)220/132kV Kota Sakatpura(RS) has four buses with double main bus scheme at 220kV level. 220kV Bus-A&B are with sectionaliser and Bus-C & D are parallel bus. 3)220kV Kota Sakatpura-KTPS ckt-4 ii)During antecedent condition, 220/132kV 160 MVA Transformer-1 and 100 MVA Transformer-3&4 and 220kV feeders to RAPS-B, KTPS-3&4 were connected at 220kV Bus-C. Other elements were on another buses. 4)220/132kV 160 MVA Transformer-1 at Kota Sakatpura(RS) iii)As reported, at 01:11 hrs, Y-ph CT at 220kV side of 220/132kV 100 MVA Transformer-4 burst leading to bus fault on 220kV Bus-C. 5)220/132kV 100 MVA Transformer-3 at Kota Sakatpura(RS) iv)On this fault, bus bar protection of Bus-C operated resulting into tripping of all the elements connected to 220kV Bus-C along with the bus coupler breaker. 6)220/132kV 100 MVA Transformer-4 at Kota Sakatpura(RS) RVPNL, RVUNL GI-1 5-Nov-25 v)As per DR of bus bar relay, Y-N fault converted into R-Y fault with delayed clearance ~240 msec is observed. 480 178 320 Y(d)(RS) Y(RS) N(RS) 7)220 KV RAPS\_A(NP)-Kota Sakatpura(RS) (RS) Ckt-2 vi)As per PMU at Kota(PG), Y-N fault converted into R-Y fault with delayed clearance ~320 msec is observed 8)220 KV Anta-Kota Sakatpura(RS) (RS) Ckt vii)At the same time, 220kV Kota Sakatpura-RAPS\_A line-2 also tripped from Kota Sakatpura end on Z-4 distance protection operation. Further, 220kV kota Saktpura-Anta line, 220kV Kota Sakatpura-KTPS line-2 along with 9)220kV Kota Sakatpura-KTPS ckt-2 210 MW unit-3,4&5 at KTPS also tripped. Reason of multiple elements tripping at KTPS yet to be received. 10)210 MW Unit-3 at KTPS(RS) viii)As per SCADA change in demand of approx. 178 MW in Rajasthan control area and loss in generation of ~480 MW at KTPS is observed 11)210 MW Unit-4 at KTPS(RS) 12)210 MW Unit-5 at KTPS(RS) i)Generation of 220kV Renew Surya Jyoti Pvt Ltd. (RSJPL) (IP) station evacuates through 220 KV RSJPL-Fatehgarh\_III line. ii)During antecedent condition, 220kV RSJPL(IP) station was generating approx. 60 MW (as per PMU). GD-1 PGCIL, RSJPL 7-Nov-25 13:40 1)220kV Fatehgarh\_III-RSJPL line Raiasthan iii) As reported, at 13:40 hrs, 220kV Fatehgarh III-RSJPL line tripped on earth fault. 60 iv)As per PMU at Fatehgarh\_III(PG), no fault and fluctuation in voltage was observed in the system v)As per PMU MW data of RSJPL, solar generation loss of ~60 MW observed at RSJPL Restation. As per SCADA, no significant change in NR solar generation loss is observed. i)220/132/33kV Jammu/Gladni(J&K) S/s have double main bus arrangement at 220kV side. ii)During antecedent condition, 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-1 & 2 were carrying 73 MW and 64 MW respectively (as per SCADA). iii)As reported, at 16:24 hrs, 132 KV CT of B-ph Bus coupler bay blasted. During the same time, 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-1 & 2 tripped from Salal end (exact nature and location of fault yet to be shared). 1) 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-1 NHPC, PDD JK, Jammu and Y(d)(NHPC) Y(d)(NHPC) Y(d)(NHPC) 10-Nov-25 iv)As per DR at Salal(NH) end, B-N fault converted to R-B-N fault again converted to R-Y-B fault occurred. Fault current was Ir=~2.105kA, Iy=~2.148kA, Ib=~2.036kA from Salal end for 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-180 1040 GI-1 2) 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-2 **PGCIL** N(J&K) 1 and Ir=~1.852kA, Iy=~1.951kA, Ib=~1.877kA from Salal end for 220 KV Salal(NH)-Jammu(PDD) (PG) Ckt-2. Fault sensed in zone-3 at Salal end. Line tripped from Salal end after zone-3 time delay. v)As per PMU at Kishenpur(PG), R-B phase to phase fault converted to 3-phase fault was observed with delayed fault clearing time of 1040ms. vi)As per SCADA, change in demand of approx. 180 MW is observed in J&K control area. 1) 220 KV Mandola(PG)-Gopalpur(DTL) (DTL) Ckt-1 i)220/66/33kV Gopalpur(DTL) has double main Bus arrangement at 220kV side. 220kV Gopalpur- SOWazirabad D/C was in open condition from Gopalpur end. 2) 220 KV Mandola(PG)-Gopalpur(DTL) (DTL) Ckt-2 ii)During antecedent condition, 220kV Bus-2 at Gopalpur(DTL) was taken into outage due to some protection related work on 220kV Gopalpur-Timarpur Ckt. 3) 220 KV Gopalpur-Sabzi Mandi (DTL) Ckt-1 iii)As reported, at 16:35 hrs, bus bar protection operated at 220kV Bus-1 at Gopalpur(DTL) during carrying out protection work on 220kV Gopalpur-Timarpur Ckt (exact reason yet to be shared). GD-1 4) 220/33kV 100 MVA ICT-1 at Gopalpur(DTL) PGCIL, DTL 14-Nov-25 iv)Due to bus bar protection operation, all the 220kV elements connected to 220kV Bus-1 at Gopalpur(DTL) tripped and complete blackout occurred at 220/66/33kV Gopalpur(DTL) S/s. 130 Y(d)(DTL, PG) Y(d)(DTL) Y(DTL)(Partial) v)At 16:47 hrs, 220kV Gopalpur-SOWazirabad Ckt-2 was taken into service to charge 220kV Gopalpur(DTL) S/s. 5) 220/66kV 100 MVA ICT-2 at Gopalpur(DTL) 6) 220/33kV 100 MVA ICT-3 at Gopalpur(DTL) vi)As per PMU at Mandola(PG), no fault was observed in the system. vii)As per SCADA, change in demand of approx. 130 MW in Delhi control area is observed. 7) 220/66kV 160 MVA ICT-4 at Gopalpur(DTL) i)400/220kV Kishenpur(PG) S/s has one and half breaker scheme at 400kV level and double main and transfer bus scheme at 220kV level. ii)During antecedent condition, 400 KV Kishenpur-Moga (PG) Ckt-1 &2 were carrying 771 MW and 744 MW respectively (as per SCADA). iii)As reported, at 11:51 hrs, 400 KV Kishenpur-Moga (PG) Ckt-2 tripped on permanent Y-N phase to earth fault due to Y-phase jumper broken near Kishenpur(PG) S/s. As per DR, fault current was 13.41 kA and fault distance was 3.6 km from Kishenpur(PG) end; fault (with unsuccessful A/R) sensed in zone-1 and Main-II relay operated at Kishenpur(PG) end. iv)On the same fault, 400 KV Kishenpur-Moga (PG) Ckt-1 also tripped from Kishenpur(PG) end only. As per DR, fault current was 2.07 kA from Kishenpur(PG) end; fault sensed in zone-4 and Main-II relay operated at 1) 400 KV Kishenpur-Moga (PG) Ckt-1 Jammu and GI-2 **PGCIL** 21-Nov-25 11:51 130 Y(d)(PG) Y(d)(PG) Y(d)(Partial)(PG) Kishenpur(PG) end. 2) 400 KV Kishenpur-Moga (PG) Ckt-2 v)During investigation, it was observed that after Z4 pickup, D60 (Main-II) relay issued 3ph tripping due to "TRIPBUS-1 optd". On examining setting parameters, it was observed that input setting parameters to Trip Bus 1 function had been assigned for "Z2,Z3 and Z4 pickup" whereas as per standard template inputs to Trip Bus function should be assigned for "Z2,Z3 and Z4 operated". vi)As corrective action taken, setting in D60 relay was corrected and implemented as per standard template. vii)As per PMU at Kishenpur(PG), Y-N phase to earth fault with unsuccessful A/R was observed with fault clearing time of 80ms. viii)As per SCADA, change in demand of approx. 130 MW is observed in J&K control area. i)220/33kV Chowadhi(JK) S/s has double main and transfer bus scheme at 220kV side and two 220kV lines are connected: 220 KV Samba(PG)-Chowadhi (JK) (PDD JK) (PDD JK) Ckt and 220 KV Chowadhi (JK)-Gladni(PDD) (PDD JK)

Samba(PG), but not received at Chowadhi(JK) (Carrier communication issue observed).

vi)As per SCADA, change in demand of approx. 80 MW is observed in J&K control area

i)765/400/220kV Agra(PG) has double main & transfer bus scheme at 220kV level.

v)As per PMU at Agra(PG), B-N phase to earth fault is observed with fault clearing time of 80 ms.

Agra(PG) were carrying approx. 175 MW & 195 MW respectively.

v)As per PMU at Kishenpur(PG), R-N phase to earth fault with unsuccessful A/R was observed with fault clearing time of 120ms.

iv)Due to bus bar protection operation, all 220kV elements connected at Agra(PG) tripped and 220kV Bus-1 at Agra(PG) became dead.

vi)As per SCADA change in demand of approx. 70 MW in UP control area and approx. 140 MW in Rajasthan control area were observed

19:44

were same (500 ms).

22-Nov-25

29-Nov-25

PDD JK, PGCIL

PGCIL, UPPTCL,

**RVPNL** 

Kashmir

Uttar Pradesh

1) 220 KV Samba(PG)-Chowadhi (JK) (PDD JK) Ckt

2) 220 KV Chowadhi (JK)-Gladni(PDD) (PDD JK) Ckt

1) 220kV Bus-1 at Agra(PG)

2) 220 KV Agra(PG)-Bharatpur(RS) (PG) Ckt

4) 220 KV Agra(PG)-Shamshabad(UP) (UP) Ckt

3) 220 KV Agra(PG)-Tundla(UP) (UP) Ckt

5) 220 KV Agra(PG)-Kirawali(UP) (PG) Ckt

GD-1

ii)As reported, at 19:44 hrs, 220 KV Samba(PG)-Chowadhi (JK) (PDD JK) Ckt tripped on permanent R-N phase fault (unsuccessful A/R) due to R-phase conductor snapped. As per DR at Samba end, fault current was 2.273kA (4.134kA during A/R) from Samba(PG) end; zone-1 distance protection (Main-II) operated at Samba(PG) end. Carrier sent from

iii)On the same fault, 220 KV Chowadhi (JK)-Gladni(PDD) (PDD JK) Ckt also tripped from Chowadhi(JK) end only. As per DR, zone-4 distance protection operated at Chowadhi end (Main-II) and fault sensed in zone-3 at

iv)During investigation, it was observed that zone-4 delay at Chowadhi(JK) end of 220 KV Chowadhi (JK)-Gladni(PDD) (PDD JK) Ckt and zone-2 delay at Chowadhi(JK) end of 220 KV Samba(PG)-Chowadhi (JK) (PDD JK) Ckt

ii)During antecedent condition, 220kV Bus-2 at Agra(PG) was already under planned outage due to AMP work. Hence all 220kV elements were connected to 220kV Bus-1 at Agra(PG). 400/220kV 315 MVA ICT-1 & 2 at

iii) As reported, at 12:12 hrs, Bus bar protection operated at 220kV Bus-1 at Agra(PG) (exact reason of bus bar protection operation including fault details yet to be shared).

# Status of submission of FIR/DR/EL/Tripping Report on NR Tripping Portal

#### Time Period: 1st November 2025 - 30th November 2025

S. No.	Utility	Total No. of tripping		formation ot Received)	Disturbance Recorder (Not Received)	Disturbance Recorder (NA) as informed by utility	Disturbance Recorder (Not Received)	Event Logger (Not Received)	Event Logger (NA) as informed by utility	Event Logger (Not Received)	Tripping Report (Not Received)	Tripping Report (NA) as informed by utility	Tripping Report (Not Received)	Remark
			Value	%	Value		%	Value		%	Value		%	
1	AHEJ4L	1	1	100	1	0	100	1	0	100	1	0	100	DR, EL & Tripping report not submitted
2	AMP Energy Green Private Limited	1	0	0	0	0	0	0	0	0	0	0	0	Details received
3	ANTA-NT	2	1	50	2	0	100	2	0	100	1	0	50	
4	BAIRASUIL-NH	4	3	75	3	0	75	3	0	75	3	0	75	
5	ВВМВ	29	10	34	13	10	68	12	3	46	11	0	38	DR, EL & Tripping report not submitted
6	CHAMERA-I-NH	2	1	50	1	0	50	1	0	50	1	0	50	
7	CPCC1	25	5	20	6	5	30	9	5	45	11	0	44	
8	CPCC2	20	0	0	0	3	0	0	2	0	0	0	0	Details received
9	СРССЗ	16	5	31	5	0	31	6	0	38	5	0	31	
10	DADRI-NT	2	2	100	2	0	100	2	0	100	2	0	100	
11	DHAULIGANGA-NH	2	2	100	2	0	100	2	0	100	2	0	100	DR, EL & Tripping report not
12	INDIGRID	1	1	100	1	0	100	1	0	100	1	0	100	submitted
13	KHURJA STPP	1	1	100	1	0	100	1	0	100	1	0	100	
14	KISHENGANGA-NH	3	2	67	2	1	100	2	1	100	2	1	100	
15	NAPP	1	0	0	0	1	0	0	1	0	0	0	0	Details received
16	PARBATI-II-NH	2	2	100	2	0	100	2	0	100	2	0	100	DR, EL & Tripping report not submitted
17	RAMPUR	1	0	0	0	0	0	0	0	0	0	0	0	Details received
18	RAPPA	7	0	0	0	0	0	7	0	100	7	0	100	Details received
19	RAPPB	3	2	67	2	0	67	2	0	67	3	0	100	DR, EL & Tripping report not
20	RENEW SURYA JYOTI PRIVATE LIMITED(RSJPL)	5	2	40	2	0	40	2	0	40	2	0	40	submitted
21	SALAL-NH	2	0	0	0	0	0	0	0	0	0	0	0	Details received
22	SHREE CEMENT	2	0	0	2	0	100	2	0	100	2	0	100	

# Status of submission of FIR/DR/EL/Tripping Report on NR Tripping Portal

#### Time Period: 1st November 2025 - 30th November 2025

S. No.	Utility	Total No. of tripping		formation ot Received)	Disturbance Recorder (Not Received)	Disturbance Recorder (NA) as informed by utility	Disturbance Recorder (Not Received)		Event Logger (NA) as informed by utility	Event Logger (Not Received)	Tripping Report (Not Received)	Tripping Report (NA) as informed by utility	Tripping Report (Not Received)	Remark
			Value	%	Value		%	Value		%	Value		%	
23	SJVN GREEN ENERGY LIMITED	1	1	100	1	0	100	1	0	100	1	0	100	
24	SLDC-DV	10	0	0	7	1	78	6	2	75	6	0	60	
25	SLDC-HP	4	1	25	4	0	100	4	0	100	2	0	50	DR, EL & Tripping report not
26	SLDC-HR	17	5	29	5	3	36	5	3	36	5	1	31	submitted
27	SLDC-JK	9	5	56	5	4	100	5	4	100	5	4	100	
28	SLDC-PS	10	2	20	7	1	78	7	1	78	9	0	90	
29	SLDC-RS	52	0	0	5	3	0	5	2	10	5	0	10	
30	SLDC-UK	9	0	0	0	1	0	0	1	0	0	0	0	Details received
31	SLDC-UP	81	20	25	27	7	36	25	14	37	24	0	30	
32	STERLITE	3	3	100	3	0	100	3	0	100	3	0	1 100	DR, EL & Tripping report not submitted
33	TANDA-NT	1	1	100	1	0	100	1	0	100	1	0	100	
34	TEHRI	12	0	0	0	9	0	0	5	0	0	0	0	Details received
35	UNCHAHAR-NT	2	2	100	2	0	100	2	0	100	2	0		DR, EL & Tripping report not submitted
Total in NF	Region De IFGC provision under clause 37.2 (c), detailed tr	343	80	23	114	49	39	121	44	40	120	6	36	

As per the IEGC provision under clause 37.2 (c), detailed tripping report along with DR & EL has to be furnished within 24 hrs of the occurrence of the event

		Status o	f Mock 1	Test of S	SPS in NR d	uring 202	5-26	
Sr. No.	Scheme Name	Owner / Agency	Commission Year	Last Review	Mock testing conducted before 2025- 26	Tentative Schedule of SPS Mock testing to be conducted during 2025-26	Date of SPS Mock testing conducted during 2025-26	Remarks
1	SPS for WR-NR corridor - 765kV Agra- Gwalior D/C	POWERGRID			27-03-2025	conducted	10.10.2025	Communication issue at Bhiwadi(PG), Bamnauli(DTL), Kota, Debari, Chittorgarh, Ratangarh, Nunamajra, Safidon, Ajitwal, Dandhari-II, Ablowal.
2	SPS for contingency due to tripping of HVDC Mundra-Mahendergarh	ADANI				SPS Unhealthy		As reported by ADANI, work order has been placed and action plan also have been rceived. Tentative timeline for revival of SPS is by December 2025.
3	SPS for high capacity 400 kV Muzaffarpur- Gorakhpur D/C Inter-regional tie-line related contingency	POWERGRID				SPS Under Review		Not conducted in 2024-25 also.
4	SPS for 1500 MW HVDC Rihand-Dadri Bipole related contingency	POWERGRID			19-03-2025 and 20-03- 2025	conducted	19.11.2025	SPS command didn't receive at 220kV Muradnagar(UP), 220kV Merta(RS), 220kV Kota Sakatpura(RS), 220kV Dhanonda(HR) and Singrauli TPS(NTPC)
5	System Protection Scheme (SPS) for HVDC Balia-Bhiwadi Bipole	POWERGRID				SPS Under Review		Not conducted in 2024-25 also
	SPS for reliable evacuation of power from NJPS, Rampur, Sawra Kuddu, Baspa Sorang and Karcham Wangtoo HEP	SJVN/HPPTCL/JS W/POWERGRID/ SORANG			19-12-2024	Dec-25	04-09-2025 (Partial: Case-1, 3 & 5 conducted)	Case-6(i) & (ii) has been implemented (as confimed by Karcham(JSW) via mail dated 08.12.2025).  Communication card issue at Wangtoo(HP)
7	SPS for Reliable Evacuation of Ropar Generation	PSTCL				SPS Under Review		As per NRLDC study, evacuation network at Ropta TPS meets N-1-1 reliability criteria, the need for an SPS at Ropar appears redundant under the current network configuration.
8	SPS for Reliable Evacuation of Rosa Generation	UPPTCL			20-04-2024	conducted	12-04-2025	Mock test report received (Review to be done in view of commissioning of 400kV Rosa- Badaun D/C in April 2021.)
9	SPS for contingency due to tripping of evacuating lines from Narora Atomic Power Station	NAPS / UPPTCL				SPS Under Review		Not conducted in 2024-25 also. As reported by UPPTCL, no SPS system is in service at Narora S/s.
10	SPS for evacuation of Kawai TPS, Kalisindh TPS generation complex	RVPNL			14-03-2025 (Partial)	conducted	26-04-2025	As informed by RVPNL, automatic load shedding part of the SPS has been implemented and mock tested. Mock test report is yet to be received.
11	SPS for evacuation of Anpara Generation Complex	UPPTCL			08-10-2024 (unit-7) and 19-10-2024 (unit- 6)	conducted	21-07-2025	
12	SPS for evacuation of Lalitpur TPS Generation	UPPTCL			21-05-2024	conducted	09-04-2025	Mock test report received
13	SPS for Reliable Evacuation of Bara TPS Generation	UPPTCL			20-11-2024	conducted	23-05-2025	Mock test report received
14	SPS for Lahal Generation	HPPTCL			08-07-2020	SPS Under Review		As reported by HPPTCL, SPS at Lahal not required now.
15	SPS for Transformers at Ballabhgarh (PG) substation	POWERGRID				Schedule awaited		N-1 compliant (To be removed)
16	SPS for Transformers at Maharanibagh (PG) substation	POWERGRID				conducted	Apr-25	Mock test report received
17	SPS for Transformers at Mandola (PG) substation	POWERGRID				conducted	Apr-25	Mock test report received
18	SPS for Transformers at Bamnauli (DTL) Substation	DTL				Dec-25		N-1 compliant (To be removed)
19	SPS for Transformers at Moradabad (UPPTCL) Substation	Uttar Pradesh			20-04-2024	conducted	02-04-2025	Mock test report pending
20	SPS for Transformers at Muradnagar (UPPTCL) Substation	UPPTCL			27-03-2025	Mar-26		
21	SPS for Transformers at Muzaffarnagar(UPPTCL) Substation	UPPTCL			27-03-2025	Mar-26		N-1 compliant (To be removed)
22	SPS for Transformers at Greater Noida(UPPTCL) Substation	UPPTCL				SPS Unhealthy		N-1 compliant (To be removed)
23	SPS for Transformers at Agra (UPPTCL) Substation	UPPTCL			21-03-2025	Mar-26		
	SPS for Transformers at 400kV Sarojininagar (UPPTCL) Substation	UPPTCL			15-05-2024	conducted	23-07-2025	Mock test report received
25	SPS for Transformers at 220kV	UPPTCL			06-06-2024	conducted	23-07-2025	Mock test report received
26	Sarojininagar (UPPTCL) Substation  SPS for Transformers at 400kV Unnao	UPPTCL			19-05-2023	SPS made healthy	27.05.2025	Mock test report received
	(UPPTCL) Substation					on 27.05.2025		

27	SPS for Transformers at 400kV Sultanpur	UPPTCL		SPS made healthy		N-1 compliant (To be removed)
	(UPPTCL) Substation			on 05.05.2025 Revised SPS		1. 2 compliant (10 de 10 morea)
28	SPS for Transformers at 400kV Bareilly (UPPTCL) Substation	UPPTCL		approved in 234 OCC		SPS yet to be implemented
29	SPS for Transformers at 400kV Azamgarh (UPPTCL) Substation	UPPTCL	06-05-2024	conducted	19-04-2025	Mock test report received
30	SPS for Transformers at 400kV Mau (UPPTCL) Substation	UPPTCL	27-04-2024	conducted	21-04-2025	Mock test report received
31	SPS for Transformers at 400kV Gorakhpur (UPPTCL) Substation	UPPTCL	27-04-2024	conducted	21-04-2025	N-1 compliant (To be removed)
32	SPS for Transformers at 400kV Sarnath (UPPTCL) Substation	UPPTCL	23-05-2024	conducted	01-04-2025	Mock test report received
33	SPS for Transformer at 400kV Rajpura (PSTCL) Substation	PSTCL	31-01-2025	Jan-26		
34	SPS for Transformers at 400kV Mundka (DTL) Substation	DTL	03-02-2025	Dec-25		
35	SPS for Transformers at 400kV Deepalpur (JKTPL) Substation	HVPNL		conducted	08-05-2025	Mock test report pending
36	SPS for Transformers at 400kV Ajmer (RVPN) Substation	RVPNL	10-09-2024	conducted	20-08-2025	Mock test report received.
37	SPS for Transformers at 400kV Merta (RVPN) Substation	RVPNL	12-09-2024	conducted	09-09-2025	Mock test report received.
38	SPS for Transformers at 400kV Chittorgarh (RVPN) Substation	RVPNL	31-08-2024 and 05-09- 2024	conducted	11-09-2025 & 12- 09-2025	Mock test report received.
39	SPS for Transformers at 400kV Jodhpur (RVPN) Substation	RVPNL	24-09-2024	Dec-25		
40	SPS for Transformers at 400kV Bhadla (RVPN) Substation	RVPNL	27-09-2024	conducted	27-09-2025	
41	SPS for Transformers at 400kV Ratangarh (RVPN) Substation	RVPNL	20-09-2024	conducted	25-09-2025	
42	SPS for Transformers at 400kV Nehtaur(WUPPTCL) Substation	UPPTCL	11-01-2025	Dec-25		
	SPS for Transformers at Obra TPS	UPPTCL	20-05-2024	Schedule awaited		ICTs failed during fire incident
44	SPS for Transformers at 400KV Kashipur (PTCUL) substation	PTCUL	Septemeber 2024	conducted	05-10-2025	
45	SPS for Transformers at 400KV Fatehgarh Solar Park (AREPRL)	ADANI		conducted	19-04-2025	Mock test report received.
46	SPS to relive transmission congestion in RE complex (Bhadla2)	POWERGRID		conducted	26-08-2025	Mock test report pending
47	SPS for Transformers at 400kV Bikaner (RVPN) Substation	RVPNL	26-09-2024	conducted	13-09-2025 & 17- 09-2025	
48	SPS for Transformers at 400kV Bawana (DTL) Substation	DTL	04-01-2025	Dec-25		
49	SPS for Transformers at 400kV Bhilwara (RVPN) Substation	RVPNL	09-07-2024 and 10-07- 2024	conducted	19-09-2025 & 23- 09-2025	Mock test report received.
50	SPS for Transformers at 400kV Hindaun (RVPN) Substation	RVPNL	26-09-2024	conducted	11-09-2025	Mock test report received.
51	SPS for Transformers at 400kV Suratgarh (RVPN) Substation	RVPNL	20-10-2024	Dec-25		
52	SPS for Transformers at 400kV Babai(RS) Substation	RVPNL	20-10-2024	conducted	07-08-2025	Mock test report received.
53	SPS for Transformers at 400kV Allahabad(PG) Substation	UPPTCL	25.07.2024	Schedule awaited		
	SPS for Transformers at 400kV Jaunpur(UP) Substation	UPPTCL				Implemented on 08.10.2025
	SPS for Transformers at 765kV Jhatikara(PG) Substation (Bamnauli section)	POWERGRID		conducted	Jun-25	Mock test report received.
	SPS for Transformers at 765kV Jhatikara(PG) Substation (Mundka section)	TOWERGRID		conducted	Jun-25	TOOK COST TOPOTE TOCKING.
56	SPS for Transformers at 765kV Bhiwani(PG) Substation	POWERGRID		SPS implemented		Mock test report received.
57	SPS for Transformers at 400kV Panki (UPPTCL) Substation	UPPTCL		Approved in 234 OCC		Expected to be implemented by Dec- 25
58	SPS for Transformers at 400kV Agra(PG) Substation	POWERGRID/UP PTCL		Approved in 234 OCC		Expected to be implemented by Dec- 25

S.No.	Power Station	Sector	Ownership	Fuel Type	Black Start Source	Capacity of Black Start Source		Date of mock drill during	Remarks
			·				before FY 25-26	FY 25-26	
	Bhakra (L)	Central	BBMB	Hydro	DG Set		08-11-2024		
2	Bhakra (R)	Central	BBMB	Hydro	DG Set	500kVA	08-11-2024		
3	Pong	Central	BBMB	Hydro	DG Set	500kVA, 380kVA	09.11.2024		
4 5	Bairasuil Chamera HPS-I	Central	NHPC	Hydro	DG Set	2X1010 KVA	14-12-2024 12-12-2024		
	Chamera HPS-II	Central	NHPC	Hydro	DG Set	1X1010 KVA & 2x1000 KVA 2x1250 KVA			
7	Chamera HPS-III	Central Central	NHPC NHPC	Hydro Hydro	DG Set DG Set	2x1250 KVA 2x725 KVA	02-12-2022		e P P
8	Dhauliganga	Central	NHPC	Hydro	DG Set	2x725 KVA 2x625 KVA	04-12-2017 13-12-2024		Evacuating line was not available
9	Kishanganga	Central	NHPC	Hydro	DG Set	2x1010 KVA	09-11-2024		
10	Parbati-2	Central	NHPC	Hydro	DG Set	2x1010 KVA 2x1000 KVA	22-12-2020	26-05-2025	
11	Parbati-3	Central	NHPC	Hydro	DG Set	2x1000 KVA 2x1010 KVA	22-12-2020	17-05-2025	
12	Salal Stage-I	Central	NHPC	Hydro	DG Set	2X875 KVA	16-12-2024	17-03-2023	
13	Salal Stage-II	Central	NHPC	Hydro	DG Set	3X1020 KVA	16-12-2024		
14	Sewa-II	Central	NHPC	Hydro	DG Set	2x500 KVA	-	16-05-2025	
15	Tanakpur HPS	Central	NHPC	Hydro	DG Set	2X625 KVA & 1X312.5 KVA	19-12-2024	10 03 2023	
16	URI-I	Central	NHPC	Hydro	DG Set	2x1000 KVA	20-12-2016		
17	URI-II	Central	NHPC	Hydro	DG Set	2x1000 KVA 2x1010 KVA	20-12-2016		Readiness from J&K for availbility of load not received
18	Anta GPS	Central	NTPC	Gas	DG Set	2.968 MW	29-02-2024		
19	Auraiya GPS	Central	NTPC	Gas	DG Set	2900 kVA	Not conducted		Because of railway line connection
20	Dadri GPS	Central	NTPC	Gas	DG Set	2.4 MW	15-12-2023		because of failway line connection
21	Faridabad GPS	Central	NTPC	Gas	DG Set	3.3 MW / 4.125 MVA	25-11-2024		
22	Koldam HEP	Central	NTPC	Hydro	DG Set	2X1250 KVA	14-03-2024		
23	Nathpa-Jhakri	Central	SJVNL	Hydro	DG Set	2*750kVA	08-12-2024		
24	Rampur	Central	SJVNL	Hydro	DG Set	2*1010kVA	08-12-2024		
25	Tehri	Central	THDC	Hydro	DG Set	2*1000kVA	13-11-2024	11.11.2025	
26	Koteshwar	Central	THDC	Hydro	DG Set	2*1010kVA	27-11-2024		
27	AD Hydro	IPP	AD Hydro Power Ltd.	Hydro	DG Set	750 kVA	27-01-2023		
28	Malana-II	IPP	Everest Power Company Ltd.	Hydro	DG Set	725kVA	27-01-2023		
29	Budhil	IPP	Greenco	Hydro	DG Set	2*800kVA	Not conducted		
30	Alaknanda IPP	IPP	GVK (UP)	Hydro			Not conducted		Due to unavailability of load. Unit is at 400kV level.
31	I.P. Gas Turbine (IPGCL G.T.)	State	IPPGCL/Delhi Gencos	Gas	DG Set	500kVA	10-04-2024		
32	Vishnu Prayag IPP	IPP	Jaiprakash power Venture Ltd. (UP)	Hydro			Not conducted		Due to unavailability of load. Unit is at 400kV level.
33	Baghlihar-I	State	Jammu & Kashmir	Hydro			Not conducted		No update received from SLDC-J&K
34	Baghlihar-II	State	Jammu & Kashmir	Hydro			Not conducted		No update received from SLDC-J&K
35	Lower Jhelum	State	Jammu & Kashmir	Hydro			20-12-2016		No update received from SLDC-J&K
36	Upper Sindh	State	Jammu & Kashmir	Hydro			20-12-2016		No update received from SLDC-J&K
37	Karcham Wangtoo	IPP	JSW	Hydro	DG Set	2*1500kVA	29-12-2021		Scheduled in 2024-25, however couldn't performed due to SCADA upgradation work at Station.
38	Baspa	IPP	JSW	Hydro	DG Set	2*625kVA	29-12-2021		Scheduled in 2024-25, however couldn't performed due to SCADA upgradation work at Station.
39	Singoli Bhatwari	IPP	L&T	Hydro	DG set	2*500kVA	Not conducted		Due to non availability of load
40	Ranjit Sagar (Thein Dam)	State	Punjab	Hydro	DG Set	2*500kVA	07-05-2024	01.12.2025	
41	Ramgarh GPS	State	Rajasthan	Gas	DG Set	625kVA	-	11-05-2025	_
42	Mahi Bajaj Sagar I	State	Rajasthan	Hydro	DG Set	200kVA	20-03-2025		
43	Mahi Bajaj Sagar II	State	Rajasthan	Hydro	DG Set	2*200kVA	21-03-2025		
44	Rana Pratap Sagar(RPS)	State	Rajasthan	Hydro	DG Set	250kVA	16-01-2011		All 4 Units got submerged in 2019. Units were restored in phases. Last unit revived in March 2025. Remainig 3 units revived by 2022 however, AVR systme is not there. Mock testing of 4th unit may be performed during 2025-26.
	Rihand (H) or Pipri	State	Uttar Pradesh	Hydro	DG Set	2*320kVA	13-02-2025	02-06-2025	
46	Obra(H)	State	Uttar Pradesh	Hydro	DG Set	1*320kVA & 1*250kVA	16-02-2024	02-06-2025	
47	Khara HEP	State	Uttar Pradesh	Hydro			Not conducted		Due to unavailability of nearby load
48	Matatila	State	Uttar Pradesh	Hydro	DG Set	2*190kVA	Not conducted		· · ·
49	Khodri	State	Uttrakhand	Hydro	DG Set	2*500kVA	Not conducted		Due to issue in governing system(old units, R&M work is
50	Chibro	State	Uttrakhand	Hydro	DG Set	2*500kVA	Not conducted		proposed).